

3056138



~~5-79~~

746.7 H
Holt, Rosa Belle.
Rugs, oriental and
occidental, antique and
modern.

X

WHITE RIVER LIBRARY
Franklin-Johnson County
Public Library
Madison at Home Ave.
Franklin, IN 46131

WILDERMANN

R U G S

ORIENTAL AND OCCIDENTAL



RUGS

ORIENTAL AND OCCIDENTAL
ANTIQUE & MODERN

A Handbook for Ready Reference

BY

ROSA BELLE HOLT

New and Revised Edition

*With 33 full-page Illustrations, 12 in full color, and other
drawings in the text, and a Map of the Orient*



CHICAGO

A. C. McCLURG & CO.

1927

COPYRIGHT

A. C. McCLURG & Co.

1901-1908-1927

P R E F A C E

TO THE THIRD EDITION

I N submitting a third edition of my book, "Rugs Oriental and Occidental, Antique and Modern," to a friendly public, I have made a few additions with the purpose of increasing its value to students. A number of important volumes on rugs have been published since mine, a pioneer, was first printed. My motive in bringing out the book originally was to present certain facts that would enable novices to appreciate the beauty and interest attaching to the subject and to assist prospective buyers to judge the merits of any particular rugs they may desire to possess.

The demand for rare and beautiful floor coverings is increasing and the American people after years of constant travel and intercourse with other countries have grown rapidly in culture and the appreciation of Oriental textiles. Not only do we desire the best examples but we are able and willing to pay adequate prices for them. Consequently by degrees we are acquiring the masterpieces of rug weaving.

ROSA BELLE HOLT.

NEW YORK CITY,
July 20, 1927.



CONTENTS

	PAGE
I. HISTORY AND DETAILS OF RUG-WEAVING	
The History	15
The Loom and Its Work	22
The Weavers	26
The Materials	30
The Quality	32
The Knotting	34
Designs	37
The Dyes	44
Oriental Colors	47
II. RUG-WEAVING IN EGYPT, PERSIA, AND TURKEY	
Rug-Weaving in Egypt	51
Persian Rugs	53
Characteristics of Certain Persian Rugs	58
Turkish Rugs	71
Characteristics of Certain Turkish Rugs	74
III. RUG-WEAVING IN INDIA, AFGHANISTAN, BELUCHIS- TAN, CENTRAL ASIA, AND THE CAUCASUS REGION	
Indian Rugs	87
Characteristics of Certain Indian Rugs	90
Afghanistan Rugs	95
Beluchistan Rugs	97
Turkoman Rugs	98
Characteristics of Certain Turkoman Rugs . . .	100
Caucasian Rugs	105

CONTENTS

	PAGE
IV. MISCELLANEOUS ORIENTAL RUGS	
Rugs of the Holy Land	111
Chinese Rugs	113
Japanese Rugs	116
Khilim Rugs	117
Polish Rugs	119
Prayer Rugs	120
Silk Rugs	123
Felt Rugs	126
Hunting Rugs	128
V. RUG-WEAVING IN EUROPE AND THE UNITED STATES	
Rug-Weaving in Europe and the United States	131
Greek Rugs	132
Moorish and Spanish Rugs	134
Bosnian, Servian, Roumanian, and Bulgarian Rugs	136
English Rugs	138
French Rugs	141
Rugs of the United States	143
VI. MISCELLANEOUS INFORMATION	
Inscriptions on Rugs	153
Concerning Oriental Symbols	156
Chinese Symbols	157
Egyptian Symbols	158
Indian Symbols	159
Japanese Symbols	160
Persian Symbols	160
Turkish Symbols	160
Miscellaneous Symbols	161
Meanings of Some of the Place-Names Associated with Rugs	162

CONTENTS

	PAGE
GEOGRAPHICAL DATA	164
Localities Arranged Geographically	165
Localities Arranged Alphabetically	170
LIST OF AUTHORITIES	175
SUPPLEMENT	179
INDEX	189

LIST OF PLATES

	PAGE
Antique Tabriz Silk Rug	<i>Frontispiece</i>
Oriental Rugs Decorating a Balcony	20
Turkish Loom and Weavers	24
Vats for Washing and Dyeing Wool — Turkey	28
Soumak Rug	30
Indian Rug Designers	32
Sinna Rug	34
Rugs being Transported	38
Wool Drying after Dyeing	44
Antique Persian Rug	54
Khorassan Rug	56
Bijar (Sarakhs) Rug	58
Camel's Hair Rug from Hamadan	60
Feraghan Rug	62
Shiraz Rug	68
Arabian Rug	70
Old Ghiordes Prayer Rug	74
Indian Prayer Rug	78
Indian Loom and Weavers	82
Afghanistan Rug	95
Tekké-Turkoman or "Bokhara" Rug	98
Samarkand Rug	102
Daghestan Rug	106
Kazak Rug	108
Antique Chinese Wool Rug	114
Khilim Rug	117
Old Kirman Prayer Rug	120

LIST OF PLATES

	PAGE
Old Anatolian Prayer Rug	122
Persian Silk Rug	124
Derbent Rug	126
Early English Rug	138
Navajo Rug	146
Antique Persian Rug	156
Map of the Orient	164

DRAWINGS IN THE TEXT

A Loom	25
Persian or Sinna Knotting	35
Turkish or Ghiordes Knotting	35
Soumak Weave	35
Five Forms of the Palmette	39, 40
Herati Border	40
Central Design	41
Running Hook Design	41
Pomegranate	41
Palm Leaves	41
Cloud Bands	41
Lozenge	41
Wave-like Designs	42
Rosette	42
Reciprocal Trefoil	42
Central Design	42
Four Characteristic Caucasian Designs	42
Fylfot, or Swastika	42
Guli Hinnai	43
Lotus	43
Medallion	43

R U G S

I

HISTORY AND DETAILS OF
RUG-WEAVING

*Fair warp and fitting woof
Weave a web that bideth proof.*

MOTTO OF THE CANTERBURY WEAVERS.

RUGS

ORIENTAL AND OCCIDENTAL ANTIQUE AND MODERN

I

THE HISTORY AND DETAILS OF RUG-WEAVING

THE HISTORY

RUGS, in the house beautiful, impart richness and represent refinement. Their manufacture was one of the earliest incentives for the blending of colors in such harmony as to please the eye and satisfy the mind ; consequently, it is one of the most important of the industrial arts. Since the days when ancient peoples first lay down to sleep wrapped in the skins of animals, the human intelligence has quickened, and as the race has become more civilized, rugs have gradually taken the place of skins. Thus began the industry of rug-weaving, and it has grown to such an extent that it is now of world-wide importance.

The word *Rug* is used in this volume in the following sense: "A covering for the floor ; a mat, usually oblong or square, and woven in one piece. Rugs, especially

RUGS: ORIENTAL AND OCCIDENTAL

those of Oriental make, often show rich designs and elaborate workmanship, and are hence sometimes used for hangings." In several books rugs and carpets are referred to as identical. In fact most written information on rugs has been catalogued under the term *carpets*; and there seems to be good reason for assuming that the terms *tapestries* and *carpets*, as used in ancient times, were synonymous with the word *rugs* of the present day, for these were spread loosely on the floor without the aid of fastenings.

Historical references to spinning and to the weaving of tapestries date back to a very early period. An ancient Jewish legend states that Naamah, daughter of Lamech and sister of Tubal-Cain, was the inventor of the spinning of wool and of the weaving of thread into cloth.

On at least two of the wonderful rock-cut tombs at Beni-Hassan, in Egypt, — 2800–2600 B.C., — there are pictures of weavers at work. In one, women are filling a distaff with cotton, twisting it with a spindle into thread, and weaving this on an upright loom. Beside them is a man, evidently an overseer, watching the weavers and their work. The other wall-painting represents a man weaving a checkered rug on a horizontal loom. Other monuments of ancient Egypt and of Mesopotamia bear witness that the manufacture of rugs dates a considerable time prior to 2400 B.C.

HISTORY OF RUG-WEAVING

At Thebes a fresco, dating 1700–1000 B.C., represents three men weaving at an upright loom. A small rug, discovered in that city some time between the years 666 and 358 B. C., and now in the possession of Mr. Hay in England, is described by Sir J. Gardner Wilkinson as follows: “This rug is eleven inches long by nine broad. It is made like many carpets of the present day, with woollen threads on linen string. In the centre is the figure of a boy in white, with a goose above it, the hieroglyphic of ‘child’ upon a green ground, around which is a border composed of red, white, and blue lines. The remainder is yellow, with four white figures above and below, and one at each side, with blue outlines and red ornaments; and the outer border is made up of red, white, and blue lines, with a fancy device projecting from it, with a triangular summit, which extends entirely round the edge of the rug. Its date is uncertain, but from the child, the combination of the colors, and ornamental border, I am inclined to think it really Egyptian, not of the Pharaonic, but of the Greek and Roman period.” Dr. Samuel Birch, who edited the last edition of Wilkinson’s work, affirms that this is so.

On the marbles of Nineveh is represented the pectoral worn by Sardanapalus. It is an exact miniature of a Kurdish rug of modern times. The Tree of Life, the motif of most of the Persian rug designs,

RUGS: ORIENTAL AND OCCIDENTAL

is in the centre, and the border is ornamented with rosettes and bars.

Phœnician art is intermediate between Egyptian and Assyrian. The color most prized in the art of Phœnicia was the rare and beautiful purple (properly crimson) dye used exclusively for the garments of royalty. For centuries the process of making this dye was lost, and even at the time of its highest fame it was familiar only to the maritime Canaanites, who procured the color from an animal juice of the murex, a shellfish. The shellfish and the dye were known to the ancients as *conchylium*.

When Cleopatra, the famous Queen of Egypt, went to meet Cæsar for the first time, she knew that he would not allow her to enter his presence if recognized, and therefore she cleverly had herself carried into his palace wrapped in a rug of the finest texture. It may well be imagined that the unexpected disclosure of the charms of this subtle Egyptian shared largely in bringing the great Roman general into her toils.

Besides Biblical writers, Homer, Æschylus, Plautus, Metellus Scipio, Horace, Pliny, Lucan, Josephus, Arrian, and Athenæus all speak of rugs. To persons interested in rugs the search for these allusions is a most fascinating occupation.

✓ The Egyptians bestowed the greatest care and patience upon the rugs they wove, as upon all else of their

HISTORY OF RUG-WEAVING

handiwork. They spread them before the images of their gods, and also on the ground for their sacred cattle to lie upon. They loved Nature intensely; like true lovers, they seemed to have reached her very heart, and they symbolized her works in their artistic designs. Even to this day many Oriental rugs have symbolic signs borrowed from the works of Nature.

In design and color the rugs woven to-day in the Orient are similar to the Assyrian and Babylonian textile fabrics of 1000-607 B. C. (Fall of Nineveh) and 538 (Fall of Babylon). At that early period these were used for awnings and floor-coverings in the palaces of the Assyrian kings (Sargon, Sennacherib, Esarhaddon, and Sardanapalus). The designs on the stone slab from the palace of Koyunjik, Nineveh, and on the door-sill from the palace at Khorsabad, are probably copied from rugs.

✓✓ From Egypt and Chaldea the manufacture of rugs was carried into Assyria, and then into Asia Minor. Ancient Egypto-Chaldean designs are occasionally seen in modern rugs, but usually in a modified form. For a long time the industry of rug-weaving was supreme in the countries mentioned, but about 480 B. C. it arrived at a high degree of perfection in Greece. Later, the art was corrupted by the Byzantine (Lower Roman) influence. In the seventh and eighth centuries the Saracens came into power in the Persian Empire after the fall

RUGS: ORIENTAL AND OCCIDENTAL

of the Sassanian dynasty, and in the African and Syrian provinces. The Saracens believed that all labor tended to the glory of God; consequently, on their western campaigns they carried rug-manufacture into Sicily, Spain, France, and Italy; and thus it was introduced throughout Europe. It should be here noted that the name Saracen was given by the later Romans and Greeks to certain of the nomadic tribes on the Syrian borders of the Roman Empire. After the introduction of Mohammedanism the name was applied to the Arab followers of Mohammed.

From earliest times it has been the custom in the East to hang rugs over graves. About the vault of the mosque at Hebron where the patriarchs Abraham, Isaac, and Jacob are said to be buried, rugs are hung at the present day.

During times of grand *fêtes* in Europe, when house decoration is done with lavishness, people, to make their homes more attractive, drape with beautiful rugs the balconies, the loggias, and the front walls of buildings. The richness and color of these rugs blend harmoniously with flags and other emblems, producing an effect of great magnificence and splendor.

When we see the exquisite loom-work that has been wrought in the Orient, we sometimes wonder how the weavers have achieved such success, for they are destitute



HISTORY OF RUG-WEAVING

of what we call education, and they dwell amid the humblest surroundings. But Nature has been their instructor, and the rare shadings and varied designs of the rugs are excellent imitations of the forms and hues of the natural world. The weavers have intuitively grasped what is correct in color from the works of Nature surrounding them, and we reap the benefit in the rich specimens of their art which they export.

These patient toilers of the East delight in subdued colorings and artistic designs; and without a doubt many a story is woven in with the threads that go to form the fabric, many a song of joy, many a dirge of woe and despair. The number of Orientals engaged in the manufacture of rugs in the United States is increasing. It is now not an uncommon sight to see these weavers at work before the loom in the show windows of the rug-importing establishments of the larger cities.

The increasing use of polished hard wood and yellow pine floors and mosaic work, even in buildings of moderate cost, is displacing the use of cheap flooring, which could be covered satisfactorily only with carpets or matting. This has enormously increased the demand for rugs; and the selection of them affords a much wider range for the exercise of personal taste and discrimination in securing an article not only of greater artistic merit, but of greater durability.

RUGS: ORIENTAL AND OCCIDENTAL

THE LOOM AND ITS WORK

THE hand loom is Oriental, the power loom Occidental. The former adds much to the fame of the Orient. The exquisite fabrics it produces have made it world-renowned, and although it is simple in structure, its products show careful and finished labor. Hand looms in all Oriental countries are similar, and are to-day almost as imperfectly developed as when used by the ancient Egyptians. To weave their mats, the ancient Egyptians took the coarse fibre of the papyrus and, with the help of pegs, stretched it between two poles which were fastened in the ground. Two bars were placed in between these poles, the threads of the warp serving to keep them apart. The woof thread was passed through and pressed down tightly a number of times with a bent piece of wood.

The loom now generally used in the Orient is made by fastening two poles perpendicularly in the ground to a sufficient depth, leaving above ground as much of each pole as equals in length the desired rug. This framework supports two horizontal rollers, the warp threads being wound around the upper, while the ends are fastened to the lower; at this the weaving is begun,

HISTORY OF RUG-WEAVING

and on it the rug is rolled while in process of construction. To the warp threads of fine linen or cotton the weavers tie the tufts of worsted that form the pile. This worsted, which has been dyed previously, hangs over their heads in balls. When a row of knots is finished, it is pressed down to the underlying woof by a long and heavy comb with metal teeth. Then the tufts are clipped close with shears, to make the pile. In the finer rugs there are seldom more than two, or at the most three, threads between every two rows of knots, but in the coarser kinds there are more threads. In many districts every family possesses a loom, and it is generally small enough to be carried from place to place.

Sir George C. Birdwood has seen the web in the horizontal loom in Western India kept stretched by being wrapped, as worked, round the body of the weaver. In some instances the spinners make thread from the cotton wool by using the left hand as a distaff, and the right one as a spindle. In other cotton rugs which he has seen, the warp threads were placed horizontally, and the loom was without treadles and reed. The woof threads were thrown across by the weaver and brought together with a small hand comb. The same style of loom, arranged vertically, is that on which some of the richly figured cotton rugs from the Deccan are woven.

RUGS: ORIENTAL AND OCCIDENTAL

In some parts of Turkey there are European factories that have adopted some of the native methods; but as the majority of Turkish rugs are apt to be crooked, frames that weave them straight are now imported from Europe.


Mrs. Isabella Bird Bishop describes a tribe of people living at Biratori, on the Island of Yezo, Japan, and bearing the name of Ainos, whose women employ their time in weaving mats. Their loom is certainly a most primitive arrangement. A comb-like frame, through which the threads pass, rests on the ankles of the weaver. There is a heavy hook fastened in the ground or floor, and to this the threads at the far end of the web are sewed. A cord fastens the near end to the waist of the weaver, who by spinal rigidity supplies the necessary tension. As the work proceeds, she drags herself along nearer and nearer the hook. This is slow work, only about a foot being accomplished in a day; as in other countries, however, the women enjoy the neighborly chats that their work allows; and often two or more will bring to the house of a neighbor their simple apparatus, and, hanging the hooks to the roof or to a tree, will weave all day.

The power looms of modern civilization are chiefly to be found in the United States and Great Britain, Philadelphia being the principal American centre, and Kidderminster, Wilton, Worcester, Rochdale, Halifax, Dewsbury, and Durham, the English centres. Brussels



HISTORY OF RUG-WEAVING

and Scotland contain a number of such looms. In all Western countries schools of art furnish most of the designs, and have done much to improve taste. This can also be said of good colorists in their branch of this industry.



A LOOM

RUGS: ORIENTAL AND OCCIDENTAL

THE WEAVERS

RUG-WEAVING in the Orient is an industry that, until recent years, has been carried on almost exclusively by women and girls. From childhood to womanhood, and on to old age, these weavers are at work. Girls of six years of age help their mothers, until they become experienced by long practice. Even ladies of rank and wealth weave rugs of fine quality for their own homes. In some districts, besides weaving for the market, girls weave one or two rugs for their dowry; this purpose furnishes them with enough excitement to keep them interested in their work and ambitious to excel. Now that there is a greater demand for rugs, and not enough women to supply the demand, men and boys have come into the business, but generally only in places where there are large factories, and especially in the cities. This is noticeably the case in India, where boys from nine to fifteen years of age do much of the weaving.

There are two classes of weavers, the sedentary and the nomadic. The former weave in their houses during the Winter, and in their courtyards during the Summer. The nomads spend the Winter in mud villages, and in the Summer go to the mountains with their flocks and

HISTORY OF RUG-WEAVING

live in tents made of goat's hair. The manner of life of the sedentary weaver works havoc with her constitution even in her youth; and consequently one is not surprised at her frail appearance. In Summer she is oppressed with heat as she sits before the frame, and in Winter she is almost frozen, for she has to work in the open air in order to have sufficient light. Hers is not an easy life. It would be pleasant to believe that in her toil, which she carries on with wondrous patience and in the humblest surroundings, the conscientious weaver finds the same inward satisfaction that comes to the true artist elsewhere.

The duties of the male portion of the family are to tend the flocks, shear the sheep, separate the various qualities of the wool into bundles, dye it, and make the framework for the rug. With the extension of the industry, a class of workers has arisen whose sole task is to manipulate and dye the wool for use. The reason why men do not usually weave is that the occupation, besides not being a paying one, requires an amount of patience not within the power of men accustomed to work out of doors. Nor is it a remunerative occupation. The reader, who is perhaps also a prospective rug-buyer, may be interested in the following calculation of the amount of labor bestowed upon a given piece of the best type, the cost of the materials, and its value when

RUGS: ORIENTAL AND OCCIDENTAL

completed. A square foot of the best Persian rug is worth about ten dollars, and it takes a single weaver twenty-three days to complete this portion. This allows the weaver about forty-four cents per day for her wool and her labor; but as three-fourths of this amount goes to pay for the wool, only eleven cents per day is left for her labor. The wages of the producer of the inferior article are somewhat better. A square foot of an inferior rug is sold for about sixty cents, and the time required for weaving it is but two days, thus allowing the weaver thirty cents per day for her wool and labor. She uses inferior wool, washes but little of it, and pays only a nominal sum for a cheap dye. The framework of her loom costs comparatively little, as the rug it produces is from twenty to thirty times the size of the superior rug. Thus it appears that, in the long run, the inferior weaver is better paid than the one who fatigues her brain with her efforts to produce a rug of the best quality. On the other hand, the weaver of the superior fabric has advantages which the other has not. As a general rule, she weaves to order, and is paid for her work in advance. This prepayment is of great importance, considering the poverty of the weaver. The situation of the weaver of the inferior article differs in that she has to buy her wool, dye it, finish her rug, and then watch the market for buyers.



HISTORY OF RUG-WEAVING

The weavers live on the simplest fare ; bread, cheese, and a raw onion make an average meal. In some districts the weavers have to work in underground huts, for the air at the surface is so dry that the threads would lose all their elasticity out of doors. In these underground places the weavers produce enough moisture by keeping at hand utensils full of water.

Although the business is conducted with the manufacturer on a strictly commercial basis, it is very difficult to induce the weavers to keep their appointments and finish a rug at the time it is promised. In India, for example, the weavers are very superstitious ; and if a boy weaver be taken ill, the entire force on that loom will stop until he recover. If he die, the entire force of native weavers may be changed. This of course causes vexatious delay, not only of days, but often of weeks and months.

RUGS: ORIENTAL AND OCCIDENTAL

THE MATERIALS

THE materials used in the manufacture of rugs cover a wide range, and are indigenous to the place where the weavers are located. Sheep's wool, camel's hair, mohair from the Angora goat, hair from the yak and from the Thibetan goat, silk, cotton, linen, hemp, flax, and jute are all used. In the Spring the raw wool is generally taken to the nearest market, where it is cleaned, washed, and spun. The cleansing process is very necessary, as it affects in an important degree the quality of the material. The wool is usually washed in running water by the men, and then sorted and cleansed a second time.

Persia, Turkey, and India all produce wool, the two former countries in larger quantities than India, but some of the very finest wool comes from that part of India known as Kashmir. The celebrated Turfani wool comes from Chinese Thibet. It is very choice, and beautiful fabrics are woven from it.

The pashim is the soft downy wool growing next the body of the goat. In color it is white, dark gray, or drab; and of this many of the finest India rugs are woven. Large-tailed sheep are common in Kabul, Peshawar, and other districts; these furnish wool from which



HISTORY OF RUG-WEAVING

many a rug is woven. | It is possible that the very sheep watched over by the shepherds of Judea the night of our Saviour's birth were reared partly for their wool, with a view to rug-weaving.

The camel is useful not only as a beast of burden; its hair is woven into fabrics both fine and durable, chief of which are rugs, beautiful, much desired, and costly; the younger the animal the more is its hair esteemed. The natural colors harmonize readily with the furnishings in most rooms, and the soft texture of the best ones is attractive.

— The process of carding is accomplished by means of a block with vertical pins in even rows close together. The wool is drawn through these many times, and then spun into yarn.

RUGS: ORIENTAL AND OCCIDENTAL

THE QUALITY

THE fineness of a rug depends largely upon the quality of the wool and the number of knots to the square foot. In one yard of the best made Persian rugs there are between twenty thousand and thirty thousand stitches made by hand. The wool must be of fine quality, but not too soft. It should be closely woven, and evenly cropped. A great deal depends upon the manipulation of the wool in the rough, and careful attention should be given to this particular.

The quality of the wool is affected by whatever circumstances affect the well-being of the sheep, and in a marked degree by climate. Hence there is a decided difference in the wools of various districts and sections of a country. It is a well-known fact that the wool produced in cold countries is soft and fine, while that of the warmer climates is, on the other hand, harder, firmer, and more lasting. Hard wool is easier for the weaver to handle, and the tufts can be cropped with more facility. It is partly owing to these facts that the rugs of the cold districts are most in demand.

The fact that some rugs are so much better than others is a natural result of the superior skill of the



HISTORY OF RUG-WEAVING

makers. Weavers are like other workers, some doing perfect work, some indifferent, and others very poor. But the quality of the rugs offered for sale in this country depends also upon the knowledge and the conscience of the wholesale buyer at the place of manufacture. When the buyer for an importing establishment brings over quantities of rugs not all of which are artistic, the question may be asked: "Why do you not always select rugs that are beautiful?" He may reply that it is his business to get those that will sell, and that as there is a great variety of taste among his customers he must try to please every one; or he may say that he buys a thousand rugs at a time, and does not see them individually. It is in the retail shop that the final purchaser may pick and choose.

The most famous rugs of the Orient have been selected with great care by men who have special knowledge of the subject, and they are owned by museums and connoisseurs. Some have been brought to this country by distinguished soldiers and statesmen, to whom they have been presented by potentates as tokens of respect. Others have been obtained through the fortunes of war.

RUGS: ORIENTAL AND OCCIDENTAL

THE KNOTTING

EXCEPT in the Soumak and the Khilim, which have the flat stitch, there are only two kinds of knotting used in Oriental rugs. These knots are called the Persian or Sinna, and the Turkish or Ghiordes.

In the Persian manner of knotting there are more knots to the square inch than in the Turkish, and the result is a finer surface. Often the Persian knotting is so fine that the surface of the fabric is like velvet. The Persian knot is tied in such a manner that one end of the pile yarn extends from every spacing that separates the warp threads. It is made in such a way that a noose is formed, which tightens as the yarn is pulled. Occasionally it is turned in the opposite direction, and executed from left to right. In this case two threads of yarn are employed, this of course making the pile twice as thick as in the other.

The Turkish or Ghiordes knot has the yarn twisted about the warp threads in such a manner that the two raised ends of the pile alternate with every two threads of the warp.

Experts have spent much time and invested much capital in the endeavor to make the rug industry as




HISTORY OF RUG-WEAVING


perfect as possible. Judging from the examples of India rugs I have seen,—some with a seven-by-six knot, others with a sixteen-by-sixteen knot,—I am convinced that the beauty, durability, and artistic effects produced by the efforts of the manufacturers will be appreciated more and more. From the fact that the best-known firms in the rug business in New York, Chicago, and other cities in the United States, and several leading firms in England, are sponsors for the present rug industry in India, it may naturally be inferred that it is prosecuted with skill and care.



PERSIAN OR
SINNA KNOTTING



TURKISH OR
GHIORDES KNOTTING



SOUMAK WEAVE

The different stitches made are as follows: seven by eight, or fifty-six hand-tied knots to the square inch; eight by eight, or sixty-four knots to the square inch; ten by ten, or one hundred knots to the square inch; twelve

RUGS: ORIENTAL AND OCCIDENTAL

by twelve, or one hundred and forty-four knots to the square inch ; and sixteen by sixteen, or two hundred and fifty-six knots to the square inch. These finer stitches are made in the very best examples produced by the finest Persian weavers. A specimen recently shown me was an exact reproduction of the rug owned by Prince Alexis Lobanow-Rostowsky, in which the stitch was the sixteen by sixteen. It was made in one of the factories in Kashmir.

The famous rug of Ardebil in the South Kensington Museum has three hundred and eighty hand-tied knots to the square inch, or thirty-three million in the whole fabric.

HISTORY OF RUG-WEAVING

DESIGNS

THE designs of Eastern rugs are often the spontaneous outcome of the fancy of the weaver. Sometimes they are handed down from one generation to another ; in some cases young girls are taught the design by an adult, who marks it in the sand ; at other times a drawing of the rug is made on paper, the instructor showing her pupils the arrangement of every thread and the color to be used. When all this has been done, the pupil must make the rug without looking at the drawing.

Persian rugs excel those of other countries in artistic design as well as in harmonious coloring. The Persians seem to have a natural intuition in the use and blending of different shades, and in the designs that contain these colors they achieve the happiest results. It is really wonderful what exquisite fabrics these people, born and reared in ignorance and poverty, produce.

The designs in Persian rugs are generally floral ; and in some districts, especially Fars, the women weavers invent the designs, varying them every two or three years. The Mohammedan religion does not allow any direct representation of animal forms ; consequently rugs woven under its influence take floral, geometric, and

RUGS: ORIENTAL AND OCCIDENTAL

vegetable forms. The Shiah sect of Moslems, however, numbering about fifteen millions,—of which eight millions are Persians,—do not regard representations of animals as unlawful. By the industry of this sect, and that of all who disregard the law of the Koran, animal forms are seen on some Persian rugs.

Among the good antique Persian rugs there are about thirty designs, all having different borders. Each design is the peculiar work of a family or tribe, and is produced continuously, from generation to generation without noticeable change, except in compliance with the demand of a buyer, or by a weaver who carries out some special fancy. Many buyers select the color, design, and size, leaving their orders with an importer or a manufacturer.

In the modern Oriental rug the designs are not to be entirely depended upon. They are apt to vary at the will of the weaver; and moreover, Occidental designs are now sent to the Orient to be woven into rugs by the native weavers of the Eastern country. The designs sent to India, to be reproduced by the different European and American firms having factories there, are almost universally strictly Oriental in character, being copies from fine old Persian pieces, or rearrangements of Oriental forms. When the design reaches India, it has to be re-drawn to the exact size of



HISTORY OF RUG-WEAVING

the rug that is to be made. From this is copied what is called a *talim*, which is the only direction the weavers have. This *talim*, or guide, shows the weavers exactly how many knots of a color are to be tied; and when these different colors are put together, the design is formed. These *talims* are carefully kept, and as they are records of the designs, can be reproduced at any time.

Large rugs show best in large and bold designs, for small and crowded designs would not be artistic. Small designs are, however, preferable on small rugs; a bold design on a small rug is inappropriate. The finer the border of a rug of whatever size, the more beautiful and costly the rug.

An average size for a large rug is six yards by four, and for this a bold vigorous design would be suitable.

Some designs found in rugs are here reproduced.

I. Five Forms of the Palmette.



a

a. With sharply marked outlines this palmette is a characteristic of the Djusha-ghan rugs.

b. This is a geometrical form of the palmette,

frequently met with in modern Caucasian rugs.



b

RUGS: ORIENTAL AND OCCIDENTAL



c. This form of the palmette has an oblong central nucleus, surrounded by wreaths of leaves. To the right and left lancet-shaped leaves nearly encircle the whole. This design is most frequently seen in old Persian rugs.

d. In some old Persian rugs this form of the palmette with its diagonal projections is seen. It tends toward the geometrical, although its centre contains a small floral spray.



e. This palmette, with its two flanking lancet-shaped leaves, is frequently seen in modern Feraghan and Kurdistan rugs.



II

II. The Herati Border, or some form of it, may often be seen in Herat, Feraghan, Khorassan, Kurdistan, and Sinna rugs.

HISTORY OF RUG-WEAVING

III. The central design is formed by eight valvular or four heart-shaped leaves. This form is often seen in Kirmanshah and Shiraz, and sometimes in Caucasian rugs.



III



IV

IV. The Running Hook design found in the Daghestan, Shirvan, and Soumak rugs.

V. Pomegranate. The fruit is often depicted on ancient Assyrian and Egyptian sculptures. It had a religious significance in connection with several Oriental cults and was early introduced into rug designs.



v



VI

VI. A palm leaf with regular contour, its centre containing a small floral design. This form of design is found in more or less detail in the rugs of Persia and India.



VII

VII. A palm leaf formed by a floral branch and without distinct outline.

VIII. Cloud bands, seen in Chinese and old Ghiordees rugs.

IX. A lozenge surrounded by the Hook design.



VIII

This is found in rugs made by nomadic tribes of Asia.



IX


X. A continued wave-like design with rosettes attached. At intervals a deli-

RUGS: ORIENTAL AND OCCIDENTAL



cate tendril effect is interposed on either side of the wave-line.

XI. A continued wave-like design interrupted by a two-cleft figure.



XII. A rosette, the tips of its leaves bending backward. The rosette is often met with in old Khorassan, Herat, Feraghan, and other Persian rugs.

XIII. Reciprocal trefoil, or spade design. Found as a border design in many of the Caucasian and some Persian rugs, especially the Saraband.



XIV

XIV. The central design holds a rosette, to which are joined four blossoms resting in valvular calyces, the complete design forming a cross.



XV



XV. Four designs characteristic of the Caucasian rug.

XVI. The Fylfot is in the form of a Greek cross with each arm continuing at right angles. It is also known as the Swastika, and is the symbol of good fortune. It has been a favorite design in



XVI

HISTORY OF RUG-WEAVING

the rugs of Greece, and of the Orient, while it predominates in the Navajo rugs of the United States.



XVII. The Guli Hinnai is a decorative floral design found at its best in the old rugs of Feraghan. It is copied from the flowers which grow in small clusters on the henna-plant, from which it derives its name.

XVIII. The Lotus is the water lily of Egypt. In various forms it is found in antique rugs of Persia.



XVIII



XIX

XIX. The Medallion, in both floral and geometrical designs, is seen in many rugs of all rug-weaving countries.

There are many more designs which by careful investigation can be found. Among others the Arabesque, Chinese fret, Circle, Comb, various forms of the Cross, Mina Khani, Octagon, the S form, Scroll, Ser-rated leaves, Shah Abbas, the Star, — six or eight pointed, — the Tarantula, Triangle, the Y form, and the Zigzag.

RUGS: ORIENTAL AND OCCIDENTAL

THE DYES

WHEN doing their best work, Oriental weavers use the softest of permanent dyes. The result obtained is in every case a thing of beauty and utility. The aniline dyes are, of course, not to be compared to the vegetable, although the best of them are not to be utterly condemned. The poorest aniline dye eats into the rug, and the color fades.

Madder ranks high among those plants which yield a permanent dye. It belongs to the genus *Rubia*; the root employed is that of the *Rubia tinctorum*. This is largely cultivated in certain districts of India, but the best comes from near Smyrna, and from other parts of Asiatic Turkey. The plant grows wild throughout a large section of Central Asia and Russia. With both the European and the Indian madders the roots of the plants are the only parts that yield the dye. In the roots three coloring matters are obtained: alizarin and purpurin, which are both red, and xanthin, which is yellow. Cochineal was introduced for dyeing purposes in 1856. It is the product of an insect called *Coccus cacti*, which lives on a species of cactus. Yellow is often produced from Persian berries, turmeric, saffron, and sumac.



HISTORY OF RUG-WEAVING

Tyrian purple dye was greatly prized by the Phœnicians. As stated above, it was obtained from a shell-fish; but the secret was known only to the maritime Canaanites. The art of producing this dye has been lost, although some aver that in recent years it has been re-discovered.

Kermes, red in color, is one of the oldest of all dyes. It was known in Syria, 1200 B. C. It is not so brilliant as cochineal, but it is much more durable. Plutarch is authority for the statement that after one hundred and ninety years stuffs dyed with kermes retained their original color. The dye is the product of the bodies of females of the species of coccus which infest certain trees along the Mediterranean coasts. When the Romans conquered Spain, a part of the tribute demanded was paid with these little bodies.

Greens are obtained from various sources. The Chinese green is a dye obtained from *Rhamnus chlorophorus* and *Rhamnus utilis*, a genus of shrubs. The fruit of several buckthorns, or the Persian berries, as they are generally called by dyers, also give greens and brilliant yellows. Most of the greens, however, are produced by the combination of indigo with yellow.

Indigo, mentioned by Pliny as Indicum, yields the deep blue dye so much prized by the Romans. Arrian speaks of indigo, and says that it was exported from

RUGS: ORIENTAL AND OCCIDENTAL

Barbarike, on the indus, into Egypt. This plant is grown in India, China, North and South America, Mexico, Central America, Africa, Japan, Madagascar, and Jamaica. When the Indian indigo plant, *Indigofera tinctoria*, is in flower, it contains the largest quantity of coloring matter. The beautiful vegetable and animal dyes which were compounded with consummate skill are now largely supplanted by the chemical dyes which are easily obtained. But in years to come the commercialism of the present will probably give way to the restoration of the splendid dyeing of the past.

To-day, painting a rug is quite a common procedure. Thousands of painted rugs are sold annually in the United States and other countries. The oil paint which is used is put on with an instrument somewhat resembling a fountain pen. After a few washings, however, the rugs become pale and lose their color.

HISTORY OF RUG-WEAVING

ORIENTAL COLORS

AMONG Orientals a good deal of significance has attached, from the earliest days, to color. In Babylon scarlet was the symbol of fire, blue of air, and purple of water. Tyrian purple was an exquisite and rare shade of crimson. Many allusions are made to it by classical writers. The principal colors of the ancient Egyptians were red, yellow, and blue. Black was the symbol of error. White signified a holy life, purity, innocence of soul. The priests of Zeus and of Osiris were robed in white. Red was the symbol of zeal for the faith. Yellow was supposed to bring evil and sorrow. Blue was the symbol of truth. Black and white were often used to outline other colors.

The Persians, unlike most other Orientals, are not fond of bright colors. They are apt to avoid the light shades of red and green as being too showy, and further, as being liable to fade. Greens and yellows in dark shades they treat with more favor. They consider black and indigo as the symbols of sorrow; rose is the symbol of Divine Wisdom; green represents initiation into the knowledge of the Most High.

Among the Chinese, yellow is the symbol of royalty.

RUGS: ORIENTAL AND OCCIDENTAL

The Emperor of China and his sons may wear yellow robes; their descendants wear yellow sashes and have yellow bridles for their horses. Red is the symbol of truth, virtue, and sincerity. It is the color of the highest degree of official rank. White is the symbol of mourning; black represents vice and depravity.

In Turkey, green is the most sacred color; and for that reason a true follower of Mahomet will not permit it to be used in his rugs, for fear it may be profaned by being stepped upon. Thirty-five or forty years ago no Christian was allowed to wear even a vestige of green anywhere upon him, while in Turkey; but this law is not now so rigidly enforced. If the Prophet or any of his family wear this color, no objection is raised, as he and they are considered holy, and thus exempt from the penalty. White is the color permitted to a student or a teacher of the law. To the Mohammedans of India and Persia, as to the Chinese, white is the emblem of mourning. In India, orange signifies devotion or pious resignation, and blue means ill-luck to the Hindoo.

Red was the favorite color of the Gauls, purple of the Romans, and saffron of the Greeks.

II

RUG-WEAVING IN EGYPT, PERSIA, AND TURKEY

II

RUG-WEAVING IN EGYPT, PERSIA, AND TURKEY

RUG-WEAVING IN EGYPT

THE supply of skins having been found inadequate to the gratification of their desire for comfort, the ancient Egyptians gradually developed the art of making mats from papyrus, a plant as important to them as any of our trees, fibrous grasses, or hemp are to us. While at work on the manufacture of these mats, the weavers used to squat on the ground. They became skilful, both in constructing the fabric and arranging the colors; the latter were quite bright and effective, being chiefly red, blue, yellow, and green, with black and white to define.

Egyptians used rugs in the decoration of their rooms, hanging them on walls and also suspending them between the pillars. But as the glory of Egypt departed, her skill in rug-making also declined; and the Egyptian rugs of the present day are of a coarse quality, being made in private houses under the primitive conditions that existed thousands of years ago. The last manufactory in working order was at Boulak, a suburb of Cairo, but it has

RUGS: ORIENTAL AND OCCIDENTAL

been closed for several years. A great many rugs, however, are imported into Egypt, the majority being from Persia, Turkey, and India. Cairo is still one of the leading emporiums for the sale to tourists of rugs of Eastern make.

Dr. F. Sarre, the distinguished archaeologist, has proved quite recently by documentary evidence that the so-called Damascus rugs are really ancient Egyptian. This is a new and interesting fact to the student of ancient Oriental rugs. The distinctive greens and reds are added evidence of Egyptian ancestry.

RUG-WEAVING IN PERSIA

PERSIAN RUGS

IN Persia the art of rug-making has attained a very high degree of excellence, having been practised there during many centuries; indeed, the exact period when this industry was introduced into that country is not known. Tradition has it that long before the days of Alexander the Great, rugs were woven at Shuster, then the capital; and being a luxury, they were woven solely for kings' palaces, and on the finest gold warp.

The Persians having been an industrious and civilized people for many centuries, and a large proportion of them having been accustomed to the nomadic and pastoral life, it is a natural inference that love of gain and the demand from the growing towns for articles of beauty and luxury gave the wandering tribes the opportunity to utilize their wool by supplying the demand for rugs. Encouraged under the reign of Shah Abbas (1557-1628) the industry prospered. Various kings of Persia cultivated certain branches of art and industry, but Shah Abbas especially gave a decided impetus to rug-weaving. He had a particular fondness for the beautiful creations of this industrial art, and the rugs made during his reign bring fabulous prices. After his death

RUGS: ORIENTAL AND OCCIDENTAL

a reaction followed. Rugs fell into comparative disuse, and the manufacture deteriorated until about 1850, when, thanks to the demand in Europe, the industry revived. To-day it is in a flourishing condition and the most important source of Persia's income.

Persians, from the Shah to the peasant, sit upon rugs when eating, with cushions placed behind them. It is only the lowest beggar who has no rug. The rugs used by the Persians themselves are rather small, the larger ones being exported to foreign countries. Usually the rooms of Persian homes are small, and narrow in proportion to their length; consequently only small rugs are required. But even when the rooms are large, the Persians prefer several small rugs to one large rug, as a floor covering. They often first cover the hard-beaten ground with a matting of split reeds, and then lay over this so many small rugs that the matting cannot be seen. This custom is becoming more and more common in Persia. With their taste in design and color, they produce beautiful effects.

+ The finest rugs are closely woven, with a pile like velvet, and with stitches on the back that resemble needlework. A rug has scarcely reached its prime until it has been down ten years; and it should last for centuries, if carefully used. As a partial explanation of this wonderful durability, it should be remembered



RUG-WEAVING IN PERSIA

that in their own homes the Persians use their finest rugs for hangings, and also that they take off their shoes before entering the house.

In ancient days rug-weaving in Persia was generally restricted to Ispahan, Khorassan, and Shuster, but in modern times the most noted districts are those of Sultanabad, Fars, Hamadan, Feraghan, Bijar, Kurdistan, Khorassan, and Kirman. But the industry is so widely spread over Persia that there is not a class of women who do not live by it, and very often really fine pieces of work are produced in districts where the art receives no encouragement. The districts mentioned above are more noted for the quality of the rugs they produce than for anything else. The rug of each district has a peculiar character of its own, both as to the quality of the wool and the design. The peculiarities characterizing each district are so noticeable that an expert can generally tell at a glance where a rug was made.

It is very difficult, if not impossible, to discover the exact value of the export and import trade of Persia. The source of this information is naturally the Customs Administration, which in Persia exists but in name. The duties of the ports and principal towns are farmed out to various persons, whose interest it is to send the inquirer away as ignorant upon the subject as he was before the interview began. But it is possible,

RUGS: ORIENTAL AND OCCIDENTAL

after a great deal of labor in collecting statistics from the dealers of a particular article, to form an estimate probably not very far from the truth. By this method we judge that the average yearly export value of rugs in Aaragh (the Sultanabad district) is three hundred thousand dollars; Hamadan one hundred thousand; Bijar one hundred and ten thousand; Malair one hundred thousand dollars; Kurdistan fifty thousand; Fars seventy-five thousand; Kirman and Khorassan one hundred thousand; and in the less known districts collectively, fifty thousand dollars. The total of these figures classes the rug export in the very first order of exports. It is plain that this amount does not represent the full value of the manufacture, inasmuch as a great quantity of the goods does not leave the country. This quantity is perhaps small in comparison with that exported, but it is large enough to make the value nearly a million dollars.

It may be of interest to mention here that the export duty on rugs on the average is two and a half cents per square foot, and carriage to the seaports ten cents per square foot, while the import duty to the United States is fifty-five per cent of the wholesale market value abroad.

In Persia several firms have done a great deal in the way of encouraging the industry of rug-weaving in that



RUG-WEAVING IN PERSIA

country. To supply the demand for Persian rugs in Europe and America, these firms have erected buildings in Sultanabad, where they keep the weavers under control and steadily employed. These firms, having been long established, are conversant with the Persians and their character ; and to prevent any deception they pay the weavers by the piece instead of by the day.

The rugs produced by these firms are of the medium quality. The wool is bought in the rough and manipulated for use. Every day a quantity of it is given out to the laborers, who must reproduce the design placed before them, and each laborer is paid from two to four dollars per square yard, according to the quality of her work. In the service of these firms, the weaver is obliged to put aside her individual taste and follow closely the designs, which are prepared in accordance with the prevailing fashions abroad. The independent native weaver does not pay any attention to the taste of the buyer. She places her work in the local market, and the native merchant purchases it for exportation.

RUGS: ORIENTAL AND OCCIDENTAL

CHARACTERISTICS OF CERTAIN PERSIAN RUGS

Bakhshis rugs are made in a small village in the district of Azerbaijan, and in the neighborhood of Herez. Those of thirty years ago were excellent, but now the materials of which they are made are poor, the rugs badly woven and of indifferent coloring. They come in large sizes, usually having a medallion in the centre.

Bibikabad rugs are quite modern, and are supplied to the market at Hamadan. Aniline dyes prevail, and the rugs are of inferior design and texture.

Bijar rugs of olden time were artistic; of those of to-day this statement cannot be truthfully made. The wool is still fine and silky, but there is an element of crudeness of design and a defiance of the laws governing color. A pronounced medallion in the centre is usually seen. This is set in a solid field of a strong contrasting color. Sometimes the field is of a bright red or blue, with the medallion omitted. The borders are generally in the same color as the field, or in camel's hair, sometimes covered with crude figures of human beings or animals, or decorated with flowers in vivid red, yellow, or green. The rugs are heavy, and in the American markets are known as *Sarakhs*.



RUG-WEAVING IN PERSIA

Birjand rugs (so called) are woven almost exclusively in the village of Daraksh, about fifty miles northeast of Birjand. The weavers of these rugs came originally from Herat. The rugs are generally satisfactory, the weaving being fine, although the pile is often uneven.

Burujird rugs are made sixty miles from Sultanabad, and south of Hamadan. They resemble in their field and in the firm texture the Saraband rug, the palm-leaf design being arranged throughout the field. The border is mainly white, with minute variations of the palm design.

Djushaghan rugs are woven in a district south of Feraghan. They are durable and attractive. The Shah Abbas design is a favorite one in antique rugs of this kind. The field is generally of a rich red, and occasionally a rare sage green. Often there is a lighter shade in the border than in the field. Crosses with angular ends are a feature, and between these are floral designs.

Feraghan rugs of olden time are as satisfactory as any rugs handed down to us. They are so harmonious in coloring and design as to be most restful to the eye. They have a richness and sheen that make them most desirable, and when to the usual soft colors a deep violet is added the attractiveness increases. A distinguishing feature is the Herati design, covering a field usually of a

RUGS: ORIENTAL AND OCCIDENTAL

rich deep blue. Sometimes the Guli Hinnai design is observed, with its more elaborate treatment. The border is often a light ground covered with a design in the form of rosettes and palmettes connected by a running vine. The main border stripe is frequently in a rich green and sometimes of a deep rose. When there are corner areas and a centre medallion they are arranged so symmetrically that the harmony is complete. The colors in these areas and the medallion are often in cream, light green, or red. At the present time Feraghan exports annually a large number of rugs rather loosely woven, but soft and durable. These are made by the Bactrian tribes. The entire centre is often filled with rather small irregular figures on a dark blue field. Yellow is often employed in a modern Feraghan, both in the border and in the field. Quite an important feature of Feraghan and other places of high altitude is the rug-woven saddlebag. When stuffed, such bags make comfortable sofa-pillows, or they can be placed as seats on chairs. Throughout Asia, saddlebags are used for the transportation of household and personal effects and other goods, and by children for their schoolbooks.

Görevan rugs are woven in the neighborhood of Herez. They are exported in large sizes, and are generally rather showy and elaborate. Quite firm and



RUG-WEAVING IN PERSIA

durable, they are popular for dining-rooms. As they are in great demand in the trade, they are turned out too rapidly, but careful selection brings happy results, for sometimes a truly beautiful rug, with rich warm coloring and a medallion not too pronounced, is found.

Hamadan rugs are generally of camel's hair, although sometimes goat's hair is added. The field is in the natural shade, as is the surrounding border. An elongated medallion appears in the centre; this is ornamented with floral designs in red, blue, and yellow, as are also the corner areas. Antique Hamadans are very beautiful. Soft and silky, yet with firmness of texture, and in subdued coloring, they seem appropriate for any room. Some of them, with fine, delicate tracery, in soft shades, remind one of beautiful stained glass seen in the old cathedrals of Europe.

Herat rugs are now woven in Persia by tribes originally from Afghanistan. The old city of Herat was under Persian influence, which accounts for the fine character of its rugs. The modern Herat rug is of excellent quality and durable. The leading design is naturally the Herati, and again one sees the palm leaf with its apexes all pointing in the same direction. The field is generally a deep blue, although sometimes a rich red, and even ivory. Green is apt to be the main color

RUGS: ORIENTAL AND OCCIDENTAL

in the border, and occasionally the butterfly motif is noticed. Some of the modern rugs have medallion centres, in which the wool is generally red or blue, and sometimes green or yellow.

Herez rugs are attractive, the chief color often being a fine blue, upon which rests a pronounced medallion. The corners are defined by serrated lines, and are in shades of the red in autumn leaves. Often these corners are decorated with small designs. The main border stripe is light in color — often cream — with good-sized markings. *Herez* rugs are made in the province of Azerbaijan.

Iran is the official name for Persia, and when a rug is called by this name, the meaning is simply that it is a Persian rug.

Ispahan rugs are antiques. During the sixteenth century and the reign of the great Shah Abbas, and even earlier, these magnificent fabrics were woven. Superb in coloring, with beautiful designs and of superior workmanship, the examples still in existence are indeed precious. In these old rugs one finds a field of red that is rich and rare. It looks like carmine, and then again it seems as if one were looking into a goblet containing the choicest wine of past centuries. Once seen, the shade is not forgotten. So also with the wonderful moss-like green that occupies the main border and



RUG-WEAVING IN PERSIA

the running vines of the Ispahan rug. Black—the most corrosive of all dyes—although used, has disappeared, leaving only the foundation. A medallion, star-form in effect, often occupies the centre. Over the field are scattered palmettes and lotus forms, all connected by running vines. A wide middle border between two narrow stripes holds the rosette and palmette, and also the lancet leaf, in tiny form. When cloud bands are seen they show Chinese influence, as do the lotus forms.

Kara Dagh rugs are made by nomads who are called Aylauts, and who live in the mountainous region north of Tabriz. In appearance, as well as in texture and size, they resemble those produced in the Caucasian province of Karabagh on the other side of the boundary. The natural color of the camel's hair, and rose color too, are much used. Sometimes the camel's hair is mixed with goat's hair. The designs are floral and rather striking in effect.

Kermanshah rugs of modern make have usually a medallion with a lotus motif in the centre of the field. This is generally of ivory, ornamented in soft tones of blue, green, or rose. The usual light effect of the rug makes it rather more suitable for a reception room or a bedroom than for other places. There are, however, deeper tones in these rugs, and sometimes there

RUGS: ORIENTAL AND OCCIDENTAL

are no medallions. Perhaps the rug is most pleasing with the palm-leaf design and that of the tree, or with many birds and various floral conceptions. The borders blend harmoniously with the rest of the rug. The finest rugs of Kermanshah were formerly made in the palace of the Governor, and many were presented to leading rulers.

Khorassan rugs are woven in the province of that name and are characterized by various forms. A long palm effect or floral design is apt to be in the borders of antique Khorassans; and a prominent color in these rugs is magenta, which, though sometimes rather harsh in the modern rugs, is soft and beautiful in the antiques. Blue is also a leading color, and animals, including the lion and the gazelle; birds of several varieties; flowers symmetrically arranged, and geometrical forms, are all often seen. The Herati design is a usual one. When stripes occur in the field they are beautifully decorated with small floral designs or with the palm, and occasionally with that migratory insect, the locust. The rugs are unevenly clipped, which gives a soft, lustrous effect. Meshhed, the capital city of Khorassan, weaves rugs of fine colors; the palm leaf when represented on this rug is very large and impressive, often on a deep blue field. Animals and birds are frequently seen on the Meshhed rug.

Kirman rugs, made in the province of Irak-Ajemi,

RUG-WEAVING IN PERSIA

frequently have a medallion in the centre, entwined with flowers. Sometimes the Tree of Life is represented, its branches bearing different fruits, and often there are symbolical little birds in the border. Sometimes a vase of flowers is the principal ornament, or several small trees either with or without foliage. Silk has often been introduced into the old rugs with charming effect. The Kirman rug is one of the most easily recognizable. It is of very fine quality, and is highly decorative. Antique rugs of this kind have the finest of wool, and, with the artistic arrangement of beautiful flowers, cypress trees, and palm effects, are most pleasing. One of the finest in this country is reproduced in this volume with a description accompanying it.

Kurdistan (the Persian portion) is a large region inhabited by the nomadic tribes called Kurds; and the sheep and goats belonging to these tribes furnish the fine wool that is woven into Kurdish rugs. The color effects are generally good. Often dark blues and reds form the groundwork, in the centre of which is a lozenge or large diamond form ornamented with small designs of the palm leaf. Then, again, a repeated design is laid out over the field. Designs of the tree, palm, and rosette, and various floral forms appear. By examining the web at one end, a design in colored wool is generally found. In one of these rugs in my own

RUGS: ORIENTAL AND OCCIDENTAL

collection the centre contains twelve different symbolical designs, including the turtle, comb, star, and cross, while the corner areas and borders hold at least thirty-five others. All of them are so carefully woven that much thought must have been bestowed upon this very strong, splendid rug.

Laristan (see Niris) rugs.

Meshhed (see Khorassan) rugs.

Mir-Saraband (see Saraband) rugs.

Muskabad (see Sultanabad) rugs.

Niris rugs are made a little to the southeast of Shiraz, in the province of Laristan, and the latter name is that used in the Western markets. All around Lake Niris are pastured sheep with fine lustrous wool which is used in the manufacture of rugs. In the modern ones floral and geometric stripes often alternate through the field, or there is a medallion in the centre of a plain field, with corner areas. The border carries several designs. There is a checked effect in the webbing at the ends. The rugs are very strong and excellent for hard use. In the older ones blue was used in the field, with rather large forms of the palm leaf.

Oustri-Nan rugs have the palm-leaf design over the field, and a good deal of white in the borders. They are firm and durable.

Saraband (Serebend) rugs are woven in the district

RUG-WEAVING IN PERSIA

of Sarawan. They always have a distinct feature in the small palm leaves that fill the field. These leaves have the hook turned at the top from left to right in one row, and right to left in the next. Usually the field that these palm leaves adorn is soft red or rose in color. Again it may be deep blue, or occasionally ivory, in which case the palm design is in red or blue. The border is always harmonious, and there are many narrow stripes which form it. The widest one is generally in an ivory tone, while the undulating vine and small flower forms appear in some of the borders. Then, too, one finds the Caucasian influence in some of the borders, and the reciprocal trefoil is often seen. Occasionally a human figure is carefully outlined in the border, and this brings a personal element into the rug. Then again, the date is woven in. Mir is the name of the village in this district where the design had its source, and in the trade to-day the finest of these rugs is often called *Mir-Saraband*.

Sarakhs (see Bijar) rugs.

Saruk rugs are very closely woven in the hamlet bearing this name. The floral designs scattered over the field of rose, dark red, or blue show a spontaneity of workmanship that is not governed by Western enterprise, though, curiously enough, aniline dyes prevail. The wool is very fine. The border is composed of a wide middle stripe, with a narrow one on either side.

RUGS: ORIENTAL AND OCCIDENTAL

Savalan (see Sultanabad) rugs.

Serapi (see Sirab) rugs.

Shiraz, the capital city of Fars, has exported some of the most interesting and exquisite rugs in existence. In the sixteenth century Shiraz was at the height of its prosperity, and all the neighboring country was noted for its flocks of sheep, which produced the finest of wool. Rugs were made at Shiraz for the reigning Shahs, who had palaces there, and the workmanship displayed in them was most beautiful. The city was visited by an earthquake in 1853, and since that catastrophe the manufacture of rugs has not regained its former prosperity; yet great improvement has been shown in recent years, and the same vegetable dyes are still in use. The Shiraz is often called the Mecca rug, as it is the one frequently selected by pilgrims to that city. Deep rich blues are often seen in a Shiraz rug, and frequently stripes extend throughout the centre, as well as in the border, where diamond forms and crosses are also frequently seen. The medallion and the palm leaf are also found. Many Persian poets have sung of the wonderful rose gardens of Shiraz, and the rug weaver there has faithfully reproduced in glorious hues these beautiful flowers. Other flowers, too, decorate this rug. The webbing at the ends is embroidered in colored yarns.



RUG-WEAVING IN PERSIA

Sinna rugs are made in the province of Irak-Ajemi. They have a very fine texture, and are greatly prized by rug-lovers. The pile is of the best wool, and very closely cut. The Herati design, minutely woven, often occupies the entire field. Again, a lozenge-shaped figure is in the centre, and covered with the most delicate tracery. The field of the rug is often in white or ivory, or in soft blue, red, yellow, or even peach-blow tint. Yellow is used frequently in the border and corner areas. Often the finest of these rugs will be puckered near the edges; that is because the yarn is so tightly twisted in the weaving. Owing in part to this firm twisting and also to the fine, close knotting, there is much durability in the best specimens.

Sirab rugs are woven in the village of that name in the district of Azerbaijan. In Western markets the name has been corrupted, and the rugs are there called *Serapi*. These rugs come in large sizes, and are of excellent colors. A medallion of good proportions occupies the field, and about this floral designs are arranged. Sometimes inscriptions are seen in the rug.

Sultanabad is one of the most important of the modern rug-producing regions of Western Asia. Factories are kept busy supplying the market, and in many cases excellent rugs are manufactured. This is especially true when old patterns are used, for no modern ones sent

RUGS: ORIENTAL AND OCCIDENTAL

out by Western firms can be deemed worthy to take the place of original Oriental designs. Large quantities of rugs from this district are exported to the United States, and are then frequently called *Savalans*. The groundwork is generally light in color, and the designs are many, while the variety of brilliant hues is perhaps the largest in Persia. *Muskabad* is a trade name for a certain grade of rug from this district.

Tabriz rugs are now supplied in large bales to the trade from factories that are under Western jurisdiction. They are of well selected yarn, closely woven, and very durable. The weaving is faultless. The centre medallion is in a rich color, set in a field of ivory or other solid color, and decorated with floral forms. The sharply defined corner areas and the borders also contain floral designs in attractive colors. Sometimes cartouches with lines from a Persian poet or birds and animal forms are seen in the borders.

Rezd, where the fire-worshippers live, furnishes rugs with a short pile, but these are used chiefly in mosques, and seldom leave Persia.

A fine Persian rug is valuable, even at the seat of manufacture. A small one, measuring three by four and a half feet, quite modern, but very fine and with splendid colors, has been sold at Teheran for eight hundred dollars.



RUG-WEAVING IN TURKEY

TURKISH RUGS

THE term Turkish Rugs includes all those rugs that are manufactured within the Turkish Empire, whether the manufacturers be Kurds or Circassians or Christians; the last of these names comprises the Armenians, the Greeks, and the Syrians. Turkish rugs are not so finely woven as Persian; they have a longer pile and looser texture. As they are usually very soft and thick, the foot when walking upon them feels as if it were treading upon a bed of moss.

The principal rug-manufacturing district of Turkey is Karajah Dag. Much weaving is done also at Cæsarea. The rugs found at Adana are generally from the latter region, while those sold at Urfa are either from the Kurdish territory or from Persia. In Constantinople are seen rugs from almost every part of Asia, but the greatest number are from within the Turkish territory of Transcaucasia.

Each rug-weaving district of Turkey seems to have a distinct and individual class of rugs; and this is not surprising, for there are a number of different tribes, each of which impresses its individuality upon the work. The surface configuration and the climate of a place

RUGS: ORIENTAL AND OCCIDENTAL

have much to do with the quality of the rugs manufactured within it. Naturally, in the rocky, mountainous regions the flocks consist of goats instead of sheep. The sheep would be injured among the steep, sharp crags, and much of their wool would be lost, as it would adhere to the rocks. The goats, however, being hardy, easily jump from crag to crag, sustaining no injury to their hair

The hair of the goat is woven into the mohair and so-called Smyrna rugs, and also into what is known as Paul's Tent Cloth. This last is woven quite differently from other rugs; it is the coarsest of all, and the women weave it on the ground. To make it firm enough to keep out every drop of rain requires laborious work with the fingers, but when the cloth is woven with care it is a most excellent shelter from the storm. A large Paul's Tent, such as a rich man owns, costs about four hundred dollars. It shelters the women of the household, as well as the cattle; and one part is partitioned off for a guest-room.

In Turkey the floor is always covered with matting, and the matting, in its turn, is so closely covered with rugs as to be quite concealed. In large cities rugs are used in the Summer for divan and couch covers; in the Winter the same rugs serve as beds.

Constantinople is the greatest rug market in the

RUG-WEAVING IN TURKEY

world. Every known nation is represented in that wonderful city, where the ancient industrial skill of Asia meets the steadily increasing demands of the West. Nothing can be more interesting to the rug-lover than to wander through the streets and byways, observing the different phases of his favorite industry. The Custom House, where enormous bales of rugs await transportation; the great warehouses, which handle only at wholesale; the bazaars, and even the street vendors, possess each an absorbing interest. The travelling merchants from Persia, who yearly journey to Constantinople, establish themselves in that busy section of the city known as Stamboul. Here they erect their khans, covering the walls and floors with rugs, many of which are really splendid in tone and quality. The large retail houses at Constantinople usually have collections of very choice rugs.

The Turkish Ministry of Commerce issued an order, effective June 1, 1926, that all rugs manufactured in Turkey and intended for export must have a small lead seal thereon, otherwise they will be prohibited from export. This is done to discourage imitations and also to prevent fraudulent transactions in the rug trade.

RUGS: ORIENTAL AND OCCIDENTAL

CHARACTERISTICS OF CERTAIN TURKISH RUGS

AKHISSAR rugs have a thick pile, and are loosely woven. Their colors are usually red and green. Rugs of mohair are made at Akhissar.

Anatolia, or Asia Minor, produces both rugs and mats of good quality. The Anatolian rug is large and very heavy. The Anatolian mats are made in large numbers, and are very thick and soft. They are used by the natives for pillows. Some are very beautiful; and although many are turned out with aniline dyes, many others are splendidly colored with vegetable dyes. The designs are many and varied.

Bergamo (ancient Pergamos) rugs have a long, silky pile, and are almost square. They are quite thick, and have geometrical figures in the centre, while the borders are floral in effect. The colors are rich, generally yellow, green, red, and blue. A red webbing at each end carries a blue or yellow embroidered stripe. Antique Bergamos are very beautiful.

Brusa (Broussa) had a fresh impetus in the rug industry a few years ago. Very fine and beautiful silk rugs are woven there now by Turkish women and girls. The Great Mosque and the Mosque of the Thunderbolt at Brusa both contain rare old rugs.



RUG-WEAVING IN TURKEY

Cæsarean rugs have a thicker pile than any of the rugs woven in Anatolia. They are garish in color and are stained with chemical dyes. Large numbers are turned out by the factories, but they in no way resemble the good rugs of former years, except in their durability.

Cassaba (see Sparta) rugs.

Demirdji rugs are a product of modern growth, unknown thirty-five years ago. To-day the town is a large manufacturing centre. The rugs bear strong Turkish elements. They are heavy and durable, and woven of excellent wool when of the first quality. There are, however, three different qualities. The weavers of these rugs have a small pattern which they reproduce in the large sizes.

Ghiordes rugs of antiquity are not in the market. Once in a decade it is possible such a rug changes hands, but this is either the result of lack of knowledge on the part of the owner, or because he is in pecuniary straits. The rug derives its name from the ancient town of Ghiordium, and its form is that of a prayer rug. The weavers were most painstaking, and used the finest of dyes and designs. The hanging mosque lamp, or a tree form, is suspended from the high point of the niche, and a column appears on either side of the field, extending to the spandrels. Above is a horizontal panel, and there is generally one below the field. In colors there

RUGS: ORIENTAL AND OCCIDENTAL

is a discriminating use of the old porcelain blue, rare green, red, yellow, ivory, and white. When white was chosen, the weavers often substituted cotton for wool, thinking it would keep its purity of tone longer. The field is generally in one of these solid colors. The borders are most interesting and beautiful. The main stripe is usually ornamented with well-defined designs of small flowers and leaves, arranged with a square effect. The other borders are generally floral, while the zigzag water motif encloses the field. The apex of the mihrab or niche runs high in the Ghiordes rug. A silk fringe often finishes the top. One collector in Constantinople has many very fine and rare specimens. He began to collect Ghiordes rugs years ago, before the value of the rug became generally known. The modern rugs are very coarse, and have no resemblance to the old ones.

Hereke rugs receive their name from the village about forty miles from Constantinople, on the Gulf of Ismid, where the Sultan has established the imperial factories and a school of art. About four hundred young women, mostly Greeks, are here actively employed in weaving rugs in silk and wool. His Imperial Majesty is anxious to give employment to the village girls, and takes much interest in this industry, which was started about fifteen years ago. The rugs are reproductions, for the most part, of famous antiques belonging

RUG-WEAVING IN TURKEY

to the Sultan. In 1898 Emperor William of Germany visited this factory. After his return home the Sultan sent him a large number of Hereke rugs. In 1902, during one of my sojourns in Berlin, I was permitted by the courtesy extended to me by the court official in charge of these rugs to see the entire collection arranged in one section of the Palace. Beside the magnificent antique Persian rugs belonging to the Imperial House of Germany these modern Turkish rugs were startling in color; but the texture was fine, and time will, of course, subdue the glowing colors, which are now often softened in the Western markets by a washing process known to certain firms. Old mohair rugs are also being reproduced at the Hereke factory with good results. Great attention is paid in all these rugs to exactness of detail in reproduction.

Kara-Geuz rugs are mostly of the runner order, with mixed designs and fugitive colors.

Karaman has a considerable trade with Smyrna. Its rugs are coarse, loosely woven, and not at all attractive.

Kir-Shehr rugs are made in the province of Angora. Because of their durability and thickness they are both useful and desirable. Their colorings are rather strong, but fine; green is the most usual color, although red and blue are frequent. The designs are mostly of Arabic origin, and quite highly decorative.

RUGS: ORIENTAL AND OCCIDENTAL

Konieh rugs are of great weight and resemble Ouchaks. They usually have a plain centre, and when there are panels these are also of one shade. Being firm and strong they are very durable.

Kulah prayer rugs of ancient make are most interesting and valuable. They are about the size of the old Ghiordes prayer rug, and have other points in common, which might be expected from the proximity of the towns. The Kulah rug, however, instead of the solid centre of its neighbor, is apt to have its field ornamented with small floral designs. The colors most prominent are a yellowish-brown, a blue, or a soft red. Green and white are seen at times. There are many narrow stripes as borders, often alternating in dark and light colors, and these are beautifully ornamented with floral effects in minute designs. The niche of the prayer rug is of medium height, often with serrated sides.

Kurdistan (the Turkish portion) rugs are woven by the women in odd moments, and one of the ways a girl gains distinction among her associates is by the skill she displays in rug-weaving. As the wool is taken from the flocks that are kept near home, and is spun and dyed there, and as the time consumed in the weaving is not counted, each rug is considered clear gain. In fact, the Kurdish women do not make their rugs entirely for the market, but for their own entertainment and use.



RUG-WEAVING IN TURKEY

Kurdish rugs are very durable, and they are much prized in Turkey; but they do not sell readily in America because of the lack of that harmony of color which our taste demands. Their coloring is often too bright and varied to attract us. An Armenian clergyman said to me recently: "I find Americans more devoted to harmony than to anything else. I have in my house one of the finest of Kurdish rugs, but I could never sell it in this country, should I wish. An American looks at it and says, 'What hideous colors!' and I doubt if I could even give it away, although it would be considered a superior rug in Turkey."

Kutahia sends out Anatolian rugs of goat's hair and wool. Some improvement has been noticed in the rugs recently.

Ladik prayer rugs were made in the ancient city of Laodicea. They are among the finest rugs of old workmanship. The field is of a solid color, often a rich wine-red. The niche is serrated on the inside to the apex, which is enclosed by straight lines. On the outside of the niche one often sees the hook design, extending into the upper field, which in its turn is frequently ornamented with lancet-shaped leaves and floral forms. The Rhodian lily sometimes plays a part in the border design. White, red, blue, a light tan, and green, with an occasional touch of violet, are used.

RUGS: ORIENTAL AND OCCIDENTAL

The webbing is red, and extends about an inch and a half, when a narrow fringe finishes the ends.

Meles (Melhaz) rugs of modern make are of coarse texture, and brilliant in fugitive dyes of red, yellow, blue, and green. They find a market at Milassa. The modern prayer rug does not compare favorably in any way with the antique. The texture of the ancient rug is thin, but with a wealth of coloring and blending of hues, as beautiful as rare. Sometimes, too, the Ghiordes panel is seen above the niche. A good deal of black was used in the old rugs, but, as is usual in antiques, it has gradually disappeared with age. Violet, too, is a color that was sometimes used with great effect in old rugs.

Mobair rugs are made of the soft, silky hair of the Angora goat; but though beautiful, they are not durable, as experiments tried at Akhissar and Kulah have shown.

Mosul rugs are strong and rich in colorings of blue, yellow, green, and red. The designs are rather striking, and with their silky softness these rugs are generally desirable. The best are made of camel's hair, including the outer border, but occasionally they are made partly of goat's hair. They are now made in several Turkish provinces, and are often wrongly called Persian rugs.

RUG-WEAVING IN TURKEY

At *Ouchak*, with its large population, there are steadily at work about two thousand looms, giving employment to fully four thousand weavers, and as many as one hundred and fifty dyers. *Ouchak* is the principal city of Asiatic Turkey for the dyeing of the wool of which the rugs are woven, and that industry is carried on in many factories. *Ouchak* rugs have a thick pile; and though green is forbidden by Mohammedan law, the modern rugs frequently have green for their dominant color. The reason for this innovation is that the influence of their religious faith has waned, and consequently the law regarding that color is not now strictly enforced. The weavers of these rugs are mostly Moslem women and girls. The wool is generally bought in the interior from nomad tribes, and the weaving is carried on in private houses in a manner similar to that of other rugs, except that the yarn is spun more loosely. In the early history of rug-weaving these rugs were known in the Western market as the *Yapraks*, and the colors were, almost invariably, red with either green or blue. Until recently, even the best *Ouchak* rugs were apt to have inferior wool for their foundation, and hemp was frequently employed. The wool was loosely woven, and the dyes were fugitive. There are now, however, certain provinces in Turkey, including *Ouchak*, where the products are controlled by European and American firms,

RUGS: ORIENTAL AND OCCIDENTAL

and where excellent wool and natural dyes are used. The rugs made under such control are very durable and in every way satisfactory. In size Ouchaks vary greatly, ranging from a few feet to fifty by twenty-five feet.

Sivas rugs are always woven of wool, and almost every hamlet carries on the industry of weaving in the homes. There are no factories, the young girls and women doing the work here, as in other parts of Turkey. *Sivas* rugs are in most cases small, measuring about eight by four feet; but lately larger and more attractive rugs are being made. Even the poorest families have fine rugs, and regard them as valuable property, to be sold only under the pressure of great extremity. The weavers are so frugal in their manner of living that their daily earning of fourteen to nineteen cents is sufficient to supply their wants.

Smyrna, next to Constantinople, is the most important commercial centre in the East. It is the open door to mysterious Asia, and within its boundaries are found representatives of every race and religious belief of that little-known continent, the land of mystics, nomads, and fanatics. It is a mistake to imagine that the so-called *Smyrna* rugs are made in that city. As a matter of fact, no rugs are manufactured there. It is the export depot for goods from the interior, and dealers have allowed the name to be used merely for convenience, for commercial



RUG-WEAVING IN TURKEY

purposes. A student of rugs can readily understand that throughout the vast territory which concentrates its commerce in Smyrna there are a score or more of valuable manufactures which could never be known under one descriptive name.

Sparta rugs are made in a village bearing that name situated in the interior not far from Smyrna. They are very heavy, firm, and in different colors. Some of those recently made are especially fine. Attention is being paid to harmonious coloring as well as to quality and texture. A splendid specimen is in the home of the leading merchant of Smyrna. It is in the softest shades of rose and blue, with a lustrous sheen. The texture is as fine as velvet, and the medallion in the centre is most gracefully designed. Many rugs are sold under the name of *Cassaba*, which are really woven at Sparta.

Yaprak (see Ouchak) rugs.

Yuruk rugs are so called from a band of nomads who dwell among the mountains of Anatolia. They have large flocks of sheep, and weave rugs of strong, hardy texture. The colors are very good, the field often of brown, ornamented with large, bold designs.

III

RUG-WEAVING IN INDIA, AFGHANISTAN, BELUCHISTAN, CENTRAL ASIA, AND THE CAUCASUS REGION

III

RUG-WEAVING IN INDIA, AFGHANISTAN, BELUCHISTAN, CENTRAL ASIA, AND THE CAUCASUS REGION

INDIAN RUGS

THE manufacture of rugs was introduced into India by the Mohammedans at their first invasion in the beginning of the eleventh century. Persian rugs, however, were always preferred to those made in India, and princes and nobles of the Delhi Court, when it was in its greatest splendor, sought the fabrics woven in Herat, or by the Sharrokhhs on the Attrek, or the nomad tribes of Western Kurdistan. These were purchased only by the princes and their wealthy followers. A few specimens of these rugs still remain in India, and are now and then reproduced with more or less accuracy.

In the sixteenth century, however, the Emperor Akbar, or more properly Jalal-ud-Din Mahomed, sent for Persian weavers to make the exquisite fabrics for which Persia was then so famous. At first these weavers continued to weave according to the designs employed in their own land; but it is not surprising that as time went on, and the natives of India learned the art of

RUGS: ORIENTAL AND OCCIDENTAL

weaving from the Persians, Hindoo ideas should have found expression, in Southern India especially. Thus geometrical designs were substituted for floral, although even now the designs of some Indian rugs revive memories of Persian teachers in the careful arrangement of flowers and leaves. The designs of Indian rugs were frequently named after the original owners, in which cases the weavers generally lived and worked in the houses of their employers. At the present time the manufacture of many Indian rugs is carried on largely in jails, where the old Persian designs are generally used.

In Indian rugs, as in those of other countries, there are certain distinct characteristics that stamp them as coming from particular districts, and in India alone are to be detected the few Assyrian types still in existence. Genuine old India rugs are works of art, but they are rarely seen.

The religion of the Hindoo does not permit of his tasting the flesh of sheep; and as India is not a wool-producing country, except in the northern part, cotton is often substituted. For this reason, and because the time consumed for weaving is less, Indian rugs are generally less expensive than Persian.

Mr. Julian Ralph, in an interesting account of his visit to the home of a prince in India, published

RUG-WEAVING IN INDIA

in one of our magazines, writes of the splendid rugs shown him by his host: "They were state rugs, and one was green with a border of gold that must have weighed twenty pounds or more. The other was red with a similar border, so stiff and cumbrous that it did not seem made to walk upon. However, the prince sent for his stiff-soled heavy-heeled ceremonial shoes which were quite as richly crusted with gold, and walked about on the rugs, crushing the gold embroidery in a ruthless way." When Mr. Ralph spoke of the damage, he said, "It is of no consequence, these borders have to be renewed very frequently."

An Indian rug of great beauty was taken to England from India by Lord Clive, who ordered the architect of his magnificent palace — Claremont — then in process of building, to design a room especially for it. Such special care for the proper display of this work of art may be exceptional, but it shows true appreciative power on the part of Clive.

From the time of the decadence of the industry of weaving fine shawls, which was so long a feature of Kashmir, the wool of which they were woven was gradually transferred to the rug industry, and the weavers turned their attention from the shawls to the rugs, on which they displayed the same patience and skill.

RUGS: ORIENTAL AND OCCIDENTAL

CHARACTERISTICS OF CERTAIN INDIAN RUGS

Agra formerly sent out very satisfactory rugs which were of great weight and thickness. The finest specimen I have ever seen belonged to the late Mrs. Potter Palmer, of Chicago, and was a duplicate of one owned by Mrs. Frederick D. Grant. The rug is of enormous size and weight, and the tree design is arranged in shades of exquisite blue upon a field of delicate fawn color. The border, in the same coloring, gives the most perfect harmony to the entire rug. Many more Agra rugs would be imported, but there is now a United States law prohibiting the importation of goods made in jail.

Allahabad Rugs are similar to those of Agra, but the latter are as a rule preferable.

Amritsar gives employment to over twenty thousand men and boys, and supplies the market with some of the finest of modern Indian rugs. Leading English and American firms have factories located there, and for that reason rugs brought into the Occident from Amritsar are reliable. They are firm in texture and have fast colors. The manufacturers realize the importance of these attributes in a rug, and their own responsibility in the matter.

RUG-WEAVING IN INDIA

The *Dhurrie* (Durrie) is a strong, well-made rug of cotton, often in stripes of blue, brown, or gray, with narrow yellow and red lines. Some Dhurries end in a fringe, and are square. In India they are largely used by the foreign population, and in the United States they are especially appropriate for summer time. They are made chiefly at Agra, Cawnpur, Delhi, Lucknow, and in the vicinity of Bombay.

Ellore rugs belong to the inexpensive class, but the designs and colors are pleasing. As they are made chiefly of fibre mixed with wool, they are not durable.

Formerly *Haidarabad* sent out rugs famous for their beauty, with designs in the forms of medallions, filled with flat floral ornaments and woven with wool pile on a cotton foundation. But the modern Haidarabad by no means compares with the antique.

Faipur rugs are generally made in the schools of art. They contain many Persian designs representing animals and the cypress tree. The borders are floral, and the field is generally ivory, red, or blue.

Lahore, the British capital of the Punjab, has rugs woven in both wool and cotton, and the work is done mostly in jails. The designs are Persian, and the texture embraces from forty to one hundred knots to the square inch.

RUGS: ORIENTAL AND OCCIDENTAL

Madras rugs are chiefly made in large quantities for commercial and export purposes.

Masulipatam rugs were once noted for their beauty, but now many of them are poor in design and workmanship.

Mirzapur rugs are sometimes wrongly sold for Turkish, which they somewhat resemble. The antiques are very durable, but this cannot be said of all the modern ones, the vegetable fibre that is used in part in the construction of them not being durable. Few are exported to the United States. The colors are often black, orange, or grayish-white.

Moodj is the name given to a coarse, hardy mat, suitable for the veranda. It is made of buffalo grass, which grows six to twelve feet high in India. This is harvested, the fibre extracted by pounding, and then it is twisted into rope or yarn. Afterward it is dyed.

Multan rugs have large geometrical figures in octagons, medallions, and circles. These rugs are very lasting. Their general coloring is dark red and blue. Sometimes a really beautiful modern Multan is discovered. Occasionally an emerald green or a yellow alternates with the usual reds and blues, and again we see a white ground with blue designs. The modern ones are not largely imported into America. The antique Multan is very fine, but scarce.

RUG-WEAVING IN INDIA

Mysore rugs are cheap and not interesting.

Patna rugs are usually in blue and white; in quality they resemble the modern Multan.

Pushmina rugs have their name from the manufacturers, who thus designate rugs that are woven of pashim.

Sindh rugs are the cheapest and least durable of all Indian rugs, and on this account not many are imported into the Western market. The colors are green and orange.

Srinagar, the capital city of Kashmir, makes very beautiful rugs from the finest wool. This is soft and silky, and as natural dyes are employed, the Srinagar rugs, as well as many other rugs from the northern portion of India, are highly valued. Antique rugs of this character are attractive in soft tones of rose and yellow.

Warangul rugs. At Warangul, in the eastern part of the Deccan, modern rugs have been woven for the past sixty years. The designs are chiefly Persian, with a strong Indian influence. To show the beauty and delicacy of some of the old rugs, I may mention that one was made at Warangul, in the sixteenth century, which contained 3,500,000 knots on its entire surface, or 400 knots to the square inch, and the designs were so complicated that a change of needle was required for every knot.

RUGS: ORIENTAL AND OCCIDENTAL

Leading importers now give names to designate the different qualities of India rugs, and therefore the name borne by a rug does not necessarily indicate the district in which it was woven. For example the Dhurrie rug is woven in several districts of the northern provinces.



RUG-WEAVING IN INDIA

AFGHANISTAN RUGS

AFGHANISTAN RUGS are usually large, the average size being about eight by eleven feet. They are made by Turkomans inhabiting that part of Afghanistan known as Afghan-Turkestan and, therefore, the rugs are sold under the name of Afghan-Turkomans. They are handsome and durable but coarser in texture than those made by other subdivisions of the great Turkoman tribe. The predominant color is red, and the rugs are excellent for a small library or den because of their rich and glowing tones.

The accompanying color plate explains, in part, the Afghanistan rug. As a rule there are three octagons placed across the width and six or seven lengthwise, depending upon the size of the rug. In many rugs the star design may be noticed within the octagon, and in the field an eight-pointed star. The main border in the older rugs is made up of clearly defined diamonds containing crosses placed between narrower borders that hold a running vine. The outside, or guard border, is easily recognized by the saw-tooth design. The webbing extends some distance beyond the pile and has horizontal lines woven through it with space between in dark blue and brown. At the end

RUGS: ORIENTAL AND OCCIDENTAL

is a fringe and in the older and better rugs there is a knotting of the upper part of this fringe. Although the rugs are rather loosely woven and the pile is not closely cut, the knotting is very firm and the sides of the rugs have a selvage that is very strong, the heavy cords having the yarn wound about them several times.

Some rugs have a strong odor, which is especially noticeable in those of Afghanistan. The reason for the presence of the odor is that the animal's hair has not been properly cleansed. Nothing but a thorough washing on the back as well as on the surface, with soap and hot water, seems to be effective in dispensing with the odor, although certain atmospheric changes affect it. Fortunately this disturbing feature is not present in all Afghan rugs.

RUG-WEAVING IN INDIA

BELUCHISTAN RUGS

BELUCHISTAN rugs bear the marks of nomadic workmanship. They show that they are woven by tribes who combine strength and skill. The designs are generally geometric, and bold in effect. The rugs have rich dull tones of blue, red, and often with markings of white or ivory on a foundation of dark brown, in fact so dark sometimes as to give the appearance of black. This is accounted for partly by the great abundance of goat's hair and camel's hair woven into it, which is sometimes dyed even darker than the natural color. There is a fine lustre in this rug, and it is one of the hardest and most durable of all the Oriental rugs. The wool used is soft and the pile left rather long, which accounts in part for the rug being so thick and heavy. Occasionally we find a beautiful old prayer rug in brown tones, and with corner areas in fine dull reds and a wonderful deep rich blue.

Some of the finest specimens are occasionally sold as blue Bokharas; and people who imagine that they have purchased one of the latter are likely to find themselves the possessors of a good Beluch, for there is no such thing as a blue Bokhara.

RUGS: ORIENTAL AND OCCIDENTAL

CENTRAL ASIA

TURKOMAN RUGS

TURKOMAN rugs are woven by nomad tribes living in Central Asia. The tribes are known as the Ersari Goklan, Sarik, Tekké, and Yomud, and most of these rugs have some points in common, although they vary a good deal in detail. Generally speaking, the Turkoman takes the greatest care to have his work perfectly done. In order to give fixity to the color the dyer steeps the wool in a mordant of alum and water. The dye is almost invariably brought from Bokhara. At Ashkabad the Turkomans dye the wool themselves when it is intended to be yellow, but when any other shade is desired it is sent to the city to be dyed. Camel's hair is largely used in the rug-weaving of Central Asia. The camel itself is carefully washed, and the soft hair growing next its skin is used for fine rugs. The goats of this vast region also receive the same watchful attention as the camel; the soft, silky fleece is accounted precious, and is used for the finest Turkoman rugs. The natives use their rugs not only for the floors of their tents, but as *portières*, thereby dividing the



RUG-WEAVING IN CENTRAL ASIA

tent into sections. This is one of the reasons for the heavy fringe one so frequently sees on the ends. It permits of hanging, and is very strong, as is the case with the Turkoman rugs themselves, no matter how fine the texture.

RUGS: ORIENTAL AND OCCIDENTAL

CHARACTERISTICS OF CERTAIN TURKOMAN RUGS

BESHIR rugs resemble in certain aspects the rugs of Afghanistan. The texture is similar, and the same rich blues and reds are seen; a red webbing at the ends extends at some length, and has dark lines crossing it. The rug is longer than the Afghanistan. The field differs. There is an Arabic effect in the design, and yet with a reminder of the Yomud in the general aspect. But the hook, which plays so important a part in the Yomud, is missing.

Bokhara rugs which are made in the city and Khanate of that name, are not the so-called Bokhara rugs of the Western world. The genuine Bokhara rugs are of good size, with large patterns, and are very strong and forceful in character. They are sold in the Occident under the name of Khiva or Afghanistan.

Genghis (often called Guendje) rugs are woven by a tribe of Turkomans who live the life of nomads. They are named after Genghis Khan, the great Mogul conqueror who invaded Central Asia in the year 1218. The rugs are woven of brown wool, or strong goat's hair, and have rather a long pile. The designs are mostly geometric, although the palm leaf and vine are often seen.

RUG-WEAVING IN CENTRAL ASIA

Guendje (see Genghis) rugs.

Kashgar rugs are made in Eastern Turkestan. They are quite coarse, with designs of a Chinese character in strong coloring. Yellows and a sort of lead-white are much used in these rugs; again, blues and ivory-white are seen, while reds, pinks, greens, and a deep orange are common. The Chinese fret, the dragon, and fishes are among the designs employed. The Tree of Life is of frequent occurrence, but is a crude representation.

Khalatch rugs are woven by a division of the Ersari tribe of the upper Oxus, bearing the name Khalatch. They are included under the one greater head of Turkomans. The rugs are recognized by the single stripes of bands that divide the field both vertically and horizontally. These bands are ornamented with single motifs, and are generally considered to be the earliest decoration of woven fabrics. Besides the bands, stars, crosses, forms of the hook, and small prayer niches, — one at the top and one at the bottom, but each facing in the same direction, — are seen. Often a stark tree effect is noticed. In the trade these Turkoman rugs are commonly called Kchatchli (pronounced Hatchli — Bokhara).

Khiva rugs are woven by Turkomans inhabiting Central Asia. The firmness, durability, and bold grandeur of these rugs render them very pleasing. The field

RUGS: ORIENTAL AND OCCIDENTAL

is of one of the splendid reds so much favored by this great race. Arranged over the field are large forms of the lozenge. Frequently these large forms contain smaller lozenges, which are very decorative. Often a part of the larger lozenge forms are indented at both top and bottom. There is generally a stark tree form between the lozenges, in a peacock blue color. Much ivory is used throughout the field and border, in heavy lines of demarcation. These rugs are sold under the name of Afghan in the Western market. Well-toned shades of red, blue, tan, ivory, and an occasional green are the usual colors. Sometimes a Khiva has a long panel centre, with a prayer niche. In many fine specimens the lustre is an added attraction.

Samarkand rugs are a product of Central Asia. They show distinctly Chinese characteristics. Sometimes the field is covered with round medallions, from one to five in number, holding odd figures. The Chinese fret is common in the design, and sometimes a large crude flower arrangement is noticed. Reds, magenta, green, blues, a soft fawn, white, and much yellow, especially in the border, are the usual colors. Soft and rich, these rugs have a distinctive character, and are attractive. Their texture, however, is quite thin, and they are not very durable for the floor, but attractive on the wall or divan.



RUG-WEAVING IN CENTRAL ASIA

Tekké-Turkoman rugs are sold in the Occident under the name of Bokharas. The design has little variety, and generally the rugs are among the easiest to distinguish. The design is usually octagon, in white or ivory tones with blue and orange, and occasionally green, upon a field of rich deep red, or rose. Brown and black, with white, are also used in the lines of demarcation or in the border. Sometimes the smaller designs are very decorative. Occasionally in the past this tribe, which is considered the most savage of all the Turkomans, has woven a rug with a diamond figure in place of the octagon, but this is not typical. Also instead of the usual red field a wonderful mahogany shade is seen with a rare green in place of the usual blue of the octagon. In the borders one often finds the eight-pointed star. The Tekké tribe use their rugs as *portières*, for divan covers, and for floor coverings. Rich in coloring, fine, yet durable, these rugs are greatly prized.

Yarkand rugs are very similar to Kashgar rugs, having the same general characteristics.

Yomud rugs are woven by the tribe bearing that name, whose territory seems to include both Astrabad and Khiva. The rugs woven by this tribe are in rich tones of deep red or plum, sometimes mahogany in tone. The design most frequently seen is the diamond, surrounded by the hook. The weaving is very

RUGS: ORIENTAL AND OCCIDENTAL

satisfactory, and the coloring in brownish-reds is particularly good. In some odd and rare pieces among the Yomud Turkomans, blue figures conspicuously, as does green also. The border in these rugs is sometimes in stripes, sometimes in a sort of crudely drawn vine.

RUG-WEAVING IN CENTRAL ASIA

CAUCASIAN RUGS

CAUCASUS is a general government belonging to Russia, and including Transcaucasia. The designs of the many rugs woven in this section of country are all parts of a system, and each design bears certain marks whereby its class may be identified.

Daghestan rugs are made in fine wools, and the mosaic designs are generally beautifully and skilfully done. The figures are nearly always geometrical, and in the form of diamonds, long octagons, lozenges, hooks, and small crosses. The colors of the best Daghestans are so well selected, that although there is no shading there is seldom anything aggressive or startling in the effect. Blues, reds, yellows, ivory, and other hues are chiefly used. The rug has a short, close pile, and although the texture is rather thin, the rug is very durable.

Derbent rugs, though woven at Derbent, the chief city of the province of Daghestan, differ somewhat from the Daghestans proper, being much softer and thicker. They are also more loosely woven, and have a longer pile. The designs are geometrical, several star devices often occupying the field; and here again we see the hook, which is a feature of the entire

RUGS: ORIENTAL AND OCCIDENTAL

Daghestan province. There is a good lustre in the Derbent rugs, and the coloring is often quiet and inconspicuous in dark blue, red, yellow, and ivory. Sometimes a soft pink is noticed.

Kabistan (Cabistan) rugs are woven at Kuba. They resemble the Daghestans to such an extent that they are often sold under that name. They have, however, more variety of design, although, as in the Daghestans, the diamond is generally a prominent feature, and often three large and many small diamonds are seen. The texture is firm, and the pile cut very close. Soft reds, greens, a delicate fawn, and browns are the usual colors. The borders may be in stripes, or with crude animal or bird devices. The antique Kabistan is very beautiful. Its texture is like velvet. Often one, and sometimes two borders contain the small single pink which is a most decorative floral ornament. The reds, light greens, ivory, and plum colors are arranged artistically, and quaint animal forms are often seen.

Karabagh rugs have characteristics of the other Caucasian rugs, but are more crude in coloring. Red is the chief color used. The rugs are coarse and quite crude in effect. The old-time rugs were vastly superior in workmanship.

Kazak rugs are woven by a nomad tribe dwelling among the Caucasus Mountains. There is a certain



RUG-WEAVING IN CENTRAL ASIA

strength and vigor about the Kazak rugs that seem to be in harmony with the tribe that weaves them. The word Kazak is a corruption of Cossack; and the durability of these rugs, as well as a certain boldness of effect in their designs and colors, corresponds with the hardihood of the people who weave them. The rugs are thick and soft; their colors are blues, soft reds, and greens. Often the field is a deep rose or a green, sometimes with one or more geometrical figures and several medallions, or with the palm-leaf design in rather large size throughout. When the palm leaf is used, it is generally decorated with a smaller leaf of a different hue. Many varieties of small designs are also seen, including circles, diamonds, squares, and the tau cross, which is almost always present. Some of the antique Kazaks are very fine.

Shirvan rugs are attractive from their quiet, agreeable tints, and fine, even texture. They are made in large quantities, and readily sold. The best are of white wool, but the inferior ones may hold cotton or goat's hair. Often blues and whites are the colors employed, with markings of red or yellow. Sometimes there are stripes in the border, one wide stripe followed by a series of narrow ones. The hook is a frequent design, and may be found in the field, incasing some geometrical figure. Sometimes a conventionalized floral design is observed in the border.

RUGS: ORIENTAL AND OCCIDENTAL

Soumak rugs ought really to be called Shemakha, for that is the name of the town in the government of Baku from which they are exported. But the contraction of the word into Soumak is now universal. Erroneously too, these rugs are known as "Kashmir," for the sole reason that they are woven with a flat stitch and the loose ends left hanging at the back, just as they are in the old Kashmir shawls. The designs bear a resemblance to those of the Daghestans, and the hook is omnipresent. The best are durable, and sometimes a rarely beautiful Soumak is discovered, distinguished from the ordinary specimens by its soft hues and fine texture. One that I have in mind is of a rich blue field, with geometrical figures in terra cotta shades, and a rare bit of green in the way of ornamentation; the field of another is rose, and the geometrical forms are in deep blues, old blues, and ivory.

Tchechen (Chichi or Tzitzi) rugs are made by the Chichi nomads living among the mountains of Daghestan. The rugs have a strong resemblance to the Shirvans, and are often sold under that name. They are of about the same color and quality, but are wider. In the border there are frequently geometrical designs arranged between two or more stripes, and the tau cross is sometimes seen.



IV

MISCELLANEOUS ORIENTAL RUGS

IV

MISCELLANEOUS ORIENTAL RUGS

RUGS OF THE HOLY LAND

NO rugs of importance are woven in Palestine. In several villages a coarse cloth is made which is waterproof because of its firm texture. It is used for cloaks or abas, and these are worn by all the men of the land. In Bethlehem is made the coarse cloth which is used as tent covering. This is produced from the sombre hair of the Palestine goat.

All Syrian rugs are made of pure wool, a home product of an average quality. Looms operated by machinery are unknown. The rugs are made in a primitive fashion by the peasant women and girls, who work at the looms in their own homes when not engaged in field labor or domestic duties. They also do the washing, dyeing, and spinning of the wool. The introduction of rug-weaving into Syria took place about the beginning of the nineteenth century, when a number of families emigrated from Brusa to villages of Syria, where they taught their art. For many years excellent rugs were woven, Haidamur especially taking the lead

RUGS: ORIENTAL AND OCCIDENTAL

in superiority of quality, design, and durability. Unfortunately, the original designs and blending of colors introduced from Turkey have entirely disappeared, and only inferior rugs are now made throughout the country. The chief colors in the modern Haidamur rugs are red and black, or sometimes crimson and black, with black or dark brown figures at each end. At Damascus a few rugs are woven, but not of any great value or distinctive beauty.

MISCELLANEOUS ORIENTAL RUGS

CHINESE RUGS

THE Chinese rugs of antiquity are remarkable, and worthy of the closest inspection. Their texture, designs, and symbolism show the greatest patience and thought. Antique wool rugs woven in China are very scarce, and because of this, and for their historical interest as well as their uniqueness and attractiveness, they bring large prices. In fact, they are almost unprocurable. A large and very fine specimen of this kind of rug is in the home of the late Governor Ames of Boston. It measures nineteen by twenty-one feet. The colors are yellow and white, and these are arranged in odd designs over the entire rug. A member of the family owning it writes: "This rug is said to have originally been in the Emperor's Palace in China. As every emperor is obliged to have the palace newly furnished when he succeeds to the throne, owing to some superstition connected with the retaining of any of the former Emperor's possessions, everything is removed and destroyed. Fortunately this rug escaped destruction.") A fine example of an antique Chinese rug is represented in one of the illustrations of this book.

The modern Chinese rugs are vastly different from those of antiquity. There is, however, much of interest

RUGS: ORIENTAL AND OCCIDENTAL

attached to them. They are sought because of their antique designs, their harmonious coloring, and their durability. The monstrous and fantastic forms that distinguished the antique are not so frequently met with in the modern production. The predominating colors in a modern Chinese rug are yellow, blue, white, and fawn, and these are arranged very effectively. The designs are quaint and odd. A border distinctly separated from the field is almost invariably seen. A most important geometrical motif observed in Chinese rugs is the Meandrian, especially the continuous and that derived from the hooked cross. The hooked cross we find with rounded arms, generally in connection with a cloud band. The rosette from the vegetable motifs is very frequent, especially in borders; also the branch and the continuous creeper. Bats, butterflies, storks, and the goose are in many borders. The lion—symbol of a happy omen—is often represented in those rugs designed especially for wedding ceremonies.

In the northern part of China rugs are decorated with colored threads in crude imitation of figures; they are woven in sections, and then sewed together. Camel's hair of a coarse quality is used extensively by the Chinese for their rugs, and the laboring class use felts in their houses. These are cheap and durable, and are placed on the tiled floors so common in the colder parts of China.



MISCELLANEOUS ORIENTAL RUGS

The skins of the doe, deer, and fox are much used in China as rugs. These skins are sewed together in sections, according to various designs, and resemble mosaic work.


† There are more circular rugs found in China than in any other country, and some are exported. But they are seldom called for in this country, and clerks in the large establishments which import them express surprise when inquiries are made for them. The warp of the ordinary Chinese rug is mostly of cotton, and the woof and pile are of wool or camel's hair.

Tsun-hua rugs are made of silk and camel's hair in the province of Chi-Li.

RUGS: ORIENTAL AND OCCIDENTAL

JAPANESE RUGS

IN olden times woven rugs were not known in Japan. The wealthy classes of Japan covered their floors with grass, over which they spread the skins of animals. The poorer classes had not even skins, but only reeds or straw. About four hundred years ago silk and wool rugs were introduced into Japan from Persia, China, and India. For a time the Japanese imitated these rugs, but later the industry ceased. Since the opening up of the country, however, rug-weaving has prospered, and the introduction of fine cotton yarns of uniform quality has increased greatly the growth of all textile industries. The modern Japanese rugs are made of cotton or jute, and are used extensively in the United States in summer homes. In the towns which produce these rugs little children may be seen busily engaged in weaving, their small fingers being very deft at this work. The chief colors employed by the Japanese in their rug-weaving are blue, white, and sometimes a beautiful pink. In weaving, designing, and coloring, as in everything else the natives do, their exactness of finish and thoroughness in detail are noticeable. The Persian designs which were once reproduced in Japan are now supplanted by designs purely Japanese. The dragon is a favorite design in some of the older rugs.



MISCELLANEOUS ORIENTAL RUGS

KHILIM RUGS

WRITTEN ALSO GHILEEM, KELIM, KILIM

The Khilim is of very early origin. Many authorities consider it the oldest type of rug. From father to son it has been woven and used in the tents of the nomadic tribes. The designs in the Khilims are most carefully drawn, mainly in geometric figures, and it is interesting to note the attention paid to every detail.

There is a great deal of artistic merit displayed in the old Khilims, so that with several contrasts in colors, which are usually rich and subdued, there is decided harmony. The yarn is twisted so tightly that when woven it resembles heavy linen. Only vegetable dyes are used in the old Khilims which can be cleaned with cold water and soap. They are very firm and strong and, as in the case of the Shirvan Khilim, can be used constantly on a floor without injury to the rug. The Sinna Khilim, however, is finer and more delicate and is for use as a table cover or may be thrown over a screen.

In the Asiatic section of the British Museum is a very interesting fragment of a Khilim, found in a dwelling house of Niya Site, excavated by Sir M. A. Stein. It originally came from Chinese Turkestan. The colors are in a wonderful state of preservation, mainly beautiful

RUGS: ORIENTAL AND OCCIDENTAL

blues, with varied designs like crosses, the larger resembling the papal cross. The designs are in cream color.

A bit of romantic sentiment is woven into the Kis Khilims, as those made by the Turks in Anatolia are often called. It is said that the word means "bride's rug" and that the name is derived from the fact that these rugs are woven by young girls, each of whom endeavors to finish her rug in time to win a husband. A lock of hair is often found in the Kis Khilim, said to have been woven in by the girl who made it.

In Oriental countries the Khilim is used as a floor covering, and also as a curtain to divide the dwelling portion of the tent from that in which the cattle are sheltered. It is also used by the natives on their long journeys. In the United States this rug is exceedingly popular as a hanging, and for the cover of a divan it is equally effective, whether used in the home or in the studio.

MISCELLANEOUS ORIENTAL RUGS

POLISH RUGS

THERE are few of the so-called Polish rugs in existence, and these are priceless and cannot be bought. They are mostly seven feet long by four wide. The name takes its origin from the fact that a Pole (by name Mersherski), after travelling in Persia and India, established a rug factory in Warsaw.

Polish rugs are of silk, with gold and silver thread interwoven. Their texture is looser than that of the usual Oriental rug, and for this reason they cannot stand hard wear; but they are exceedingly handsome with their gold lustre and silky sheen. In these rugs a number of warp threads are crossed by the metal threads and overspread, so that the lines or ribs are brought out more prominently. This in part accounts for the softness and looseness of the texture.

Some time ago Dr. Wilhelm Bode, the eminent German scholar and authority on antique Oriental rugs, decided that these unusual rugs were of Persian origin, because of their general style and design. Since then Mr. R. Martin has proved this by documentary evidence.

RUGS: ORIENTAL AND OCCIDENTAL

PRAYER RUGS

THE prayer rug is so distinctly *sui generis* that it requires a little explanation. It is to be found wherever dwell the followers of Mohammed, and the design usually includes a representation of a mosque, or place of public worship, showing the mihrab, which is the niche in the wall of the mosque, so located that when the worshipper prostrates himself before it he will be prostrating himself toward Mecca.*

The Mohammedan, if he build a mosque, locates it so that its axis extends in the direction of Mecca; in such buildings the mihrab is not necessary, as the natural position of the worshipper places him so that his face is toward the sacred city. Where Christian buildings, such as the great Basilica of St. Sophia at Constantinople have been appropriated for Moslem worship, the niche or mihrab may be located well toward one corner of the building.

The prayer rug was evidently invented for the purpose of providing the worshippers with one absolutely

* Some prayer rugs have a representation of the hands of Mohammed, and on them the suppliant places his own as he throws himself prostrate. In the corners of some of these rugs pulpits are represented, and occasionally trees.



MISCELLANEOUS ORIENTAL RUGS

clean place on which to offer prayers. It is not lawful for a Moslem to pray on any place not perfectly clean, and unless each one has his own special rug he is not certain that the spot has not been polluted. With regard to the purity of the place of prayer Mohammedans are especially careful when making their pilgrimages, the rugs which they take with them having been preserved from pollution by being rolled up until the journey is begun, or until the hour of prayer arrives. It does not matter to these followers of Mohammed how unclean a rug that is on the floor may be, because over it they place the prayer rug when their devotions begin.

About two hundred years ago small embroidered rugs were largely made in Persia, chiefly at Ispahan. These were prayer rugs, and on each of them, near one end, was a small embroidered mark to show where the bit of sacred earth from Mecca was to be placed. In obedience to a law in the Koran that the head must be bowed to the ground in prayer, this was touched by the forehead when the prostrations were made, and so the letter of the law was carried out. The custom still prevails. The Persian women who make the finest prayer rugs seldom weave any other kind of rug. But the encroachments of civilization and commerce have changed the original purpose of the prayer rug. Once

RUGS: ORIENTAL AND OCCIDENTAL

it was sacred, and the masterpieces of workmanship in the products of Asia Minor were devotional in character. Upon these rugs many a soul prostrated himself before Allah in reverence; but now in the further interior only is the prayer rug made for aught but commerce.

As a class the modern Anatolian prayer rugs are quite inferior, being woven irregularly, and without regard to details or finishing; yet there are among them some fine specimens of Anatolian weaving. The famous prayer rugs of Asia Minor (Anatolian) made at Ghiordes, Kulah, Laodicea, and Meles are described in preceding pages. They are the joy of the collector and the artist. The antique Ghiordes rugs are really fine in colors, generally with much pale green, red, or blue. The design most frequently seen is the Tree of Life. One special kind is distinguished by a yellow vine on a dark blue field.



MISCELLANEOUS ORIENTAL RUGS

SILK RUGS

LONG before other countries learned the art of cultivating silkworms, China was at work weaving fabrics of silk. Chinese historians claim that the origin of reeling silk and putting it to use was discovered by a woman, — Se-Ling-She, wife of Hwang-te, third Emperor of China, — and for that reason she has always been regarded by them as the “goddess of silkworms.” The date of this discovery is about 2640 B. C. For about two thousand years the Chinese kept secret their methods of reeling and weaving silk, but finally Japan, Persia, and India learned the art, Persia having for many centuries transported raw silk between China and the West. Very slowly grew the process of silk-weaving. Greece, Spain, and Sicily by degrees attained the knowledge. In A. D. 550 it was introduced into Constantinople, and in 1148 silk manufacture was carried into Italy, and the cultivation of mulberry trees was enforced by law. The industry soon spread into the south of France, where it rapidly advanced.

At the present day enormous quantities of silk are produced in various parts of the world. The principal countries are China, Japan, India, Southern Europe, and some parts of Persia and Asia Minor. During the Middle Ages and down to the seventeenth century, the

RUGS: ORIENTAL AND OCCIDENTAL

province of Ghilan in Persia produced very fine silk and in large quantities. In all the countries and districts just mentioned, magnificent silk rugs have been woven for many centuries.

The silk rug when at its best is unsurpassed in beauty; it is distinguished by its richness, exquisite coloring, and rare sheen. But silk rugs require the most luxurious surroundings: nothing looks so out of place as one of these costly fabrics of the loom in a poor setting. They are more suitable for decorative purposes and museums than for service; they should be used as hangings, not for floor coverings. An exquisite silk rug interwoven with pearls is hung before the famous Peacock Throne of the Shah at Teheran, Persia.

The most magnificent silk rugs have been woven in China, and these are interesting from every point of view, especially as regards history, color, and texture. The silk rugs of Khotan are remarkable for their beauty and fineness; on important occasions of state and ceremony the Chinese place them upon the table. Silk carpets of special beauty worked with gold threads are made in Peking for the Imperial Palace, although many of this kind found at the Court are said to be of Central Asiatic origin.

In making silk rugs, the greatest care is necessary in the shading. Sometimes the shading of woollen rugs is made more effective by the addition of silk.



MISCELLANEOUS ORIENTAL RUGS

As the demand for silk rugs is comparatively small, they are seldom woven on speculation. When made to order in Persia, they cost from ten dollars to fifteen dollars per square foot; thus the usual price of a silk rug of Persian make is from two hundred dollars up to thousands of dollars. Those made in Turkey can be bought much cheaper.

The Turkoman silk rugs are generally twice the size of the usual sheep's wool or camel's hair rugs. They are very fine, and often two hundred dollars is paid for a rug of this kind eight feet square.

Rugs made of raw silk are exported from Samarkand, and silk rugs of old Persian designs are copied and woven at Cæsarea. Some weavers of the modern silk rug, however, do not have recourse to established designs; they give play to their imagination, as do the weavers of wool rugs. Other weavers copy chiefly designs from chintz, and still others work from designs introduced from Europe.

Mrs. Bishop tells us that silk produced at Resht is brought to Kashan to be spun and dyed. Then it is sent to Sultanabad to be woven into rugs. It is next returned to Resht to have the pile cut by the sharp instruments used for cutting the velvet pile. After the rugs are finished, they are sent to Teheran to be sold.

RUGS: ORIENTAL AND OCCIDENTAL

FELT RUGS

IN the Orient a large and heavy rug is made of felt. This is used extensively by the natives, but is too heavy to export. Even the shepherds of the Kotan-Daria and of the Keriya-Daria use it in their primitive and isolated abodes. Sometimes an old felt rug is propped up by poles and becomes a tent, in which dwell the shepherds of Central Asia.

This felt rug is made of the hair of the camel, goat, or sheep, or by a mixture of all these kinds. It is matted together by heavy and constant pounding, moistened with water, turned and beaten again and again until it becomes compact and solid. Sometimes the felts are decorated with colored threads and often the name of the weaver is woven in. Among the best felts are those made at Astrabad and Yezd.

In color felts are gray, brown, or white. The last named are woven at Khotan. No dye is used; the hue is that of the hair of the animal, or the composite hue resulting from the mixture of the hair of different animals.

The felts have no seams, and are from one to four inches thick. Although this material is of far more ancient date than the days of St. Clement, a legend



MISCELLANEOUS ORIENTAL RUGS

connects his name with the discovery of felt. The tradition is that while on a pilgrimage the Saint, having put a wad of carded wool into his shoes to protect his feet from blisters, found at the end of his journey that the pressure and moisture had converted the wool into felt.

RUGS: ORIENTAL AND OCCIDENTAL

HUNTING RUGS

The hunting rugs of Persia are the most remarkable and interesting rugs known. They had their origin in the Chinese pictures of hunting scenes, from which the designs were copied. The most sumptuous example of this type of rug now in existence is in the possession of the Austrian Government. Mounted hunters in Persian dress adorn a center field, galloping in pursuit of native Persian animals over a ground covered with flower-clad vines. Winged genii hover among flowers in the broad main border.

Another fine hunting rug on display in the Boston Museum is so similar in design to Persian and Indian lacquer work of the sixteenth and seventeenth centuries that it is evident the motif must have been copied. It represents a hunting scene with Indian and other Far-Eastern animals. A hunting car drawn by an ox and other interesting scenes are shown in a pavilion. Mosques of grotesque design make up the border.

These two rugs are the supreme examples of Indo-Persian hunting rugs. Similar ones of coarser and less elaborate workmanship are included in various private and museum collections. Among these is one belonging to Baron Adolphe Rothschild, another to M. Maciet of Paris and a third at the Royal Palace at Stockholm.

V

RUG-WEAVING IN EUROPE AND
THE UNITED STATES

V

RUG-WEAVING IN EUROPE AND
THE UNITED STATES

IN the preparation of this section of this work, there has been no attempt or desire to slight in any way the weaving industry of the West. It has not seemed advisable, however, to go into many details on the subject, for it is one easily learned from many sources by any one who desires. There is not the mystery about Occidental weaving that there is about Oriental, the latter perhaps appealing to our innate desire of acquiring knowledge difficult of access. A short account of rug-weaving in Europe and the United States will, therefore, be quite as satisfactory to the general reader as a more lengthy description.

RUGS: ORIENTAL AND OCCIDENTAL

GREEK RUGS

GREEK rugs are almost as ancient as Greece herself. Many an old love-song of this land has praised the skill of the woman deftly plying the hand loom. But if one expects to see the glory of ancient Greece, in its perfection of form and design, transmitted in any degree to the industry of modern rug-weaving he will be disappointed. From time immemorial rugs have constituted a most important part of the dowry of a young girl from the provinces. Even now the courting of a bride in Crete is often prefaced with the question whether the girl is skilled in the handling of a loom. But the modern Greek rug is seldom seen outside of its own country, for it is generally made for home use, and the weaver is not easily induced to part with it. Besides this, the foreign market would not be large for them, especially in competition with the well-known and excellent Oriental rugs.

Greek rugs are of two kinds—the heavy ones which serve for floor coverings in the winter, and the thinner, which are used all the year round. Both are made of home-produced wool, often with hemp woof, and are worked by women and girls only, in wooden looms of a primitive order.

RUG-WEAVING IN EUROPE

Athens is the only place in Greece where rugs are produced in a factory. Under the patronage of Her Majesty the Queen, an Association for the Education of Poor Women exists. This philanthropic association has founded an industrial institution which employs four hundred women and girls in its various departments, of whom about thirty are engaged in rug-weaving. The best rugs are those purely Grecian in design and quality, and for these special orders are generally sent in. The rugs thus woven are durable and effective. Sometimes an attempt is made to imitate Turkish rugs, but without their superb effect. Coarse rugs of an inferior class are sold in the bazaars of Athens. The predominant color in these is a dingy white, with stripes of various colors at the ends. The rug is really durable, though the noticeable, fuzzy nap soon wears off.

RUGS: ORIENTAL AND OCCIDENTAL

MOORISH AND SPANISH RUGS

THE Arab conquerors of Spain, or the Moors as they are often called, are believed to have taught the Spaniards and Venetians the art of rug-weaving. The rugs now known as Moorish are made by the descendants of this race. Their leading color is yellow, and in style and quality they resemble the so-called Smyrna rug. Antique Moorish rugs are found in the cathedrals of Toledo and Seville. These are relics of the thirteenth century and have geometric designs.

Morocco rugs are Moorish. Those of modern manufacture are very inferior. The poorest aniline dyes are used, and it seems hardly possible that the splendid specimens of the fourteenth to the end of the seventeenth century were woven in Morocco. But the rugs in the Sultan's palace at Fez prove this fact, as does the splendid antique rug in the possession of Prince Schwarzenberg, at Vienna. Fez was formerly one of the chief seats of the rug industry, which is now limited mostly to Rabat. Unfortunately, aniline dyes are now largely used, and even the designs are less artistic than in former years. There is, however, a rug not known to the trade, and only rarely met with outside its home. It is the

RUG-WEAVING IN EUROPE

Tuareg rug, and is woven by the Berbers, a tribe occupying the desert south of Algeria and Tunis and known as Tuareg or Tawarek by the Arabs. The Tuaregs are great traders, and control the principal caravan routes. Their rugs are woven by the women, and seldom if ever leave the families which weave them. The most beautiful are used as shrouds, and are buried with their owners.

Tunis sends out a few rugs woven at Kairuan. They are thick, heavy, but inferior in many ways to rugs of Oriental workmanship.

Rabat rugs were often sold as Spanish, but they are quite different. As a rule they are rather coarse in texture. The colors, however, are generally Spanish and rather strong. Reds verging on magenta, and brilliant yellows and blues. A very fine old one I once owned was in rich blues and a moss-green. Arabesque designs were prominent, outlined in black.

In the Public Museum at Algiers antique rugs of this type hang on the walls.

RUGS: ORIENTAL AND OCCIDENTAL

BOSNIAN, SERVIAN, ROUMANIAN, AND BULGARIAN RUGS

BOSNIAN rugs in olden times were sometimes very fine. Then came years of general depression, when the industry of weaving fell into decay. Finally the Austro-Hungarian administration was established at Bosnia, and new life was given to the work. Looms were erected by the Government, and a number of women were sent to Vienna, where they were taught the art of weaving. Returning to Bosnia, they were able to impart to others the knowledge they had gained, and thus the work prospered. To enhance further the value of these rugs, the latest designs in the old Bosnian rugs were selected, and by the harmonious blending of these with new designs and colors, modern rugs were made, which show decided improvement.

Servian rugs are woven throughout all Servia, but the principal seat of the industry is at Pirot, on the southern boundary of the Balkan Mountains. The rugs are of wool, and the best are very durable. The dyes are generally vegetable, the weaving is a home industry, and the designs are all worked on a black or red ground. The preferment in the modern rug is for red,

RUG-WEAVING IN EUROPE

but the older rugs had the black ground. The general design is an extended square, in the centre of which is a panel. The rest of the field is filled with stripes and geometrical forms in rather bright and varied coloring.

Roumanian rugs of modern make are quite inferior. They are woven on ordinary hand looms in the villages and towns among the mountains of Roumania. They are coarse, and the designs are in stripes, zigzag lines, or straight-lined figures. Occasionally flower designs have appeared, but these have been poorly reproduced, and in the most unsuitable combinations of color. Old Roumanian rugs are not in the market. They are owned by private individuals, and are not to be procured except at very high prices, if at all. These rugs differ from the modern ones in their better workmanship and designs.

Bulgarian rugs, as a rule, are very coarse in texture, loosely woven, and unattractive. Occasionally Bulgarian rugs are seen with finer weaving and well-chosen colors. Both men and women take part in preparing the wool, the former setting up the simple looms, preparing the darker dyes, and arranging the warp. The women choose the designs and colors, and weave the rugs. The colors commonly used are yellow, blue, brown, black, white, green, and red.

RUGS: ORIENTAL AND OCCIDENTAL

ENGLISH RUGS

IN England the introduction of tapestries as hangings for walls was made by Eleanora, sister of Alfonso the Tenth of Castile, when she became the wife of Edward the First. In her journeyings these fabrics of the loom were carried as part of the royal baggage, and must have given some sense of cheer, particularly when they clothed the bare walls of the dreary castle of Cærnarvon.

Edward the Third (1327-1377) invited Flemish weavers to settle in England. At that time England produced wool in large quantities, although very few fabrics were woven there, nine-tenths of the wool being sent to Ghent or Bruges to be manufactured; for the Flemish were the first people in the northern part of Europe who advanced in the arts and in manufactures. Throughout Northern and Western Europe rugs were seldom used, except for wall hangings and table covers, until the time of the Reformation in Germany.

Great Britain is now quite active in the manufacture of rugs with certain designs, a decided impetus to the improvement of this industry being given by Mr. William Morris, the English poet and artistic decorator, who was born near London in 1834.



RUG-WEAVING IN EUROPE

The Morris Rug. With strong, firm texture, fine vegetable dyes, and with purely artistic designs, the Morris rug bears testimony to-day to the honesty, perseverance, and skill of the man for whom it is named. He himself testifies: "I am an artist or workman with a strong inclination to exercise what capacities I may have—a determination to do nothing shabby if I can help it." Decorative art in many branches is the richer to-day for the influence of Mr. Morris, but it is his rug-making that now claims attention. Mr. Bernhard Quaritch informs me in a letter dated August 31, 1899, that Mr. Morris learned the art of making rugs from a volume of the work entitled "*Descriptions des Arts et Metiers*." Mr. Morris had his own loom, and not only wove rugs, but dyed the wool for them himself, and instructed pupils, to whom his inspiration was a power. Long and laboriously he worked to achieve the best results, using vegetable dyes only, and he was finally successful. No dyer of the Orient could have been more pleased than was he when his efforts resulted in soft, glowing tints.

In design Mr. Morris excelled. He educated the popular taste by bringing forth the beauties of the simpler forms of the floral and vegetable world; he delighted especially in displaying the acanthus in varied conventional forms. Every rug he designed bears

RUGS: ORIENTAL AND OCCIDENTAL

witness to his enthusiasm for harmony. Too æsthetic, some critics declare him to have been; but no one can deny the importance of his creations, for England needed to be awakened to a knowledge of her own inability to appreciate artistic decoration of the home, especially by means of the productions of the loom. It was this very fact, and his inability to procure artistic furniture such as would satisfy his æsthetic taste, that started Mr. Morris to create those fabrics which he desired.

RUG-WEAVING IN EUROPE

FRENCH RUGS

THE art of rug-weaving was first introduced into the West by the Moors when they conquered Spain. With the advance of civilization it proceeded to the land of the Gauls, where during the reign of Henry the Fourth it was brought from Persia. An inventor named Dupont was placed in charge of a workroom by the King, in the *Palais du Louvre* about the year 1605. In the year 1621 an apprentice of Dupont's, named Lourdes, was instructed to establish the industry of weaving in a district near Paris, where was the *Hospice de la Savonnerie*, an institution for poor children. The factory was called *La Savonnerie* because the building had been previously used for the manufacture of soap. Since 1825 *La Savonnerie* has been consolidated with the Gobelins manufactory. In 1664, Colbert, minister to Louis the Fourteenth, founded the establishment at Beauvais which is owned by the French Government, as is also that of the Gobelins, which Colbert bought of the Gobelin family. But it is to the Saracens that France ultimately owes the origin of her famous tapestries, and it is to the Saracens, through France, that Western and Northern Europe trace their obligation.

RUGS: ORIENTAL AND OCCIDENTAL

The industry has attained large proportions in France. At Aubusson alone over two thousand workmen are employed in rug-weaving. A fine specimen of the work done there is a rug of Oriental design made for a collector in New York. The piece-work system is now generally used throughout the weaving districts of France. The manufacturers themselves usually place the rugs on the market. France buys the greater quantity, although many are exported.

Austria-Hungary, Germany, Holland, and Italy have also had some experience in rug-weaving, and even little Switzerland at one time attempted its introduction, but with unsatisfactory results. Belgium, however, was more successful, for Brussels still produces a large number of rugs.

RUG-WEAVING IN UNITED STATES

THE UNITED STATES

THE United States is largely occupied in rug-weaving, and the centre of the Eastern section of this manufacture is Philadelphia. But in various sections of the country there are rug factories, both large and small.

The *Abenákee* rug is made at Pequaket, New Hampshire. It is the result of a desire on the part of Mrs. Helen R. Albee to give profitable employment to the women of the rural community where she lives. Her success is now assured, and the reward for much labor and thought has come in a lively demand for the rug.

The *Abenákee* rugs are not woven. They are an evolved form of the much despised New England hooked rug, which was made by drawing strips of old rag through burlap. The thick, soft, velvety *Abenákee* rugs of the present day are far removed in color, design, and texture from their humble ancestors. These rugs are all wool, hand-dyed in warm tones of terra-cotta, old rose, old pink, tans, dull yellows, rich old blues, olive and sage greens, and old ivory. They are made to order usually, to match in their ground color some special color in the room where they are to be placed, and the borders are made in harmonious tones. The

RUGS: ORIENTAL AND OCCIDENTAL

range of design is wide, from Oriental to Occidental — from Japanese to North American Indian. But all suggestions, so soon as received, are modified and removed as far as possible from direct imitation of any foreign rugs. Mrs. Albee has aimed, not to reproduce Oriental effects, but to have the designs original and distinctive. Fortunately, for years previous to the establishment of this industry, she had studied the principles of design and their application to various textiles, and the knowledge which she thus acquired has proved most valuable.

The designs are bold and effective, but fineness of detail is precluded by the strips of material, each of which is a quarter of an inch wide. The color is arranged in broad masses.

The *New England Hooked* or *Rag* rug has for its foundation a strip of burlap or sacking. Through this, strips of cloth are hooked, which form loops, and this surface may be sheared or not, as the maker desires. There is such an absence of attractiveness in the old-time rag rug, that several women of taste and experience in art methods have sought the improvement of this industry. The results have been excellent, so that, ugly as the original rug is, it is esteemed as being the progenitor of the more artistic Abenákee, Sabatos, and Onteora rugs.

RUG-WEAVING IN UNITED STATES

The *Sabatos* rug is a product of the little mountain village of Center Lovell, Maine, started in 1900 by Mrs. Douglas Volk of New York. She has now about a dozen women engaged in the work, this number including the spinners, dyers, and weavers.

The *Sabatos* rug is durable, harmonious in color and design, and is distinctly a home product. The wool of which it is made is sheared from the flocks of sheep in the vicinity. The shearing takes place annually in June; the wool is then carded, spun, and dyed. The threads of hand-spun wool are worked through a hand-woven webbing, and securely knotted or tied with a specially devised knot. The designs thus far are mainly adaptations from the native American Indian motives, which are simple and characteristic, furnishing a chance for broad color effects.

A special point is made of the dyes employed, those of vegetable origin ruling, and only those dyes which from experience have been found to be practically fast are used,—such for instance as genuine old Indigo blue, madder root, and butternut.

Berea College, Kentucky, is endeavoring to encourage the weaving of rag rugs of a superior order. So far, the industry which was started in 1905, is in a primitive state, the natives preferring to weave cotton and wool coverlets, the designs of which they brought

RUGS: ORIENTAL AND OCCIDENTAL

across the mountains with them from Virginia in the early settlement of Kentucky. Floor rugs they consider troublesome. The weaving is carried on in the homes throughout the mountains of that region known as "Appalachian America"; it is really a survival of the old Colonial industry. The rugs are woven of strips of new ticking, and are especially designed for bathrooms, children's nurseries, and porches. The coloring is done with the vegetable dyes and native barks and roots. The color schemes are the simple ones of a primitive people.

Navajo Rugs. The Navajo Indian Reservation covers about eleven thousand square miles, about six hundred and fifty of which are in the northwest corner of New Mexico, and the remainder in the northeast portion of Arizona. The region is well adapted for the raising of sheep, and every family possesses flocks, which are driven from place to place for pasture. The Navajos, however, never go to any great distance for this, but keep generally within a radius of fifty or sixty miles from home. This tribe weaves a rug that is useful, unique, durable, and when at its best, impervious to rain. Among the tribes, and in some Western homes, they are used as blankets, but it has become a fashion in many of the best houses in the Eastern States to use them entirely as rugs, couch coverings, and *portières*.



RUG-WEAVING IN UNITED STATES

It is believed that the Spaniards, when they arrived in that section of North America inhabited by the Pueblo tribe of Indians, communicated to them the industry of weaving these rugs, and that the Pueblos taught it to the Navajos. Thus it appears that the weaving of the Navajo rug was a result of the Moors' invasion of Europe. The sheep, which are raised by thousands, were also introduced by the Spaniards. The wool is not washed until after the shearing. In the last quarter of the nineteenth century the Navajos began to use the shears of the white man; previously they procured the wool by cutting it off the body of the animal with a knife, and pulling it from the legs.

The native dyes are red, yellow, and black, and the natural colors of the wool are black, gray, and white. The dyes of the white man are now much used. Formerly there was a beautiful blue, which has given way to the indigo. A scarlet cloth called Bayeta was once much used in the weaving of these rugs, but Germantown yarn and other inventions of the white man have largely superseded the old-time materials and methods.

The spindle is of the crudest form, and sometimes the wool is simply picked out from the mass, and rolled into the yarn or thread on the hand.

The looms are fashioned after the most primitive

RUGS: ORIENTAL AND OCCIDENTAL

ones of the Orient, and the weaver sits on the ground and weaves upward. Women do most of the weaving, but occasionally a dusky-faced man may be seen at the loom. It takes about a month to weave a rug six feet ten inches by five feet seven inches.

The designs in the Navajo rugs are many, and mostly in angles and straight lines, the serrated diamond design being common, as is the swastika or fylfot. The weaver makes up her own designs as she goes along, occasionally only tracing it in the sand.

There is a symbolism attached to many forms in these rugs. The square with four knit corners represents the four quarters of heaven and the four winds. A tau cross is a symbol of protection and safety, and a prayer to the Great Spirit. A spiral form represents the purified soul, and a double spiral is a symbol of the soul's struggle. A wave mark represents the sea, over which the people came from a far country. Black is the symbol of water, regarded as the mother or spirit. Red is the symbol of fire, and is regarded as the father.

The native costume of the women of the Navajo tribe consists of two small rugs in dark blue or black, with a bright stripe at each end. They are of the same size, and sewed together at the sides, except where a place is left open for the arms. Formerly the Indians

RUG-WEAVING IN UNITED STATES

reserved their hand-made rugs for their own use, but now that there is so great a demand for the work of their hands, they sell those rugs, and content themselves with blankets of factory make.

Old Navajo rugs, like Oriental ones, are growing scarcer every year, and naturally are becoming more valuable and desirable. The fine textures, perfect workmanship, and glowing colors are seen at their best in productions of the past.

VI

MISCELLANEOUS INFORMATION

VI

MISCELLANEOUS INFORMATION

INSCRIPTIONS ON RUGS

WE are occasionally indebted to an Oriental scholar for a translation of an inscription on a rug; often these inscriptions show the religious belief of the maker. |

One fine rug in a museum in Austria has the following inscription: "Allah! No God exists besides Him, the Living, the Eternal. Nothing causes Him to slumber or to sleep. To Him belongs everything in heaven and on earth. Who can intercede with Him without His permission? He knows what is before and what is behind, and only so much of His wisdom can be grasped as He permits. His throne fills heaven and earth, and the support of both to Him is easy. He is the High One, the Exalted!"

A rug of Persian weave owned by Baron Nathaniel Rothschild has, worked in the oval cartouches, an inscription translated by Professor F. Bayer as follows:

RUGS: ORIENTAL AND OCCIDENTAL

1. "Honored mayst thou be in the world,
Among the clever and wise.
2. May no sorrow be allotted thee by an unfavoring Heaven,
And may no care torment thy heart.
3. May earth be all to thee that thou wouldst have it, and
destiny prove thy friend.
May high Heaven be thy protector.
4. May thy rising star enlighten the world,
And the falling stars of thine enemies be extinguished.
5. May every act of thine prosper,
And may every year and every day be to thee Spring-time."

In the Industrial Museum at Berlin there is a rug with this inscription: "There is no Deity but God, and Mahomet is His Prophet."

On a Persian silk rug is a line from the Koran: "All perisheth but His face."

Another rug has: "God is greatest! He is great!"

Often a marking in a corner of a rug is simply the name of the maker, and the date.

The Holy Carpet of the Mosque at Ardebil, now in the South Kensington Museum, at London, has the following interesting inscription woven in black characters in the light cream cartouche at the top of the carpet. Translated it reads:

MISCELLANEOUS INFORMATION

“I have no refuge in the world other than thy threshold.

My head has no protection other than this porchway.

The work of the slave of this Holy Place,

Maksoud of Kashan

In the year 946.”

(The year 946 of the Hegira corresponds to A. D.
1568.)

RUGS: ORIENTAL AND OCCIDENTAL

ORIENTAL SYMBOLS

ALL Oriental rugs have designs, and every design is symbolical. To the connoisseur, as well as to the owners of rugs, it is vastly interesting to understand the meaning attached to these symbols by the Orientals. Every one is familiar with the tree design in some of its various forms, and with the stiff little birds and the many odd and strange-looking animals which frequently are seen on an Eastern fabric of the loom. Yet each unique figure has a meaning, and it is a fascinating, as well as an apparently endless task, to find the hidden significance of these symbols. If one goes no further, he should at least become familiar with the designs on his own rugs, and know, if possible, what they typify.

The rug itself symbolizes Eternity and Space, and the filling or plan is the symbol of the world—beautiful, but fleeting and limited.



MISCELLANEOUS INFORMATION

CHINESE SYMBOLS

BAT	<i>Happiness.</i>
BUDDHIST SCEPTRE . . .	<i>Success in literary labors.</i>
CHI-LIN (a kind of doe) . .	<i>Nobleness; gentleness.</i>
CLOUD-BAND	<i>The Deity.</i>
COCK AND HEN ON AN ARTI- FICIAL ROCK-WORK . . .	<i>Pleasures of country life.</i>
CRANE	<i>Immortality.</i>
CROW	<i>Evil.</i>
DEER	<i>Official emolument.</i>
DRAGON	<i>The imperial emblem, signifying in- crease and imperial grandeur.</i>
DRAGON WITH FIVE CLAWS ON EACH OF ITS FOUR FEET .	<i>Exclusive emblem of the Emperor.</i>
DRAGON AND PHŒNIX . .	<i>Newly wedded pair.</i>
DUCK	<i>Conjugal affection.</i>
GOOSE	<i>Domestic felicity.</i>
GOURD	<i>Happiness.</i>
LION	<i>Victory.</i>
MAGPIE	<i>Good luck.</i>
OLD MAN LEANING ON A STAFF	<i>Long life.</i>
OWL	<i>Dread.</i>
PEACH	<i>Old age.</i>
PHŒNIX	<i>The Emblem of the Empress.</i>
STORK	<i>Long life.</i>
TORTOISE	<i>Long life.</i>
TREE OF LIFE WITH SEVEN BRANCHES ON A SHORT STEM	<i>Seven days of Creation.</i>
YOUNG STAGS	<i>Long life.</i>

RUGS: ORIENTAL AND OCCIDENTAL

EGYPTIAN SYMBOLS

ASPS	<i>Intelligence.</i>
BAT WITH A RING IN ITS CLAWS	<i>Duration.</i>
BEE	<i>Immortality.</i>
BEETLE	<i>Earthly life and the development of man in the future state.</i>
BLOSSOM	<i>Life.</i>
BOAT	<i>Serene spirit gliding upon the waters.</i>
BULL	<i>Source of life.</i>
BUTTERFLY	<i>Soul.</i>
CARTOUCHE	<i>Eternity.</i>
CRESCENT	<i>Celestial virgin.</i>
CROCODILE	<i>Beneficent Deity.</i>
DOVE	<i>Love; mourning of a widow.</i>
EAGLE	<i>Creation; preservation; destruc- tion; power.</i>
EGG	<i>Life.</i>
EYE OF OSIRIS	<i>Eye of the Eternal Judge over all.</i>
FEATHER OF AN OSTRICH .	<i>Truth; justice. (The ostrich it- self does not appear in Egyp- tian art.)</i>
FEATHERS OF RARE BIRDS .	<i>Sovereignty.</i>
FROG	<i>Renewed birth.</i>
HAWK	<i>Power.</i>
IBIS	<i>Usefulness; the heart.</i>
LIZARD	<i>Divine wisdom.</i>
LOTUS	<i>The Sun; creation; resurrection.</i>
NILE KEY	<i>Life.</i>

MISCELLANEOUS INFORMATION

PALM TREE	<i>Immortality; longevity.</i>
PAPYRUS	<i>Food for mind and body.</i>
PINE CONE	<i>Fire.</i>
POMEGRANATE	<i>Life.</i>
ROSETTE	<i>A lotus motive.</i>
SAIL OF A VESSEL	<i>Breath; the belief that the soul is inactive and worthless until revived by the breath of the mind.</i>
SCARABÆUS	<i>Immortality; resurrection; a rul- ing providence.</i>
SOLAR DISK WITH SERPENTS	<i>Royalty.</i>
SPHINX	<i>Beneficent Being.</i>
STAFF IN THE HANDS OF THE GODS	<i>Purity.</i>
SUN	<i>Deity; life.</i>
VIPER	<i>Power.</i>
WHEEL	<i>Deity.</i>
ZIGZAG	<i>Water.</i>

INDIAN SYMBOLS

ASS	<i>Humility; austerity.</i>
BANIAN OR BURR TREE	<i>Deity (because of its outstretched branches and overshadowing beneficence).</i>
BUTTERFLY	<i>Beneficence of Summer.</i>
FYLFOT CROSS OF BUDDHISM	<i>Auspiciousness.</i>
KNOT AND FLOWER DESIGN	<i>Divine bounty and power.</i>
SERPENT	<i>Desire.</i>

RUGS: ORIENTAL AND OCCIDENTAL

JAPANESE SYMBOLS

PINE TREES	<i>Long life.</i>
STORKS	<i>Long life.</i>
TORTOISES	<i>Long life.</i>

PERSIAN SYMBOLS

DESCENDING EAGLE	<i>Bad luck.</i>
EAGLE	<i>Light; height.</i>
FLYING EAGLE	<i>Good luck.</i>
HOUNDS	<i>Fame; ever increasing honor.</i>
LEOPARDS	<i>Fame; ever increasing honor.</i>
LION	<i>Power; victory.</i>
PEACOCK	<i>Fire; light.</i>
PHOENIX	<i>Immortality.</i>
STANDING EAGLE	<i>Good luck.</i>
SUN	<i>Light.</i>
SWORD	<i>Force.</i>
TREE OF HEALTH	<i>Immortality.</i>
TREE OF LIFE	<i>Knowledge; truth.</i>

The Coat of Arms of Persia is the Lion holding a sword in his paw, and with the Sun at his back.

TURKISH SYMBOLS

CRESCENT	<i>Increasing power.</i>
--------------------	--------------------------

The Turkish Coat of Arms is the Crescent and the Star. These heavenly bodies are supposed to signify growth.

MISCELLANEOUS INFORMATION

MISCELLANEOUS SYMBOLS

ANEMONE	<i>Good fortune.</i>
BAT	<i>Maternity.</i>
BIRD	<i>Spirit.</i>
BOAR	<i>Winter.</i>
BUTTERFLY	<i>Ethereal soul.</i>
CIRCLE	<i>Eternity ; perpetual continuity.</i>
CYPRESS TREE	<i>Tree of life ; immortality ; perfect and renewed life.</i>
DOG	<i>Destruction ; vigilance.</i>
ELEPHANT	<i>Patient endurance ; self-restraint.</i>
EVERGREENS	<i>Immortality.</i>
FIR CONE	<i>An existence terminated but united — the union of the tribes against the dominion of Rome.</i>
FLY	<i>Destroying attribute.</i>
HARE	<i>Fertility.</i>
HEART	<i>Man morally.</i>
HIPPOPOTAMUS	<i>Destroying power.</i>
HOG	<i>Deep meditation.</i>
JUG	<i>Knowledge.</i>
LILY	<i>Purity.</i>
OLIVE	<i>Consecration to immortality.</i>
OWL	<i>Wisdom.</i>
OX	<i>Patience ; gentleness.</i>
PEACOCK	<i>Resurrection (because of the annual renewing of its plumage, and from a belief in the incorrupti- bility of its flesh).</i>

RUGS: ORIENTAL AND OCCIDENTAL

PHENIX	<i>Good luck; herald of prosperity; birth of great men.</i>
PIG	<i>Universal kindness.</i>
RAM	<i>Spiritual leadership.</i>
REED	<i>Royalty.</i>
RHINOCEROS	<i>Religious recluse.</i>
SCORPION	<i>Invincible knowledge.</i>
SERPENT	<i>Life; immortality.</i>
SPEAR	<i>Destructive power.</i>
SPIDER	<i>Slave of passion.</i>
SQUIRREL	<i>Averter of evil.</i>
STARS	<i>Divinity.</i>
SWASTIKA	<i>Good fortune.</i>
TURTLE	<i>Constancy.</i>
WHEEL	<i>Universe.</i>
WINGS	<i>Spontaneous motion.</i>
WOLF	<i>Destroying power.</i>

MEANINGS OF SOME OF THE PLACE-NAMES ASSOCIATED WITH RUGS

AKHISSAR	<i>White Citadel.</i>
BAGDAD	<i>Abode of Peace.</i>
BAKU	<i>Place of Winds.</i>
BELUCHISTAN	<i>Land of the Beluchis.</i>
BHAGULPORE	<i>Tiger City.</i>
BOKHARA	<i>Treasury of Sciences; the Noble.</i>
DECCAN	<i>The South Land.</i>
DERBENT	<i>Fortified Gate.</i>
FARS	<i>Land of the Farsi or Persians.</i>
FU-CHAU	<i>Happy City.</i>

MISCELLANEOUS INFORMATION

GILAN	<i>The Marshes.</i>
GULISTAN	<i>The Rose Garden.</i>
HAIDERABAD	<i>Gate of Salvation.</i>
HERAT	<i>The Pearl of Khorassan ; the Gate of India.</i>
ISLAMABAD	<i>Abode of Islam.</i>
ISPAHAN	<i>Place of Horses.</i>
JERUSALEM	<i>Heir of Peace.</i>
KANDAHAR	<i>Key of India.</i>
KARABAGH	<i>Country of the Sun.</i>
KARA DAGH	<i>Black Mountains.</i>
KELAT	<i>Castle.</i>
KHORASSAN	<i>Land of the Sun.</i>
KWATAH	<i>Citadel.</i>
MECCA	<i>The Heart of Islam ; the Holy City.</i>
MESHED	<i>Tomb of a Martyr.</i>
MIRZAPORE	<i>City of the Emir.</i>
NING-PO	<i>Peaceful Wave.</i>
PESHAWAR	<i>Advanced Fortress.</i>
SAMARKAND	<i>The Head of Islam.</i>
SHANG-HAI	<i>Approaching the Sea.</i>
SRINAGAR	<i>City of the Sun.</i>
TABRIZ	<i>Pinnacle of Islam.</i>
TEHERAN	<i>The Pure.</i>
YEZD	<i>City of Light ; City of Worship.</i>

RUGS: ORIENTAL AND OCCIDENTAL

GEOGRAPHICAL DATA

OWING to the variety of ways in which the names of Oriental localities are spelled when transliterated, it is extremely difficult to establish a standard of spelling. Many curious examples of this occur both on maps and in dictionaries. It is certainly confusing to open an atlas that is supposed to be an authority, and find that the name one seeks differs in spelling from that used in the atlas first consulted. Then by looking into dictionaries it is found that each of these has a different way of spelling the word sought. Then turning to a guide book of the country there will probably be found not only another combination of the letters, but also a conflict between the descriptive matter in the book and the map accompanying it. When books of travel are consulted, the embarrassment is still further increased.

After having accepted a mode of spelling geographical names for use in this volume, I propose in the pages that follow to assist the reader to locate the places mentioned, by assigning them to their respective countries, so that at a glance he may identify them. This classification will also be a key to the map.



MISCELLANEOUS INFORMATION

Occasionally the name of a place has been inserted which is not rug-producing, but only a mart for the selling of rugs. This has seemed advisable as the names are intimately associated with the rug industry.

LOCALITIES ARRANGED GEOGRAPHICALLY

Afghanistan

BALKH.	ISTALIF.
CHARIKAR.	JELALABAD.
GHAZNI (GÄZNE).	KABUL (CABUL, CABOOL).
GULISTAN.	KANDAHAR.
HERAT.	ZERNI.

Beluchistan

BAGH (BHAG).	MASTUNG.
BELAR.	ORMARAH.
GUNDAVA.	QUETTA (KWATAH).
JHALAWAN (DISTRICT).	RUSTAM KHAN.
KELAT.	SARAWAN (DISTRICT).
KHOZDAR.	SONMEANI.

Chinese Empire

CANTON.	SHAN-TUNG.
FU-CHAU.	SU-CHAU.
HANG-CHAU.	TIENT-SING.
KIANG-SU.	TSI-NAN.
NING-PO.	TSING-CHAU.
SHANG-HAI.	TSING-NING.

Province of East Turkestan

KARASHAR.	KUCHA.
KASHGAR.	YANGI-HISSAR.
KHOTAN.	YARKAND.

RUGS: ORIENTAL AND OCCIDENTAL

India

AGRA.	KASHMIR (STATE, BRITISH
AHMEDABAD.	INDIA).
ALLAHABAD.	KHYRPUR.
ALLEPPI.	KOHAT.
AMBALA (UMBALLA).	KOTAH.
AMRITSAR.	KUSHMORE.
BAHADAPUR (DISTRICT).	LAHORE.
BANGALORE.	LUCKNOW.
BARDWAN.	MADRAS.
BARELI (BAREILLY).	MALABAR (DISTRICT).
BELLARY.	MANDALAY.
BENARES.	MASULIPATAM.
BEYPUR.	MERUT.
BHAGALPUR (BOGLIPOOR).	MIRZAPUR.
BIJAPUR.	MORADABOD.
BOMBAY.	MULTAN.
CALCUTTA.	MURSHIDABAD.
CAWNPUR.	MYSORE.
CHANDA.	NAGPUR.
DECCAN (DEKKAN-PENINSULA).	NORTH ARCOT (DISTRICT).
DELHI.	PATNA.
ELLORE.	PESHAWAR.
GOA.	POONA (POONEH).
GORAKHPUR (GORUKPORE).	RAIPUR.
HAIDERABAD (HYDERABAD).	RAMPUR.
JABALPUR (JUBBULPORE-JUB-	RANGPUR.
BULPUR).	SERAMPUR.
JAIPUR (JEYPURE).	SHIKARPUR.
JALANDHAR (JULLINDER).	SRINAGAR (SERINUGGAR).
JAMMU (JAMU).	SURAT.
JODHPUR.	TANJORE.
	WARANGAL.

MISCELLANEOUS INFORMATION

Japan

AITSU-KEN.	SAKAI.
KIOTO.	TOKIO.

Persia

AARAGH (PROVINCE, WRITTEN KHORA-MABAD.	
IRAK ON MAPS).	KHORASSAN (KHORASAN,
ARDEBAL (DISTRICT).	PROVINCE).
ARDEBIL.	KHUZISTAN (ANCIENT SUSIANA,
ASTRABAD.	PROVINCE).
AZERBAIJAN (PROVINCE).	KIRMAN.
BIBIKABAD.	KUCHAN.
BIJAR.	KURDISTAN (THE PERSIAN
BIRJAND.	PORTION).
BUJNURD.	LAR.
BURUJIRD.	LARISTAN (PROVINCE).
BUSHIRE.	LURISTAN (PROVINCE).
ENZELI.	MAKRAN (MEKRAN, DISTRICT).
FARS (PROVINCE FARSISTAN).	MAZANDARAN.
FERAGHAN.	MEHRAN.
GASK.	MESHHEH.
GHILAN (GILAN).	NIRIZ.
HAMADAN.	NISHAPUR.
HEREZ.	OUSTRI-NAN.
IRAK-AJEMI (PROVINCE).	RAWAR.
ISPAHAN (MARKET ONLY).	RESHT.
KAIN (GHAIN, GHAYN).	SHIRAZ.
KARA DAGH (DISTRICT).	SHIRWAN.
KASHAN.	SHUSTER.
KERMANS SHAH (KERMANS HA-	SINNA.
HAN).	SIRAB.
KHONSAR.	SULTANABAD.

RUGS: ORIENTAL AND OCCIDENTAL

TABRIZ (TABRIEZ).	YEZD.
TEHERAN (MARKET ONLY).	ZARAND.

Russian Empire

ASTRAKHAN.	ERIVAN.
BAKU.	KARS.
BATUM.	KAZAN.
DAGHESTAN (GOVERNMENT).	SHUSHU.
DERBENT.	
CAUCASIA {	TRANSCAUCASIA {
DAGHESTAN.	KARABAGH.
DERBENT.	SHEMAKHA.
KUBA.	SHIRVAN.

Central Asia

BOKHARA.	KHIVA.
FERGHANA (PROVINCE).	KOKAND (KHOKAND).
HISSAR.	SAMARKAND.

Turkey in Asia

REGIONS

ARABIA.	KURDISTAN.
ARMENIA.	MESOPOTAMIA.
ASIA MINOR OR ANATOLIA.	SYRIA.

DISTRICTS AND TOWNS

ADANA.	ASUM.
ADIAMAN (ADIIYEMEN).	BAGDAD (BAGHDAD), SHIPPING
AFIUM-KARA-HISSAR.	PORT.
AIDIN.	BEHESNE.
AKHISSAR.	BEIRUT.
AKSHEHR.	BERGAMA (BERGAMO, PER-
ALEPPO.	GAMO).
ALTUN.	BRUSA (BROUSSA).
ANATOLIA (DISTRICT).	CÆSAREA.

MISCELLANEOUS INFORMATION

CHAL.	KHORSABAD.
CONSTANTINOPLE.	KIR-SHEHR.
DEMIRDJI.	KONIEH.
DIARBEKIR.	KULAH (KOULA, COULA).
EL-HOSN.	KUTAHIA (KUTAI, KUTAYAH).
ERZERUM.	LADIK.
FAKEH.	MARASH (MARESH).
GEMERIK.	MECCA.
GHIORDES (GORDIS, QOURDES, MEDINA.	
GÜRDIZ, ANCIENT GORDUS).	MILASSA (MELASSO, MYLASSO).
HAIDAMoor.	MOSUL (MOUSSUL).
HAKKAM.	OUCHAK (USHAK, OUSHAK).
HAYZOR.	SAFIETA.
HEREKE.	SAVAS.
HISSAR.	SHARJAH (SHARKAH).
HOMS.	SHIRVAN.
HOSSU.	SMYRNA (MART ONLY).
JERUSALEM.	SOHAR.
KAISARIEH (CÆSAREA).	SPARTA.
KARAHISSAR.	TREBIZOND.
KARAMAN.	URFA (OORFA).
KERKUK.	ZILEH (ZILLEH, ZELI).

Africa

CAIRO (MART).	MISRATAH.
KAIROUAN (the only place	TAJURA.
where the genuine Tunisian	TRIPOLI.
rugs are now made).	

France

AUBUSSON.	TOURCOING.
BEAUVAIS.	TOURNAY.
ROUBAIX.	

RUGS: ORIENTAL AND OCCIDENTAL

Greece

AGRINION.

RACHOVA.

OWEPHISSA.

LOCALITIES ARRANGED ALPHABETICALLY

A

AARAGH, PERSIA.	ALLAHABAD, INDIA.
ADANA, TURKEY IN ASIA.	ALLEPPI, INDIA.
ADIAMAN, TURKEY IN ASIA.	ALTUN, TURKEY IN ASIA.
AFIUM-KARA-HISSAR, TURKEY IN ASIA.	AMABALA, INDIA.
AGRA, INDIA.	AMRITSAR, INDIA.
AGRINION, GREECE.	ANATOLIA, TURKEY IN ASIA.
AHMEDABAD, INDIA.	ARDEBAL, PERSIA.
AIDIN, TURKEY IN ASIA.	ARDEBIL, PERSIA.
AITSI-KEN, JAPAN.	ASIUM, TURKEY IN ASIA.
AKHISSAR, TURKEY IN ASIA.	ASTRABAD, PERSIA.
AKSHEHR, TURKEY IN ASIA.	ASTRAKAN, RUSSIA IN ASIA.
ALEPPO, TURKEY IN ASIA.	AUBUSSON, FRANCE.
	AZERBAIJAN, PERSIA.

B

BAGDAD, TURKEY IN ASIA.	BEHESNE, TURKEY IN ASIA.
BAGH, BELUCHISTAN.	BEIRUT, TURKEY IN ASIA.
BAHADAPUR, INDIA.	BELAR, BELUCHISTAN.
BAKU, RUSSIA IN ASIA.	BELLARY, INDIA.
BALKH, AFGHANISTAN.	BENARES, INDIA.
BANGALORE, INDIA.	BERGAMA, TURKEY IN ASIA.
BARDWAN, INDIA.	BEYPUR, INDIA.
BATUM, RUSSIA IN ASIA.	BHAGALPUR, INDIA.
BEAUVAIS, FRANCE.	BIBIKABAD, PERSIA.

MISCELLANEOUS INFORMATION

BIJAPUR, INDIA.
BIJAR, PERSIA.
BIRJAND, PERSIA.
BOKHARA, CENTRAL ASIA.
BOMBAY, INDIA.

BRUSA, TURKEY IN ASIA.
BUJNURD, PERSIA.
BURUJIRD, PERSIA.
BUSHIRE, PERSIA.

C

CAIRO, EGYPT.
CALCUTTA, INDIA.
CANTON, CHINESE EMPIRE.

CAWNPUR, INDIA.
CHANDA, INDIA.
CHARIKAR, AFGHANISTAN.

D

DAGHESTAN, RUSSIA IN ASIA.
DECCAN, INDIA.
DELHI, INDIA.

DEMIRDJI, TURKEY IN ASIA.
DERBENT, RUSSIA IN ASIA.
DIABEKIR, TURKEY IN ASIA.

E

EL-HOSN, TURKEY IN ASIA.
ELLORE, INDIA.
ENZELI, PERSIA.

ERIVAN, RUSSIA IN ASIA.
ERZERUM, TURKEY IN ASIA.

F

FAKEH, TURKEY IN ASIA.
FARS, PERSIA.

FERAGHAN, PERSIA.
FU-CHAN, CHINESE EMPIRE.

G

GEMERIK, TURKEY IN ASIA.
GHAZNI, AFGHANISTAN.
GHILAN, PERSIA,
GHIORDES, TURKEY IN ASIA.

GOA, INDIA.
GORAKHPUR, INDIA.
GULISTAN, AFGHANISTAN.
GUNDAVA, BELUCHISTAN.

H

HAIDAMoor, TURKEY IN ASIA.
HAIDERABAD, INDIA.
HAKKAM, TURKEY IN ASIA.

HAMADAM, PERSIA.
HANG-CHAU, CHINESE EM-
PIRE.

RUGS: ORIENTAL AND OCCIDENTAL

HAYZOR, TURKEY IN ASIA.
HERAT, AFGHANISTAN.
HEREZ, PERSIA.

HISSAN, CENTRAL ASIA.
HISSAR, TURKEY IN ASIA.
HOMS, TURKEY IN ASIA.

I

IRAK-AJEMI, PERSIA.
ISPAHAN, PERSIA.

ISTALIF, AFGHANISTAN.

J

JABALPUR, INDIA.
JAIPUR, INDIA.
JALANDHAR, INDIA.
JAMMU, INDIA.

JELALABAD, AFGHANISTAN.
JERUSALEM, TURKEY IN ASIA.
JHALAWAN, BELUCHISTAN.
JOHPUR, INDIA.

K

KABUL, AFGHANISTAN.
KAIN, PERSIA.
KAIROUAN, AFRICA.
KAISARIEH, TURKEY IN ASIA.
KANDAHAR, AFGHANISTAN.
KARABAGH, RUSSIA IN ASIA.
KARAHISSAR, TURKEY IN ASIA.
KARAMAN, TURKEY IN ASIA.
KARASHAR, EAST TURKESTAN.
KARS, RUSSIA IN ASIA.
KASHAN, PERSIA.
KASHGAR, EAST TURKESTAN.
KASHMIR, INDIA.
KAZAN, RUSSIA IN ASIA.
KELAT, BELUCHISTAN.
KERKUK, TURKEY IN ASIA.
KERMANSIAH, PERSIA.
KHIVA, CENTRAL ASIA.
KHONSAR, PERSIA.
KHORA-MABAD, PERSIA.

KHORASSAN, PERSIA.
KHORSABAD, TURKEY IN ASIA.
KHOZDAR, BELUCHISTAN.
KHUZISTAN, PERSIA.
KHYRPUR, INDIA.
KIANG-SU, CHINESE EMPIRE.
KIOTO, JAPAN.
KIRMAN, PERSIA.
KIR-SHEHR, TURKEY IN ASIA.
KOHAT, INDIA.
KOKAND, CENTRAL ASIA.
KONIEH, TURKEY IN ASIA.
KOTAH, INDIA.
KUBA, RUSSIA IN ASIA.
KUCHA, EAST TURKESTAN.
KULAH, TURKEY IN ASIA.
KURDISTAN, PERSIA.
KUSHMORE, INDIA.
KUTAHIA, TURKEY IN ASIA.

MISCELLANEOUS INFORMATION

L

LADIK, TURKEY IN ASIA.
LAHORE, INDIA.
LAR, PERSIA.

LARISTAN, PERSIA.
LUCKNOW, INDIA.
LURISTAN, PERSIA.

M

MAKRAN, PERSIA.
MALABAR, INDIA.
MARASH, TURKEY IN ASIA.
MASTUNG, BELUCHISTAN.
MASULIPATAM, INDIA.
MAZANDARAN, PERSIA.
MECCA, TURKEY IN ASIA.
MEDINA, TURKEY IN ASIA.
MEHRAN, PERSIA.
MERUT, INDIA.

MESHHEH, PERSIA.
MILASSA, TURKEY IN ASIA.
MIRZAPUR, INDIA.
MISRATAH, AFRICA.
MOSUL, TURKEY IN ASIA.
MUJUR, TURKEY IN ASIA.
MULTAN, INDIA.
MURSHIDABAD, INDIA.
MYSORE, INDIA.

N

NAGPUR, INDIA.
NING-PO, CHINESE EMPIRE.
NIRIZ, PERSIA.

NISHAPUR, PERSIA.
NORTH ARCOT, INDIA.

O

ORMARAH, BELUCHISTAN.
OUCHAK, TURKEY IN ASIA.

OUSTRI-NAN, PERSIA.
OWEPHISSA, GREECE.

P

PATNA, INDIA.

PESHAWAR, INDIA.

POONA, INDIA.

Q

QUETTA, BELUCHISTAN.

R

RACHOVA, GREECE.
RAMPUR, INDIA.
RANGPUR, INDIA.

RESHT, PERSIA.
RUSTAM KHAN, BELUCHISTAN.

RUGS: ORIENTAL AND OCCIDENTAL

S

SAFITA, TURKEY IN ASIA.	SHIRWAN, PERSIA.
SAKAI, JAPAN.	SHUSHA, RUSSIA IN ASIA.
SAMARKAND, CENTRAL ASIA.	SHUSTER, PERSIA.
SARAKHS, PERSIA.	SINNA, PERSIA.
SARAWAN, BELUCHISTAN.	SIRAB, PERSIA.
SERAMPUR, INDIA.	SIVAS, TURKEY IN ASIA.
SHANG-HAI, CHINESE EMPIRE.	SMYRNA, TURKEY IN ASIA.
SHAN-TUNG, CHINESE EMPIRE.	SOHAR, TURKEY IN ASIA.
SHARJAH, TURKEY IN ASIA.	SONMEANI, BELUCHISTAN.
SHEMAKHA, RUSSIA IN ASIA.	SRINAGAR, INDIA.
SHIKARPUR, INDIA.	SU-CHAU, CHINESE EMPIRE.
SHIRAZ, PERSIA.	SULTANABAD, PERSIA.
SHIRVAN, RUSSIA IN ASIA.	SURAT, INDIA.
SHIRVAN, TURKEY IN ASIA.	

T

TABRIZ, PERSIA.	TOURNAY, FRANCE.
TAJURA, AFRICA.	TREBIZOND, TURKEY IN ASIA.
TANJORE, INDIA.	TRIPOLI, AFRICA.
TEHERAN, PERSIA.	TSI-NAN, CHINESE EMPIRE.
TIENT-SING, CHINESE EMPIRE.	TSING-CHAU, CHINESE EMPIRE.
TOKIO, JAPAN.	TSING-NING, CHINESE EMPIRE.
TOURCOING, FRANCE.	

U

URFA, TURKEY IN ASIA.

W

WARANGAL, INDIA.

Y

YARKAND, EAST TURKESTAN. YEZD, PERSIA.

Z

ZARAND, PERSIA. ZILEH, TURKEY IN ASIA.
ZERNI, AFGHANISTAN.

MISCELLANEOUS INFORMATION

LIST OF AUTHORITIES

- ALLEN, J. ROWELLY: *Early Christian Symbolism.*
American Journal of Archæology.
- ASHENHURST, THOMAS R.: *Design in Textile Fabrics.*
- AUBER, M. L., ABBE: *Bible Myths.*
- BABELON, ERNEST: *Manual of Oriental Antiquities.*
- BALL, J. DYER: *Things Chinese.*
- BIRDWOOD, SIR GEORGE C.: *The Industrial Arts of India.*
- BISHOP, MRS. ISABELLA L. BIRD: *Journeys in Persia and Kurdistan.*
- BISHOP, MRS. ISABELLA L. BIRD: *Unbeaten Tracks in Japan.*
- BLACKIE, C.: *Dictionary of Place Names.*
- BODE, WILHELM: *Vorderasiatische Knüpfteppiche.*
Bonnicks's Egyptian Belief and Modern Thought.
- BRUMMER, MARTIN: *Egypt, Three Essays on the History, Art, and Religion.*
- BUDGE, E. A. WALLIS: *The Mummy Badge.*
Century Atlas, The.
Century Dictionary, The.
Chambers's Encyclopædia.
- CLARKE, SIR C. PURDON: *Oriental Carpets.* (English Edition.
Published by the Imperial and Royal Austrian Commercial
Museum. Vienna, 1892.)
Constable's Hand Atlas of India.
- COXON, HERBERT: *Oriental Carpets.*
- CURSON, HON. GEORGE N.: *Persia and the Persian Question.*
- DAVIS AND COBERN: *Ancient Egypt.*
- DENNY, M. B.: *The Folk Lore of China.*

RUGS: ORIENTAL AND OCCIDENTAL

- DRESSER, CHARLES: *Carpets*.
- EDWARDS, AMELIA: *Third Lecture, Pharaohs, Fellahs, and Explorers*.
- ELKINS, JOSEPH, D.D.: *Ancient Symbolism among the Chinese*.
- ELY, TALFOURD: *Manual of Archæology*.
Emmaus's Life in Ancient Egypt.
- EVANS, E. P.: *Animal Symbolism in Ecclesiastical Architecture*.
- FABER, GEORGE STANLEY: *Origin of Pagan Idolatry*.
- FERGUSON, JAMES: *Tree and Serpent Worship*.
- FUSENBETH, F. C., D.D.: *Emblems of Saints*.
- GOODYEAR, WILLIAM H.: *The Grammar of the Lotus*.
- HEDIN, SVEN: *Through Asia*.
- HULME, F. EDWARD: *Symbolism in Christian Art*.
Iconographic Encyclopædia of the Arts and Sciences.
- INMAN, THOMAS, M.D.: *Ancient Faiths*.
- JAMES, A. G. F. ELIOT: *Indian Industries*.
- JONES, OWEN: *The Grammar of Ornament*.
Journal of the Society of Arts.
- KARABACEK, DR. JOSEPH: *Die Persische Nadelmalerei*.
- KNIGHT, RICHARD PAYNE: *The Symbolical Language of Ancient Art and Mythology*.
- LANDOR, A. HENRY SAVAGE: *In the Forbidden Land*.
- LAYARD, AUSTEN HENRY: *Discoveries in the Ruins of Nineveh*.
- LAYARD, AUSTEN HENRY: *Nineveh and Babylon*.
- LAYARD, AUSTEN HENRY: *Nineveh and Its Remains*.
- LENORMANT, FRANÇOIS AND CHEVALIER, CHARLES: *Manual of the Ancient History of the East*.
- LESSING, JULIUS: *Oriental Carpets*.
- LÜBKE, WILHELM: *History of Ancient Art*.
- MALCOM, SIR JOHN: *History of Persia*.
- MARTIN, F. R.: *History of Oriental Carpets Before 1899*.
- MARVIN, CHARLES: *Merv, the Queen of the World*.
- MASPERO, GASTON C. CHARLES: *Manual of Egyptian Archæology*.

MISCELLANEOUS INFORMATION

- MASPERO, GASTON C. CHARLES: *Dawn of Civilization.*
Meyer's Handbook of Ornament.
- MUMFORD, JOHN KIMBERLY: *Oriental Rugs.*
- MÜNTZ, EUGENE: *A Short History of Tapestry.*
- O'DAGREE, H. EUGENE: *Les Symbols Antiques.*
- O'DONOVAN, EDMUND: *The Merv Oasis.*
- PERROT, GEORGES AND CHIPIEZ, CHARLES: *History of Art in Ancient Egypt.*
- PERROT, GEORGES AND CHIPIEZ, CHARLES: *History of Art in Chaldæa and Assyria.*
- PETRIE, WILLIAM MATTHEWS FLINDERS: *Decorative Art.*
- PETRIE, WILLIAM MATTHEWS FLINDERS: *Ten Years' Digging in Egypt.*
- PHILLIPS, G.: *British Manufactures and Industries.*
- RACINET, M. A.: *L'Ornement Polychrome.*
- REBER, FRANZ VON: *History of Ancient Art.*
- RECLUS, ELISIE: *The Earth and Its Inhabitants.*
- Redgrave's Manual of Design.*
- RENOUF, P. LEPAGE: *Religion of Ancient Egypt.*
- RIEGL, DR. ALOIS: *Altorientalische Teppiche.*
- ROBINSON, VINCENT: *Eastern Carpets.*
- RYAN, CHARLES: *Egyptian Art.*
- SAYCE, ARCHIBALD HENRY, LL.D.: *Babylonians and Assyrians. Sculpture, Manual of.* Paris.
- SHARPE, SAMUEL: *Mythology and Egyptian Christianity.*
- SHELLEY, G. E.: *Birds of Egypt.*
- Smith's Greek and Roman Antiquities.*
- SMITH, Major R. MURDOCK, R. E.: *Persian Art.*
- Smith's Religion of the Semites.*
- Southesk's Origin of Pictish Symbolism.*
- Spon's Encyclopædia of the Industrial Arts, Manufactures, and Raw Commercial Products.* (Edited by Charles G.W. Lock.)

RUGS: ORIENTAL AND OCCIDENTAL

- STRICKLAND, AGNES: *Lives of the Queens of England.*
STUART, H. VILLIERS: *Egypt after the War.*
SYKES, ELLA C.: *Through Persia on a Side Saddle.*
Thompson's Paper on Beast and Bird in Ancient Symbolism.
(Trans. Roy. Soc., Edinburgh.)
Twining's Symbols of Early Christian Art.
VÁMBÉRY, ARMINIUS: *History of Bokhara.*
VAN DYKE, JOHN CHARLES: *History of Painting.*
WATSON, DR. FORBES: *The Textile Manufactures and Costumes*
of the People of India.
WEALE, JOHN: *Quarterly Papers on Architecture.*
WESTROFF, HODDER M., and WAKE, CHARLES STANILAND:
Ancient Symbol Worship.
Westwood's Illumination.
WHEELER, SAMUEL GREEN: *Persia and the Persians.*
WILKINSON, SIR J. GARDNER: *The Ancient Egyptians.*
WILLIAMS, S. WELLS: *The Middle Kingdom.*
WILSON, THE REV. SAMUEL GRAHAM, M. A.: *Persian Life and*
Customs.
WINKLEMAN, JOHANN JOACHIM: *History of Art among the*
Greeks.
WYATT, M. DIGBY: *Industrial Arts of the Nineteenth Century.*
ZERFFI, G. C.: *A Manual of the Historical Development of Art.*

SUPPLEMENT

1927

PERSIAN RUGS

The antique rugs of Ispahan (so called), are now known by most authorities as Herats. From investigations this seems to be a fact, at any rate, the rugs are magnificent, extremely rare and very valuable. The modern Ispahan rug is absolutely not in the same category with the older rugs. The texture of the former is, however, firm and durable. There are several interesting Herat rugs in the Imperial Museum at Constantinople. They appear to have been woven in the sixteenth century.

Garden rugs. There is a romantic fascination about this rare type of rugs. The usual pattern is laid out in squares and oblongs representing flower beds, pools, paths and streams flowing into channels. The pattern is said to have its origin in a woven textile made for Chosroe I, Sassanian king of Persia in the sixth century, and which, according to the story, was designed to bring into the palace the spirit of flowering summer and to represent a royal pleasure park. The ground is said to have been of gold thread and the leaves of silk. Inlays of precious stones and crystal enhanced the beautiful texture.

In the year 637 the Arabs plundered the palace and took possession of the rug, the beauty of which made such an impression upon them that descriptions of it were written in their chronicles. Moreover, the tradition of its decorative scheme was so poignant a thousand years after its capture as to suggest to the Persians a revival of the same design in a true knotted rug. The excellent technique of the rare existing examples of this type of rugs sets it apart from other rugs composed like it of small fields.

Notable among these early Garden rugs is one which belongs to the late sixteenth century and now owned by Dr. Figdor of Vienna. Another, equally fine, has arrived in the United States by way of Constantinople and Berlin, where it was in the collection of Wagner, the antiquarian.

The Figdor rug is of wool with a silk warp. Gold and silver threads are interwoven, particularly in the flower and animal forms, in a manner to suggest the texture of the so-called Polish rugs. Birds and flowers are extraordinarily vibrant in color. A four-legged creature defying

RUGS: ORIENTAL AND OCCIDENTAL

classification moves under the shade of trees. A slender border framed by two plain bands is filled with delicate tracery of vines broken by flower forms and lancet leaves. It is not, however, laid out in the squares characteristic of Garden rugs, though it has the typical canals.

The carpet from the Wagner collection can not be ascribed to an earlier period than 1640 and may be Kirman work. It shows a central pool from which issue four canals and animals playing among the surrounding trees.

Later rugs of this type are stiffer in design. Good examples are those in the Kaiser Friedrich Museum, the one formerly in the collection of Mr. Lamm at Naesby, Sweden, and others loaned to the Metropolitan Museum of Art and to the Frankfort Museum of Decorative Art. The Lamm rug seems to have been produced in the seventeenth or possibly the eighteenth century and may be Shiraz work.

In the Art Journal in 1891 Sir Martin Conway describes a rug once in the possession of Sir Sidney Colvin and which since has disappeared. He thinks its original length must have been eighteen or twenty-seven feet and the predominant color was blue, shown in the paths and border. In the center was a pavilion from which emerged four streams. At the corners were four reclining trees. Parterres of flowers, branches of trees, and birds gave beauty and naïveté to the field. The wide border has a design of cyprus trees, shrubs and billing birds.

Sir Martin also describes in the Burlington Magazine a similar rug which is woven of wool throughout and is thirty-one feet long by twelve feet three inches wide. In the center is a pool or tank and along each side are four pavilions with four trees at right-angles to them. The border, composed like that of the Colvin rug, of cyprus trees and flowers surrounds the two principal canals, forming a cross through the middle of the carpet. This example and that of the Lamm rug are, according to Sir Martin, the only complete survivals of this type known today.

Vase rugs show a certain type of floral pattern which uses blossoms en masse or single flowers set in vases. Their forms and colors date them in the second half of the sixteenth century, the Sefevi period, during which knotting was in the state of highest perfection. The blossoms often are of great delicacy and are arranged with symmetrical precision. Diagonal vines, frequently so slim in outline and inconspicuous in color

as to escape notice, make a background for the vase motifs, which may be surrounded by flower forms of an angular and much conventionalized type. The borders, usually are narrow, but when wider they remind one of the borders of animal rugs to which, undoubtedly, they are related. Such carpets are to be seen in the museums and collections of England, Germany, Austria and Sweden. England is particularly rich in them.

A rug in the Ottoman Museum, Constantinople, is of special magnificence. The field is filled with diamond forms, each showing a different floral design. The Leipzig Museum of Decorative Art has a vase rug into which animals are introduced, which is interesting as pointing again to the relationship between these types.

TURKISH RUGS

When Paris Bordoni (1500-1571) painted the beautiful ceremonial picture in the Academy in Venice he used an Ouchak for the center of the steps. This is positive proof, if other be wanting, of the age of such a rug. Furthermore, Van Dyke painted such a carpet between the years 1620 and 1625 when he lived in Genoa.

For many years this type of rug was called Hispano-Moresque and the colors are indeed Spanish, splendid old reds, yellows and blues, but authorities have proved that it was made in the place whose name it bears. It is supposed that the large ones were woven for reigning monarchs, especially for those of Spain.

The designs contain large stars, mostly in blue, with yellow outlines on warm yellow ground. The stars of varying sizes and shapes are spread over the ground in an irregular way so that they often are cut by the border. The thin lines with which the geometrical designs are executed and also the floral designs when they occur suggest pen drawings. In the sixteenth century Chinese motifs occur in them, such as the cloud band, symbol of eternity, and the Tschì which represents the sacred sponge and is frequently found in Chinese works of the Ming dynasty.

CAUCASIAN RUGS

Kuba rugs are a development of the early Armenian rugs. They were woven in the seventeenth and eighteenth centuries. The weaving

RUGS: ORIENTAL AND OCCIDENTAL

is firm and fine, and the designs interesting. Arranged on a field which is generally of deep blue is seen the diamond design and also palmettes and small octagon and arabesque forms. Also small conventionalized forms of tree and leaf are symmetrically placed. The colors are usually blue, ivory, deep red, old rose, light green, and so dark a brown that it looks black. A Kuba rug that I own has all the colors mentioned and a border of the well-known cufic design with narrower borders of vines and also of rosettes.

CHINESE RUGS

Instead of adhering to original patterns several firms employing designers have added to the original motifs and sometimes in the border of a modern Chinese rug will be seen mixed motifs. Sometimes one part of a design will be taken from one border and part from another and these two will be so arranged as to form a so-called Chinese border.

These rugs are made in factories in China and also in Asia Minor, Austria, India and other countries, and I have actually seen them being woven in New York City.

The Great War bottled up the Dardanelles and prevented the exportation of Oriental rugs from Persia and Turkey but following the Armistice rugs from the Far East flooded the market. Before the war Chinese rugs and rugs from Chinese Turkestan were just beginning to be popular, and when other rugs were no longer to be found the Chinese captured the market. They lend themselves to many rooms where the strong colors of the modern Near-Eastern rug might not be harmonious. But as with all incoming carpets they also, when too strong in color, are dyed to please our taste by having a certain preparation put into the dye vats that softens the texture as well as the color.

The modern Chinese rugs come principally from Peking and Tien-tsin. In Nanking rugs similar to those of Peking are made. Several provinces in China make rugs coarser in quality than those made in Peking and Tien-tsin, but with interesting, if crude, designs. Mongolia and Manchuria (especially Mukden) now send many rugs to the United States and other foreign countries. The demand from all countries, the United States in particular, is responsible for the development of Chinese rugmaking to a large industry. In Shanghai a Chinese rug factory has been purchased by men from the United States who expect to enlarge

1927 SUPPLEMENT

and improve the output. No rugs from this factory are sold in China, either to the public or to buyers for American or any other foreign trade. Instead, the rugs are shipped to the United States and at stated intervals sold at auction to different buyers for the retail trade.

ANIMAL RUGS

Animal rugs are to be found in rather large numbers in the museums and private collections. Human figures seldom are depicted and the animal forms do not point to the chase. They were woven in Persia and also in India and are usually of silk with silver threads interwoven, but some are of wool.

Perhaps the most perfectly preserved specimen is in the Poldi-Pezzoli Museum in Milan. In material, in technical perfection and in the soft shining texture of its wool it is exceptional. It is rich in Chinese motifs, such as flying clouds, cranes and the Tschì. Persian genii are also included in the designs.

In the Stieglitz Museum in Leningrad is a magnificent specimen of an animal rug. It is of silk and the center of the field has a round medallion with curved edges. The corner areas hold vines and playing among them are falcons and various birds. An interesting border is formed of inscriptions in cartouches.

Dr. F. Sarre in his "Rugs of the Middle Ages From Asia Minor and Spain" gives a picture and a description of an animal rug of the first half of the fifteenth century. It is a fragment which was found by Dr. Bode in Rome. Two rigidly-conventionalized animal figures are represented in each diamond-shaped lozenge, and seem to show the oft-recurring Chinese motif of the struggle between dragon and phoenix.

SPANISH RUGS

The earliest allusion to Spanish rugs was made by Edrisi, the Mohammedan geographer of the twelfth century. One of the oldest Spanish rugs in existence, belonging to the thirteenth or fourteenth century, is described at length by Dr. Sarre in his book and is used by him to show the relationship of Spanish design to that of Asia Minor, and the persistence through several centuries of certain patterns and of a distinctly Spanish technique of knotting.

RUGS: ORIENTAL AND OCCIDENTAL

This carpet, called the Castle Carpet, is only a fragment but Dr. Bode believes it to have been at least four times as long as it was wide. The field is pale pink, the borders dull blue and the colors in the pattern are not particularly harmonious. A slim tree, more like a pole, occupies the center of the field and stretches out gaunt horizontal arms from which hang castles like rigid blossoms. These form medallions of considerable size and frequency and are identical with one another. They have high pointed roofs and ornate walls. Around the narrow border runs a continuous repetition of the sentence, "There is no God but God," written in the long strokes characteristic of Spanish orthography.

Its woolen threads are not, as is usual in rugs of the Orient, knotted in a continuous column over the same warp threads, but alternate, each row leaving every other thread untied. The result is a particularly sharp pattern. The method is characteristic of rug work in Europe in the Middle Ages.

Dr. Sarre says that the pattern of this rug had its origin in the Oriental Tree of Life which originated about the year 600 and which is Islamic. It appears in Spain in 961 on a column in the Mosque of Cordova, where are found also other features present in the design of this carpet and of allied work in later centuries. In fact Spanish rugs constantly rehearse the elements of design present in the Castle Carpet.

In the inventory of Princess Juana on her marriage to the Count of Foix in 1392 five carpets made of blue wool with a design of lions, horses and doves are mentioned. In the inventory of Kaiser Karl V are listed carpets from Alcares and in the records of the Monks of the Escorial allusion is made in 1575 to an Alcares carpet given to Philip II. Countess d'Aulnay says that the dais of the throne room in the palace of Charles II was covered with wondrous carpets.

About 1724 carpets in the Turkish style were made in Spain under the direction of Cornelius Vandergoten. Fine specimens are found in the Victoria and Albert Museum, South Kensington. These are mostly of the seventeenth century, although some belong to the sixteenth. One is knotted of colored wools on woolen warps. On its deep blue ground are three medallions, every one of which has a well-balanced arrangement of small flowers and leaves on a slender stalk. The border design is formed of vases of flowers and monsters, ending in leaf-like scrolls.

1927 SUPPLEMENT

The length is nine feet ten and a half inches by five feet three and a half inches.

Antique Spanish rugs are fine and firm in texture. The so-called Gothic Sanctuary Rugs are both very attractive and very rare. The field is of soft yellow relieved by rich blue. Sometimes a deep red adds a harmonious contrast. The designs are restful and simple. Many of them are suggestive of church emblems. The lily, at times as a single flower and again in a vase is seen, and frequently a wine glass or chalice. There are graceful arabesque forms with running vines, crosses and scrolls. Fine specimens are seen in the Palace of the Escorial and in the Prado Gallery in Madrid.

In the Province of Granada is the district of Alpujarra and probably the rugs bearing the name of this district were made there. An Alpujarra rug that I owned was on a dark blue field with ivory flower-filled vases arranged symmetrically over the field. In a serrated square center was an amusing little duck-like figure with webbed feet and a spreading tail, worked in red. In the four corners were small ducks. The wide border had harmoniously-arranged plants, alternating with daisies on stalks which, however, had no blossoms. Above the ivory serrated lines of the border were three lively-looking animals resembling unicorns, and below the top border were the same creatures. Between every one was an eight-pointed star, and there were stars and small trees and ducks in the field. The Alpujarra is again being woven in Granada, and we are now seeing with increasing frequency these specimens of Spanish loom work.

FINNISH RUGS

Finnish rugs have been woven for many years. One in the Victoria and Albert Museum, South Kensington, bears the date, 1799. The warp is in white flax and the weft in fine white wool. The colors are green, blue, white, red and yellow on a field so dark it may be called black.

SARDINIAN RUGS

Rugs have been made for generations on the Island of Sardinia, which to an extent unparalleled elsewhere has retained her traditional arts uncorrupted and unchanged. The descendants of the first Sardinian

RUGS: ORIENTAL AND OCCIDENTAL

weavers sit before the ancient looms weaving on new warps of wool the same patterns that have taken form over and over again under the fingers of succeeding generations. Certain patterns are distinctive of certain families, but in all of them occur birds, animals and geometric figures.

Vegetable dyes survive in this medieval island. Black, yellow and red supply the color schemes. The rugs are exceedingly simple but so aloof and uninfluenced by the culture of the world, which has been content to let Sardinia alone in her yet feudal civilization. Sardinian rugs are indeed romantic and unique.

INDEX

INDEX

A

- Aaragh, value of rug trade, 56; spelling, 167, 170.
- Abbas, Shah, 53; rugs woven during reign of, 62; *see* Shah Abbas design.
- Abenákee rugs, 143, 144.
- Acanthus forms employed by Morris, 139.
- Adana, 71, 168, 170.
- Adiaman, 168, 170.
- Adiyemen, 168.
- Afghan rugs, 102.
- Afghan-Turkomans, 95.
- Afghan-Turkestan, 95 (and plate).
- Afghanistan place-names, 165.
- Afghanistan rugs, 95 (and plate), 96, 100.
- Afium-Kara-hissar, 168, 170.
- African place-names, 169.
- Agra, 166, 170.
- Agra rugs, 90.
- Agrinion, 170.
- Ahmedabad, 166, 170.
- Aidin, 168, 170.
- Ainos, their method of weaving, 24.
- Aitsi-ken, 167, 170.
- Akbar, Emperor, 87.
- Akhissar rugs, 74, 80; meaning, 162; spelling, 168, 170.
- Akshehr, 168, 170.
- Albee, Mrs. Helen R., 143, 144.
- Aleppo, 168, 170.
- Alexander the Great, rug-weaving in time of, 53.
- Algiers, Public Museum, at, 135.
- Alizarin (red coloring matter), 44.
- Allahabad, 166, 170.
- Allahabad rugs, 90.
- Allen, J. Rowelly, 175.
- Alleppi, 166, 170.
- Alpujarra, District of, 187.
- "Altorientalische Teppiche," Riegl, 177.
- Altun, 168, 170.
- Amabala, 170.
- Ambala, 166.
- American interests in India, 35; in Ouchak, 81; in Amritsar, 90.
- American Journal of Archaeology*, 175.
- American rug-weaving, 24.
- Ames, late Gov., rug owned by, 113.
- Amritsar, 78 (plate), 166, 170.
- Amritsar rugs, 90.
- Anatolia, 74, 168, 170.
- Anatolian mats, 74.
- Anatolian rugs, 74, 79, 122 (and plate).
- "Ancient Egypt," Davis and Cobern, 175.
- "Ancient Egyptians, The," Wilkinson, 178.
- "Ancient Faiths," Inman, 176.
- "Ancient Symbol Worship," Westroff and Wake, 178.
- "Ancient Symbolism among the Chinese," Elkins, 176.
- Anemone, symbolism of, 161.
- Angora goat's hair, 30.

INDEX

- Angora province, 77.
 Aniline dyes, 44, 46, 134.
 Animal forms, not allowed by Moham-
 medan religion, 37; employed by
 Shiah sect and certain others, 38; in
 Jaipur rugs, 91; in Chinese rugs,
 114; symbolism of, 156.
 Animal rugs, 185.
 "Animal Symbolism in Ecclesiastical
 Architecture," Evans, 176.
 Antique Spanish rugs, 185.
 "Appalachian America," 146.
 Arabesque design, 43, 135.
 Arabian place-names, 168.
 Arabian rug, 70 (plate).
 Ardebil (District), 167, 170.
 Ardebil rug in South Kensington Mu-
 seum, 36, 154; spelling, 167, 170.
 Armenia, 168.
 Armenian Christian weavers, 71.
 Armenian rugs, 183.
 Arrian, quoted, 45.
 Ashenhurst, Thomas R., 175.
 Ashkabad, 98.
 Asia Minor, 168.
 Asiatic Turkey produces madder, 44.
 Asium, 168, 170.
 Asps, symbolism of, 158.
 Ass, symbolism of, 159.
 Association for the Education of Poor
 Women, Athens, 133.
 Assyrian rug-weaving, 19, 88.
 Astrabad, 103, 126, 167, 170.
 Astrakan, 170.
 Astrakhan, 168.
 Athens rug industry, 133.
 Auber, Abbé M. L., 175.
 Aubusson rug manufactory, 142, 169,
 170.
 Austria, rug-weaving in, 142.
 Austrian Imperial House, owner of
 hunting rug, 128.
 Authorities consulted, 175-178.
 Awnings and floor-coverings, ancient,
 19.
 Aylauts, nomadic weavers of Kara
 Dagh rugs, 63.
 Azerbaijan province, 62, 69, 167, 170.
 Azerbijan district, 58.

B

- Babelon, Ernest, 175.
 Babylon, fall of, 19.
 Babylonian rug-weaving, 19; colorsym-
 bolism, 47.
 "Babylonians and Assyrians," Sayce,
 177.
 Bactrian tribes, rugs woven by, 60.
 Bagdad, 162, 168, 170.
 Bagh, 165, 170.
 Baghdad, 168.
 Bahadapur (District), 166, 170.
 Bakhshis rugs, 58.
 Baku, government of, 108; meaning of
 Baku, 162; spelling, 168, 170.
 Balkh, 165, 170.
 Ball, J. Dyer, 175.
 Bangalore, 166, 170.
 Banian or burr tree, symbolism of, 159.
 Barbarike, 46.
 Bardwan, 166, 170.
 Bareilly, 166.
 Bareli, 166.
 Basilica of St. Sophia at Constanti-
 nople, 120.
 Bat, symbolism of, 157, 161.
 Bat with a ring in its claws, symbolism
 of, 158.
 Batum, 168, 170.
 Bayer, Professor F., 153.
 Bayeta scarlet in Navajo rugs, 147.
 "Beast and Bird in Ancient Symbo-
 lism," Thompson's paper on, 178.
 Beauvais rug manufactory, 141, 169,
 170.
 Bee, symbolism of, 158.
 Beetle, symbolism of, 158.
 Behesne, 168, 170.
 Beirut, 168, 170.
 Belar, 165, 170.
 Belgium, rug-weaving in, 142.

INDEX

- Bellary, 166, 170.
 Beluch rug called "blue Bokhara," 97.
 Beluchistan rugs, 97; meaning of *Beluchistan*, 162; place-names, 165.
 Benares, 166, 170.
 Beni-Hassan, rug-weavers seen in wall-paintings at, 16.
 Berea College, Ky., rag rugs, 145.
 Bergama, 168, 170.
 Bergamo (Province), 168.
 Bergamo rugs, 74.
 Berbers, rugs woven by, 135.
 Beshir rugs, 100.
 Bethlehem tent cloth, 111.
 Beypur, 166, 170.
 Bhag, 165.
 Bhagalpur, 166, 170.
 Bhagulpore, 162.
 Bibikabad, 167, 170.
 Bibikabad rugs, 58.
 "Bible Myths," Auber, 175.
 Bijapur, 166, 171.
 Bijar, 55, 56; spelling, 167, 171.
 Bijar rugs, 58 (and plate), 67.
 Birch, Dr. Samuel, quoted, 17.
 Bird, symbolism of, 161.
 "Birds of Egypt," Shelley, 177.
 Birdwood, Sir George C., quoted, 23, 175.
 Birjand, 167, 171.
 Birjand rugs, 59.
 Bishop, Mrs. Isabella Bird, quoted, 24, 125, 175.
 Black, symbolism of, 47, 48; corrosiveness of dye, 63, 80.
 Blackie, C., 175.
 Blaine, Mrs. Emmons, rugs owned by, 34 (plate), 124 (plate).
 Blossom, symbolism of, 158.
 "Blue Bokhara" a misnomer, 97.
 Blue, symbolism of, 47, 48.
 Boar, symbolism of, 161.
 Boat, symbolism of, 158.
 Bode, Wilhelm, 156 (plate), 175, 184.
 Boglipoor, 166.
 Bokhara, dyes from, 98; meaning of *Bokhara*, 162; spelling, 168, 171.
 Bokhara rugs, no blue, 97; so-called and genuine, 98 (plate), 100, 103.
 Bombay, 166, 171.
 Bonnick's "Egyptian Belief and Modern Thought," 175.
 Borders, 38-42.
 Bordoni, Paris, 183.
 Bosnia, 136.
 Bosnian rugs, 136.
 Boulak, Egypt, rug factory, 51.
 "Bride's rug," 118.
 "British Manufactures and Industries," Phillips, 177.
 British Museum, Asiatic section, 117.
 Broussa, 74, 168; *see* Brusa.
 Brummer, Martin, 175.
 Brusa, 74, 111, 168, 171.
 Brussels, power looms in, 24; rug-production, 142.
 Buckthorns, certain species produce dyes, 45.
 Buddhist Sceptre, symbolism of, 157.
 Budge, E. A. Wallis, 175.
 Bujnurd, 167, 171.
 Bulgarian rugs, 137.
 Bull, symbolism of, 158.
 Burley, Clarence, rug owned by, 106 (plate).
 Burnham, Mrs. L. G., rug owned by, frontispiece plate.
 Burujird rugs, 59; spelling, 167, 171.
 Bushire, 167, 171.
 Butterfly, symbolism of, 158, 159, 161.
 Buyers' selection for Western market, 33, 38.
 Byzantine influence on rug-weaving, 19.

C

- Cabistan rugs, *see* Kabistan rugs.
 Cabool, 165.
 Cabul, 165.
 Cæsar first saw Cleopatra wrapped in rug, 18.
 Cæsarea, 71, 168, 169.

INDEX

- Cæsarean rugs, 75, 125.
 Cairo, rug emporium, 52, 169, 171.
 Calcutta, 166, 171.
 Camel's hair, 30, 31, 98
 Canton, 165, 171.
 Carding, 31.
 Carpaccio Vittore, painting by, 20
 (plate).
 Carpets, catalogue term for rugs, 16.
 "Carpets," Dresser, 176.
 Cartouche, symbolism of, 158.
 Cassaba rugs, 75, 83.
 Castle Carpet, 186.
 Caucasian rugs, modern, characteristic
 designs of, 39, 41, 42; descrip-
 tions, 105-108; place-names, 168.
 Cawnpur, 91, 166, 171.
 Center Lovell, Maine, 145.
 Central Aisa, rugs, 98; place-names,
 168.
 "Century Atlas," 175.
 "Century Dictionary," 175.
 Chal, 169.
 "Chamber's Encyclopædia," 175.
 Chanda, 166, 171.
 Charikar, 165, 171.
 Chemical dyes, 46.
 Chevalier, Charles, 176.
 Chichi rugs, 108.
 Chinese dye, green, 45.
 Chinese fret design, 43, 101, 102, 114
 (plate).
 Chinese influence seen in design of
 Ispahan rugs, 63; of Kashgar rugs,
 101; of Ouchak rugs, 183; of Samar-
 kand rugs, 102 (and plate).
 Chinese pictures copied in Persian
 hunting rugs, 124 (plate), 128.
 Chinese place-names, 165.
 Chinese rugs, 41, 113-115 (and plate
 facing 114), 184, 185; of silk, 124.
 Chinese silk industry, 123; silk rugs,
 124.
 Chinese symbolism of colors, 47, 48;
 of various designs, 157.
 Chinese Turkestan, 117, 184.
 Chintz designs in silk rugs, 125.
 Chipiez, Charles, 177.
 Christian weavers of Turkish rugs, 71.
 Circassian rug-weavers, 71.
 Circle design, 43, 161.
 Circular rugs, 115.
 Claremont, English home of Lord
 Clive, 89.
 Clarke, Sir C. Purdon, 175.
 Cleopatra borne before Cæsar in a rug,
 18.
 Chi-lin (a kind of doe), symbolism of,
 157.
 Chosroe I, Sassanian King of Persia,
 181.
 Climatic influences on rug-weaving,
 32, 71; on odors of rugs, 96.
 Clive, Lord, 89.
 Cloud bands, 41, 63, 157.
 Coat of arms of Persia, 160.
 Coat of arms of Turkey, 160.
 Cobern, —, 175.
Coccus cacti, insect which produces
 cochineal, 44.
 Cochineal, 44.
 Cock and hen on an artificial rock-
 work, symbolism of, 157.
 Colbert, fostered rug industry in
 France, 141.
 Colors, sensed by weavers, 21; Per-
 sians' intuition for, 37; obtained by
 aniline and vegetable dyes, 44; im-
 portance to Orientals, 47; Persian
 choice of, 47; symbolism of, 47,
 48; in modern Turkish rugs, 77;
 in Kurdish rugs, 79.
 Colvin, Sir Sidney, 182.
 Comb design, 43.
Conchylum, ancient name of Phœni-
 cian purple, 18.
 Cone, pine, symbolism of, 159; fir, 161.
 Constable's "Hand Atlas of India,"
 175.
 Constantinople, rug market, 71-73,
 82; silk-weaving introduced into,
 123; spelling, 169.
 Conway, Sir Martin, 182.
 Cossac (Kazak), 107, 108 (plate).
 Cotton, 30, 76.
 Cotton rugs, Indian, 23, 88, 91;
 Japanese, 116.

INDEX

- Coula, 169.
 Coverlets woven in "Appalachian America," 145.
 Coxon Herbert, 175.
 Crane, symbolism of, 157.
 Crescent, symbolism of, 158, 160.
 Crete girl weavers, 132.
 Crimson, 18, 47.
 Crocodile, symbolism of, 158.
 Crooked Turkish rugs, 24.
 Cross designs, 43.
 Crow, symbolism of, 157.
 Curson, Hon. George N., 175.
 Customs administration in Persia, 55.
 Customs Tag, Turkish, 73.
 Cypress tree design in Jaipur rugs, 91; symbolism of, 161; *see* 120 (plate) and 124 (plate).

D

- Daghestan, 168, 171.
 Daghestan rugs, 41, 105, 106 (and plate), 108.
 Damascus, 112.
 Damascus Rugs, 52.
 Daraksh, 59.
 Date woven into rugs, 67, 154, 155.
 Davis, —, 175.
 Davis Estate, Will J., rug owned by, 30.
 "Dawn of Civilization," Maspero, 177.
 Deccan, rugs from the, 23; meaning of *Deccan*, 162; spelling, 166, 171.
 "Decorative Art," Petrie, 177.
 Deer, symbolism of, 157.
 Definition of *rug*, 15.
 Dekkan-peninsula, 166.
 Delays caused by superstitious weavers, 29.
 Delhi, 91, 166, 171.
 Delhi Court, 87.
 Demirdji rugs, 75; spelling, 169, 171.
 Denny, M. B., 175.
 Derbent rugs, 105, 126 (plate); meaning of *Derbent*, 162; spelling, 168, 171.
 Descending eagle, symbolism of, 160.
 "Descriptions des Arts et Metiers," 139.
 Design, of Persian rugs, 17; Oriental designs adapted from Nature, 19; Egypto-Chaldean designs in modern rugs, 19; furnished by Western art schools, 25; hereditary, 37; manner of teaching to pupils, 37; of Persian rugs, 37; selected by buyer, 38; Occidental, copied by native weavers, 38; made from *talims*, or working drawings, 38, 39; proportioned to size of rug, 39; units described, 39-43; determines district where woven, 55; of modern Persian product, 57; Shah Abbas, 59; Herati border, 59, 61, 64, 69; Guli Hinnai, 60; Tree of Life, 17, 65; use of old patterns, 69; introduced by Persian weavers into India, 87; Hindoo, 88; floral, in Indian rugs, 88; Persian, in Jaipur rugs, 91; in Lahore rugs, 91; in Warangul rugs, 93; in Japanese rugs, 116; of silk rugs, 125; of Morris rugs, 139; of Navajo rugs, 148, symbolical, 156-162.
 "Design in Textile Fabrics," Ashen-hurst, 175.
 Designers, Indian, 32 (plate).
 Dewsbury, power looms in, 24.
 Dhurrie, Indian, 91, 94.
 Diarbekir, 169, 171.
 "Dictionary of Place Names," Blackie, 175.
 Dining-rooms, Görevan rugs popular for, 61.
 "Discoveries in the Ruins of Nineveh," Layard, 176.
 Djushaghan rugs, characteristic palmette of, 39; description, 59.
 Dog, symbolism of, 161.
 Dove, symbolism of, 158.
 Dowry, girls weave rugs for, 26, 132.
 Dragon, symbolism of, 157.
 Dragon and Phoenix, symbolism of, 157.

INDEX

- | | |
|--|--|
| <p>Dragon with five claws on each of its four feet, symbolism of, 157.
 Dresser, Charles, 176.
 Duck, symbolism of, 157.
 Dunlap, Mrs. Robert, rug owned by, 117 (plate).
 Dupont, French weaver, 141.</p> | <p>Durability of fine Persian rugs, 54; of Kurdish rugs, 79.
 Durham, power looms in, 24.
 Durrie, <i>see</i> Dhurrie, Indian.
 Duties, Persian system of collecting, 55; on rugs, 56.
 Dyes, 18, 44-46, 98, 139, 147.</p> |
|--|--|

E

- | | |
|--|---|
| <p>Eagle, symbolism of, 158, 160.
 Eagle, descending, symbolism of, 160.
 Eagle, flying, symbolism of, 160.
 Eagle, standing, symbolism of, 160.
 "Early Christian Symbolism," Allen, 175.
 Earnings of weavers, 27, 28, 82.
 "Earth and Its Inhabitants, The," Reclus, 177.
 East Turkestan place-names, 165.
 "Eastern Carpets," Robinson, 177.
 Edrisi, Mohammedan geographer, 185.
 Edwards, Amelia, 176.
 Egg, symbolism of, 158.
 "Egypt after the War," Stuart, 178.
 "Egypt: Three Essays on the History, Art, and Religion," Brummer, 175.
 "Egyptian Art," Ryan, 177.
 "Egyptian Belief and Modern Thought," Bonnick, 175.
 Egyptian wall-paintings of weavers, 16, 17; ancient rug-weaving, 18, 22; symbolic colors, 47; substitution of woven rugs for skins, 51; modern rugs, 51; factory, 51; imported rugs, 52; symbols, 158, 159.
 Egypto-Chaldean designs in modern rugs, 19.
 Elephant, symbolism of, 161.
 El-Hosn, 169, 171.
 Elkins, Joseph, D.D., 176.</p> | <p>Ellore, 166, 171.
 Ellore, rugs, 91.
 Ely, Talfourd, 176.
 "Emblems of Saints," Fusenbeth, 176.
 Emmaus's "Life of Ancient Egypt," 176.
 "Encyclopædia of the Industrial Arts, Manufactures, and Raw Commercial Products," Spon's, 177.
 English interests in India, 35; in Amritsar, 90.
 English rugs, 138-140 (and plate).
 English rug-weaving centres, 24.
 Enzeli, 167, 171.
 Erivan, 168, 171.
 Ersari Goklan tribe, 98.
 Ersari tribe of upper Oxus, 101.
 Erzerum, 169, 171.
 Europe, introduction of rug-weaving into, 20; use of rugs at <i>fêtes</i>, 20; imports looms into Turkey, 24; demand for rugs since 1850, 54; factories to supply trade with, 57; interest in Ouchak industry, 81.
 Evans, E. P., 176.
 Evergreens, symbolism of, 161.
 Experts can determine where rug was made, 55.
 Export trade (Persian) in rugs, 55, 56.
 Eye of Osiris, symbolism of, 158.</p> |
|--|---|

F

- | | |
|--|---|
| <p>Faber, George Stanley, 176.
 Factories, rug-weaving, 26, 38, 51, 56, 57, 69, 70, 90, 119.
 Fakeh, 169, 171.</p> | <p>Fars, designs peculiar to, 37; modern rug-weaving district, 55; value of rug trade, 56; rugs exported from, 68; meaning of <i>Fars</i>, 162; spelling, 167, 171.</p> |
|--|---|

INDEX

- Farsistan (Province), 167.
 Feather of an ostrich, symbolism of, 158.
 Feathers of rare birds, symbolism of, 158.
 Felt rugs, 126, 127.
 Felts, Chinese, 114.
 Feraghan, 167, 171.
 Feraghan rugs, characteristic designs of, 40, 42, 43; description, 59; plate, 62.
 Ferghana (Province), 168.
 Fergusson, James, 176.
Fêtes, rugs used as decorations during, 20.
 Fez, 134.
 Figdor, Dr., of Vienna, 181.
 Finnish rugs, 187.
 Fir cone, symbolism of, 161.
 Fire-worshippers of Yezd, 70.
 Flat stitch, in Soumak and Khilim rugs, 34, 117.
 Flax, 30.
 Floor-coverings and awnings, ancient, 19.
 Floral designs in Indian rugs, 88; in Jaipur rugs, 91.
 Fly, symbolism of, 161.
 Flying eagle, symbolism of, 160.
 "Folk Lore of China, The," Denny, 175.
 France, rug-weaving introduced by Saracens, 20; silk industry in, 123; place-names, 169.
 Frankfort Museum of Decorative Art, 182.
 French rugs, 141, 142.
 Fringe on rugs intended for hanging, 99.
 Frog, symbolism of, 158.
 Fu-Chan, 171.
 Fu-Chau, 162, 165.
 Fusenbeth, F. C., D.D., 176.
 Fylfot design, 42, 148, 159.

G

- Garden Rugs, 181.
 Gask, 167.
 Gauls, red favorite color of, 48.
 Gâzne, 165.
 Gemerik, 169, 171.
 Genghis Khan, 100.
 Genghis rugs, 100.
 Geometrical designs replace floral in India, 88.
 Germantown yarn used in Navajo rugs, 147.
 Germany, rug-weaving in, 142.
 Ghain, 167.
 Ghayn, 167.
 Ghazni, 165, 171.
 Ghilan, silk trade in, 124; spelling, 167, 171.
 Ghileem rugs, *see* Khilim rugs.
 Ghiordes, 169, 171.
 Ghiordes knotting, 34, 35.
 Ghiordes panel in Meles prayer rug, 80.
 Ghiordes rugs, 41, 74 (plate), 75, 78, 122.
 Ghiordium, 75.
 Gilan, 163, 167.
 Goa, 166, 171.
 Goats replace sheep in rocky regions, 72; raised by Turkomans, 98.
 Gobelins manufactory, 141.
 "Goddess of silkworms," 123.
 Gold warp used for antique Persian rugs, 53; in state rugs of India, 89; in Polish rugs, 119; in Chinese silk rugs, 124.
 Goodyear, William H., 176.
 Goose, symbolism of, 157.
 Gorakhpur, 166, 171.
 Gordis, 169.
 Gordus, 169.
 Görevan rugs, 60.
 Gorukpore, 166.
 Gothic sanctuary rugs, 187.
 Gourd, symbolism of, 157.
 "Grammar of Ornament, The," Jones, 176.
 "Grammar of the Lotus, The," Good-year, 176.

INDEX

Granada, Province of, 187.
 Grant, Mrs. Frederick D., rug owned by, 90.
 Graves, custom of hanging rugs over, 20.
 Great Britain, power looms in, 24, 25.
 Greece, rug-weaving in, 19; swastika design in rugs of, 43; saffron favorite color in, 48; silk-weaving in, 123; ancient and modern rugs of, 132, 133; place-names, 170.

"Greek and Roman Antiquities," Smith, 177.
 Greek Christian weavers, 71; in Hereke, 76.
 Green dyes, how produced, 45; symbolism of, 47, 48; used though forbidden by law, 81.
 Guendje rugs, 100, 101.
 Guli Hinnai design, 43, 60.
 Gulistan, 163, 165, 171.
 Gundava, 165, 171.
 Gurdiz, 169.

H

Haidamoor, 169, 171.
 Haidamur rugs, 111, 112.
 Haidarabad rugs, 91.
 Haiderabad, 163, 166, 171.
 Hair, lock of, woven in Kis Khilims, 118.
 Hakkam, 169, 171.
 Halifax, power looms in, 24.
 Hamadam, 171.
 Hamadan, 55, 56, 58, 59, 167.
 Hamadan rugs, 60 (plate), 61.
 "Hand Atlas of India," Constable, 175.
 Hand looms, 22.
 "Handbook of Ornament," Meyer, 177.
 Hang-chau, 165, 171.
 Hangings, rugs used as, 16, 55.
 Hare, symbolism of, 161.
 Havermeyer, late H. O., rug owned by estate of, 114 (plate).
 Hawk, symbolism of, 158.
 Hay, Mr., owner of Theban rug, 17.
 Hayzoor, 169, 172.
 Heart, symbolism of, 161.
 Hedin, Sven, 176.
 Hemp, 30, 81.
 Herat, 59, 61, 87, 163, 165, 172.
 Herat rugs, 40, 42, 61, 181.
 Herati border, 40, 59, 61, 64, 69, 117.
 Hereke, 169.
 Hereke rugs, 76.
 Herez, 58, 60, 167, 172.
 Herez rugs, 62.

Hindoo designs, 88; religious abstinence from sheep flesh, 88.
 Hippopotamus, symbolism of, 161.
 Hispano-Moresque rugs, 183.
 Hissan, 172.
 Hissar, 168, 169, 172.
 "History of Ancient Art," Lübke, 176.
 "History of Ancient Art," Reber, 177.
 "History of Art among the Greeks," Winkleman, 178.
 "History of Art in Ancient Egypt," Perrot and Chipiez, 177.
 "History of Art in Chaldea and Assyria," Perrot and Chipiez, 177.
 "History of Bokhara," Vámbéry, 178.
 "History of Painting," Van Dyke, 178.
 "History of Persia," Malcom, 176.
 Hog, symbolism of, 161.
 Holland, rug-weaving in, 142.
 Holt, Miss Ellen, rugs owned by, 95 (plate), 122 (plate).
 Holy Land, rugs of the, 111, 112.
 Homs, 169, 172.
 Hooked rugs, New England, 143, 144.
 Hossu, 169.
 Hounds, symbolism of, 160.
 Hulme, F. Edward, 176.
 Human figure introduced into design, 67.
 Hunters, Mounted, in Persian dress, 128.
 Hunting rugs, Persian, 124 (plate), 128.
 Hyderabad, 166.

INDEX

I

- Ibis, symbolism of, 158.
 "Iconographic Encyclopædia of the Arts and Sciences," 176.
 "Illumination," Westwood, 178.
 Imperial Museum at Constantinople, 181.
 Import duties to United States on rugs, 56.
 "In the Forbidden Land," Landor, 176.
 India, looms used in, 23, 82 (plate); weavers, 26; superstitions among weavers, 29; wool from, 30; rugs woven of pashim, 30; rugs of various knottings, 35; firms having factories in, 35; Occidental designs introduced into, 38; use of talims in, 39; raises madder, 44; symbolism of colors, 48; of designs, 159; place-names, 166.
 Indian designers, 32 (plate).
 "Indian Industries," James, 176.
 Indian rugs, 78 (plate), 87-94; *see under* India.
 Indicum, *see* Indigo.
 Indigo, 45-47.
Indigofera tinctoria, Indian indigo plant, 46.
 Indo-Persian Hunting Rugs, 128.
 "Industrial Arts of India, The," Birdwood, 175.
 "Industrial Arts of the Nineteenth Century," Wyatt, 178.
 Industrial Museum at Berlin, rug in collection of, 154.
 Inman, Thomas, M.D., 176.
 Inscriptions on rugs, 70, 124 (plate), 153-155.
 Irak, 167.
 Irak-Ajemi province, 64, 69, 167, 172.
 Iran (Persia), 62.
 Islamabad, 163.
 Ispahan, 55, 121, 163, 167, 172.
 Ispahan rugs, 62, 181.
 Istalif, 165, 172.
 Italy, rug-weaving introduced by Saracens, 20; silk culture in, 123.

J

- Jabalpur, 166, 172.
 Jails, rugs woven in, 78 (plate), 88, 90.
 Jaipur, 166, 172.
 Jaipur rugs, 91.
 Jalal-ud-Din Mahomed, 87.
 Jalandhar, 166, 172.
 James, A. G. F. Eliot, 176.
 Jammu, 166, 172.
 Jamu, 166.
 Japanese looms, 24; rugs, 116; symbols, 160; place-names, 167.
 Jelalabad, 165, 172.
 Jerusalem, 163, 169, 172.
 Jewish legend of invention of spinning and weaving, 16.
 Jeypore, 166.
 Jhalawan (District), 165, 172.
 Jodhpur, 166.
 Jones, Owen, 176.
 Joohpur, 172.
Journal of the Society of Arts, 176.
 "Journeys in Persia and Kurdistan," Bishop, 175.
 Jubbulpore, 166.
 Jubbulpur, 166.
 Jug, symbolism of, 161.
 Jullinder, 166.
 Jute, 30, 116.

K

- Kabistan rugs, 106.
 Kabul, 165, 172.
 Kabul sheep, 30.
 Kain, 167, 172.

INDEX

- Kairouan, 169, 172.
 Kairuan, 135.
 Kaisarieh, 169, 172.
 Kaiser Friederich Museum, 182.
 Kandahar, 163, 165, 172.
 Karabacek, Dr. Joseph, 176.
 Karabagh province, 63; meaning of *Karabagh*, 163; spelling, 168, 172.
 Karabagh rugs, 106.
 Kara Dagħ rugs, 63; meaning of *Kara Dagħ*, 163; spelling, 167.
 Kara-Geuz rugs, 77.
 Karahissar, 169, 172.
 Karajah Dagħ, 71.
 Karaman rugs, 77; spelling, 169, 172.
 Karashar, 165, 172.
 Kars, 168, 172.
 Kashan, 125, 167, 172.
 Kashgar, 165, 172.
 Kashgar rugs, 101, 103.
 Kashmir, capital of, 93; spelling, 166, 172.
 Kashmir shawls and rugs, 89, 108.
 Kashmir wool, 30.
 Kazak rugs, 106, 107, 108 (plate).
 Kazan, 168, 172.
 Kchatchli rugs, *see* Khalatch rugs.
 Kelat, 163, 165, 172.
 Kelim rugs, *see* Khilim rugs.
 Kerkuk, 169, 172.
 Kermanshah rugs, 63; spelling, 167, 172.
 Kermanshahan, 167.
 Kermes, red dye, 45.
 Khalatch rugs, 101.
 Khalatch tribe, 101.
 Khilim designs, 117.
 Khilim rugs, 34, 117 (and plate), 118.
 Khiva, 103, 168, 172.
 Khiva rugs, 100, 102.
 Khokand, 168.
 Khonsar, 167, 172.
 Khora-mabad, 167, 172.
 Khorasan (Province), 167.
 Khorassan province, 55, 56, 64; meaning of *Khorassan*, 163; spelling, 167, 172.
 Khorassan rugs, 40, 42, 56 (plate), 64, 66.
 Khorsabad, 169, 172.
 Khotan, 165.
 Khotan silk rugs, 124; felt rugs, 126.
 Khozdar, 165, 172.
 Khuzistan, 167, 172.
 Khyrpur, 166, 172.
 Kiang-su, 165, 172.
 Kidderminster, power looms in, 24.
 Kilim rugs, *see* Khilim rugs.
 Kioto, 167, 172.
 Kirman, modern rug-weaving district, 55; value of rug trade, 56; spelling, 167, 172.
 Kirman rugs, 64, 120 (plate), 182.
 Kirmanshah rugs, 41.
 Kir-Shehr rugs, 77; spelling, 169, 172.
 Kis Khilims, 118.
 Knight, Richard Payne, 176.
 Knot and flower design, symbolism of, 159.
 Knots and knotting, 23, 32, 34-36, 93.
 Kohat, 166, 172.
 Kokand, 168, 172.
 Konieh rugs, 78; spelling, 169, 172.
 Kotah, 166, 172.
 Koula, 169.
 Kuba, 106, 168, 172, 183.
 Kucha, 165, 172.
 Kuchan, 167.
 Kulah rugs, 78, 80, 122; spelling, 169, 172.
 Kurdish rug design represented in ancient Nineveh, 17.
 Kurdish rugs, wool used in, 65; woven by girls and women, 78; durability and colors, 79.
 Kurdistan, modern rug-weaving district, 55; nomadic tribes of Western, 87; spelling 167, 168, 172.
 Kurdistan rugs, characteristic designs of, 40; value of trade in, 56; descriptions, 65, 78.
 Kurds, nomadic tribes, 65, 71.
 Kushmore, 166, 172.
 Kutahia rugs, 79; spelling, 169, 172.
 Kutai, 169.
 Kutayah, 169.
 Kwatah, 163, 165.

INDEX

L

- Ladik rugs, 79; spelling, 169, 173.
 Lahore, 166, 173.
 Lamm, Mr., of Naesby, Sweden, 182.
 Landor, A. Henry Savage, 176.
 Laodicea, 79, 122.
 Lar, 167, 173.
 Largest rug woven, 95.
 Laristan province, 66, 167, 173.
 Laristan rugs, 66.
 Layard, Austen Henry, 176.
 Leipzig Museum of Decorative Art, 183.
 Lenormant, François, 176.
 Leopards, symbolism of, 160.
 Lessing, Julius, 176.
 "Life in Ancient Egypt," Emmaus, 176.
 Lily, symbolism of, 161.
 Linen, 30.
 Lion, symbolism of, 157, 160.
 "Lives of the Queens of England," Strickland, 178.
 Lizard, symbolism of, 158.
 Lobanow-Rostowsky, Prince Alexis, rug owned by, 36.
 Lock, Charles G. W., 177.
 Looms, 22-24 (and plate), 82 (plate), 111, 147.
 Lotus design, 43, 158.
 Lourdes, French weaver, 141.
Louvre, Palais du, rugs woven in, 141.
 Lübke, Wilhelm, 176.
 Lucknow, 91, 166, 173.
 Luristan (Province), 167, 173.

M

- Maciet, M., Paris, rug owned by, 128.
 Madder, 44.
 Madras, 166.
 Madras rugs, 92.
 Magpie, symbolism of, 157.
 Makran, 167, 173.
 Malabar (District), 166, 173.
 Malair, 56.
 Malcom, Sir John, 176.
 Manchuria, 184.
 Mandalay, 166.
 "Manual of Archæology," Ely, 176.
 "Manual of Design," Redgrave, 177.
 "Manual of Egyptian Archæology," Maspero, 176.
 "Manual of Oriental Antiquities," Babelon, 175.
 "Manual of Sculpture," 177.
 "Manual of the Ancient History of the East," Lenormant and Chevalier, 176.
 "Manual of the Historical Development of Art, A," Zerffi, 178.
 Manufacturers of rugs, 35.
 Marash, 169, 173.
 Maresh, 169.
 Martin, F. R., 176.
 Marvin, Charles, 176.
 Maspero, Gaston C. Charles, 176, 177.
 Mastung, 165, 173.
 Masulipatam rugs, 92; spelling, 166, 173.
 Materials used in rug-weaving, 30.
 Mazandaran, 167, 173.
 McCormick, Mr. Cyrus H., rug owned by, 108 (plate).
 Meandrian motif in Chinese rugs, 114.
 Mecca rug, 68; meaning of *Mecca*, 163; spelling, 169, 173.
 Medallion design, 43.
 Medina, 169, 173.
 Mehran, 167, 173.
 Mekran (District), 167.
 Melasso, 169.
 Meles rugs, 80, 122.
 Melhaz, *see* Meles rugs.
 Mersherski, established Polish rug factory, 119.
 Merut, 166, 173.
 "Merv Oasis, The," O'Donovan, 177.
 "Merv, the Queen of the World," Marvin, 176.
 Meshed, 163.
 Meshhed, 64, 167, 173.

INDEX

- | | |
|---|---|
| <p>Meshhed rugs, 56 (plate), 64, 66.
 Mesopotamia, monuments show ancient rug-weavers, 16; spelling, 168.
 Metropolitan Museum of Art, 182.
 Meyer's "Handbook of Ornament," 177.
 "Middle Kingdom, The," Williams, 178.
 Mihrab in prayer rug, 120.
 Milassa, 80, 169, 173.
 Mina Khani design, 43.
 Mir, 67.
 Mir-Saraband rugs, 66, 67.
 Mirzapore, 163.
 Mirzapur rugs, 92; spelling, 166, 173.
 Misratah, 169, 173.
 Mohair from Angora goat, 30, 72.
 Mohair rugs, 72, 77, 80.
 Mohammedan religion does not allow use of animal forms, 37; used by Shiah sect and others, 38; green sacred color, 48, 81; white emblem of mourning, 48; introduction of rug-weaving into India, 87.
 Moodj mats, 92.
 Mongolia, 184.
 Moorish rugs, 134.</p> | <p>Moors introduced rug-weaving into the West, 141; indirectly taught weaving of Navajo blankets, 147.
 Moradabad, 166.
 Morocco rugs, <i>see</i> Moorish rugs.
 Morris rug, 139.
 Morris, William, 138-140.
 Moslems, <i>see under</i> Mohammedan.
 Mosques, location of, 120.
 Mosul rugs, 80; spelling, 169, 173.
 Moussul, 169.
 Mujur, 173.
 Mukden, 184.
 Multan rugs, 92, 93; spelling, 166, 173.
 Mumford, John Kimberly, 177.
 "Mummy Badge, The," Budge, 175.
 Müntz, Eugene, 177.
 Murex, source of Phœnician purple, 18, 45.
 Murshidabad, 166, 173.
 Museum, Algiers Public, 135.
 Muskabad rugs, 66, 70.
 Mylasso, 169.
 Mysore, 166, 173.
 Mysore rugs, 93.
 "Mythology and Egyptian Christianity," Sharpe, 177.</p> |
|---|---|

N

- | | |
|--|---|
| <p>Naamah, legendary inventor of spinning, 16.
 Nagpur, 166, 173.
 Names of rugs, 94.
 Nanking, 184.
 Natural forms in rug designs, 19, 21, 37, 65.
 Navajo Indian Reservation, 146.
 Navajo rugs, swastika design in, 43; description of, 146-149 (and plate).
 Navajo women's costume, 148.
 New England hooked or rag rugs, 143, 144.
 Nile Key, symbolism of, 158.</p> | <p>"Nineveh and Babylon," Layard, 176.
 "Nineveh and its Remains," Layard, 176.
 Nineveh marbles, 17; fall of, 19.
 Ning-po, 163, 165, 173.
 Niris, Lake, 66.
 Niris rugs, 66.
 Niriz, 167, 173.
 Nishapur, 167, 173.
 Niya Site, 117.
 Nomadic weavers, 26; design peculiar to, 41.
 North Arcot (District), 166, 173.</p> |
|--|---|

INDEX

O

- Octagon design, 43.
- O'Dagree, H. Eugene, 177.
- O'Donovan, Edmund, 177.
- Odor of rugs, 95, 96.
- Old man leaning on staff, symbolism of, 157.
- Olive, symbolism of, 161.
- Onteora rugs, 144.
- Oorfa, 169.
- Orange, symbolism of, 48.
- "Oriental Carpets," Clarke, 175.
- "Oriental Carpets," Coxon, 175.
- "Oriental Carpets," Lessing, 176.
- Oriental Rugs, Ancient, 52.
- "Oriental Rugs," Mumford, 177.
- Oriental symbols, 156-162.
- Oriental Tree of Life, 186.
- "Origin of Pagan Idolatry," Faber, 176.
- "Origin of Pictish Symbolism," Southesk, 177.
- Ormarah, 165, 173.
- "Ornement Polychrome, L'," Racinet, 177.
- Ottoman Museum, Constantinople, 183.
- Ouchak, 81, 169, 173.
- Ouchak rugs, 78, 81.
- Oushak, 169.
- Oustri-Nan rugs, 66; spelling, 167, 173.
- Outlines of black and white, 47.
- Owephissa, 170, 173.
- Owl, symbolism of, 157, 161.
- Ox, symbolism of, 161.

P

- Painting, rug, 46.
- Palestine rugs, 111.
- Palm leaf designs, 41.
- Palm tree, symbolism of, 159.
- Palmer, Estate of Mrs. Potter, rug owned by, 54, 90.
- Palmette, forms of, 39, 40.
- Papyrus, importance to Egyptians, 51; symbolism of, 159.
- Pashim (goat's wool), 30, 93.
- Patna, 166, 173.
- Patna rugs, 93.
- Patriarchs' graves, rugs hung over, 20.
- Patterns, small, used by Demirdji weavers, 75.
- Paul's Tent Cloth, 72.
- Peach, symbolism of, 157.
- Peacock, symbolism of, 160, 161.
- Peacock Throne at Teheran, 124.
- Pearls interwoven in silk rug, 124.
- Peking, 184.
- Pequaket, N. H., 143.
- Pergamo, 168.
- Pergamos, 74.
- Perrot, Georges, 177.
- "Persia and the Persian Question," Curson, 175.
- "Persia and the Persians," Wheeler, 178.
- Persia, significance of white in, 48; antiquity of rug-making in, 53; civilization of, 53; rugs principal source of income, 54; use of rugs in, 54; export and import trade and value of rug industry, 55, 56; home consumption of part of product, 54, 56; manufacturing firms, 56, 57; official name, Iran, 62; silk trade with China, 123; place-names, 167.
- "Persian Art," Smith, 177.
- Persian berries, 44, 45.
- Persian coat of arms, 160.
- Persian designs in India, 87, 88; in Jaipur rugs, 91; in Lahore rugs, 91; in Warangul rugs, 93; once used in Japan, 116.
- Persian Empire, its conquest by Saracens, 19.
- Persian knotting, 34-36.
- "Persian Life and Customs," Wilson, 178.
- Persian rugs, Tree of Life design on, 17; value of, 28; excellence of design and coloring, 37; animal designs, 37.

INDEX

- 38; designs and borders in good antiques, 38; characteristic designs, 40-43; choice of colors, 47; use of, in Persia, 54; small ones not exported, 54; durability of fine specimens, 54; used as hangings, 55; districts where woven, 55; experts can tell where woven, 55; value of trade in, 55, 56; export and import duties on, 56; manufactured for Western markets, 56, 57; descriptions of characteristic weaves, 58-70; preferred to Indian, 87; silk rugs, 124 (plate), 125; hunting rugs, 128; antique rug, 156 (plate); symbols, 160, 181, 182.
- Persian weavers taken to India, 87.
- Persian wool, 30.
- "Persische Nadelmalerei, Die," Karabacek, 176.
- Peshawar sheep, 30; meaning of *Peshawar*, 163; spelling, 166, 173.
- Petrie, William Matthews Flinders, 177.
- "Pharaohs, Fellahs, and Explorers," Third Lecture, Edwards, 176.
- Philadelphia, power looms in, 24; rug-production of, 143.
- Phillips, G., 177.
- Phœnician art, 18.
- Phœnician purple, 18.
- Phœnix, symbolism of, 157, 160, 162.
- Pig, symbolism of, 162.
- Pine cone, symbolism of, 169.
- Pine trees, symbolism of, 160.
- Pirot, Servia, 136.
- Place-names associated with rugs, meanings of, 162, 163; various spellings of, 164-174.
- Pliny, quoted, 45.
- Plutarch, quoted, 45.
- Poldi Pezzol, Museum, Milan, 185.
- Polish rugs, 119.
- Pomegranate design, 41, 159.
- Poona, 166, 173.
- Pooneh, 166.
- Power looms, 22, 24.
- Prado Gallery, Madrid, 187.
- Prayer rugs, Ghiordes, 75; Ghiordes and Kuhl, 78; Ladik, 79; modern and antique compared, 80; Beluchistan, 97; Karamanian and Kurdish, 117; description, 120-122.
- Public Museum at Algiers, 135.
- Puckered edges of Sinna rugs, 69.
- Pueblo Indians taught rug-weaving by Spaniards, 147.
- Punjab, capital of the, 91.
- Purple, *see* Phœnician and Tyrian purple; symbolism of, 47; favorite color of Romans, 48.
- Purpurin (red coloring-matter), 44.
- Pushmina rugs, 93.
- Q**
- Qourdes, 169.
- Quaritch, Bernhard, 139.
- "Quarterly Papers on Architecture," Weale, 178.
- Quetta, 165, 173.
- R**
- Rabat, 134, 135.
- Rachova, 170, 173.
- Racinet, M. A., 177.
- Rag rugs, New England, 143, 144.
- Raipur, 166.
- Ralph, Julian, 88, 89.
- Ram, symbolism of, 162.
- Rampur, 166, 173.
- Rangpur, 166, 173.
- Rawar, 167.
- Reber, Franz von, 177.
- Reciprocal trefoil design, 42, 67.
- Reclus, Elisie, 177.
- Red, symbolism of, 47, 48.
- Redgrave's "Manual of Design," 177.
- Reed, symbolism of, 162.

INDEX

- "Religion of Ancient Egypt," Renouf, 177.
 "Religion of the Semites," Smith, 177.
 Renouf, P. LePage, 177.
 Resht, 125, 167, 173.
 Restoration of old dyeing, 46.
Rhamnus chlorophorus, 45.
Rhamnus utilis, 45.
 Rhinoceros, symbolism of, 162.
 Rhodian lily design, 79.
 Riegl, Dr. Alois, 177.
 Robinson, Vincent, 177.
 Rochdale, power looms in, 24.
 Romans, dyes prized by, 45; purple favorite color of, 48.
 Rose color, symbolism of, 47.
 Rosette, symbolism of, 159.
 Rothschild, Baron Adolphe, rug owned by, 128.
 Rothschild, Baron Nathaniel, rug owned by, 153.
 Roubaix, 169.
 Roumanian rugs, 137.
 Royal Palace at Stockholm, 128.
 Royalty, yellow symbol of, in China, 47.
Rubia, dye-yielding genus, 44.
Rubia tinctorum, 44.
 Rugs, utility of, 15; origin of need for, 15; weaving of, began, 15; definition of name, 15; identical with carpets, 16; represented in Egyptian wall-paintings, 16, 17; on Nineveh marbles, 17; Egyptian, 18; Assyrians used, as awnings and floor-coverings, 19; rug-weaving in Egypt, Chaldea, Assyria, Asia Minor, and Greece, 19; introduced into Europe, 20; hung over graves, 20; used in Europe during *fêtes*, 20; increasing use of, 21, 26; value by square foot, 28; sometimes woven underground, 29; pashim rugs from India, 30; of camel's hair, 31; knotting in Persian, 32; product of cold districts in demand, 32; selected for Western market, 33; famous rugs in collections, 33; industry encouraged in India, 35; designs in Persian, 37, 38; designs in modern Oriental, 38; proportion between size and design, 39; replace skins in Egypt, 51; modern Egyptian, 51; imported into Egypt, 52; Cairo emporium for sale of, 52; antique Persian, 53; Shah Abbas's encouragement of rug-weaving, 53; value of Shah Abbas rugs, 53; decline and growth of industry in Persia, 54; use of, in Persia, 54; durability of, 54; district where woven determined by design and fabric, 55, 88; value of trade to Persia, 55, 56; export and import duties upon, 56; firms prosecute trade in, 56, 57; quality and design of modern Persian, 57; characteristics of Persian, 58-70; value in Orient, 70; characteristics of Turkish, 71-83; use of, in Turkey, 72; in Constantinople market, 72, 73; characteristics of Indian, 87-94; less expensive than Persian, 88; Indian gold-embroidered state rugs, 89; Lord Clive's rug, 89; rugs have replaced shawls in Kashmir, 89; rugs of Afghanistan, 95, 96; of Beluchistan, 97; Turkoman rugs, 98-104; Caucasian rugs, 105-108; rugs of Holy Land, 111, 112; of China, 113-115; of Japan, 116; Khilim, 117, 118; Polish, 119; prayer, 120-122; silk, 123-125; felt, 126, 127; hunting, Persian, 128; Greek, 132, 133; Moorish and Spanish, 134, 135; Bosnian, Servian, Roumanian, and Bulgarian, 136, 137; English, 138-140; French, 141, 142; United States, 143-149; inscriptions on, 153-155; Oriental symbols on, 156-162; meanings of place-names associated with, 162, 163.
 "Rugs of the Middle Ages from Asia Minor and Spain," 185.
 Running hook design, 41.
 Russian Empire, place-names, 168.
 Rustan Khan, 165, 173.
 Ryan, Charles, 177.

INDEX

S

- S-form design, 43.
 Sabatos rugs, 144, 145.
 Saddlebags, rug-woven, 60.
 Saffron, 44, 48.
 Safeta, 169.
 Safita, 174.
 Sail of a vessel, symbolism of, 159.
 St. Clement, legendary discoverer of felt, 126, 127.
 Sakai, 167, 174.
 Samarkand rugs, 102 (and plate), 125; meaning of *Samarkand*, 163; spelling, 168, 174.
 Saraband rugs, 42, 59, 66.
 Saracens, their conquest and influence, 19; origin of name, 20; introduced rug weaving to Europe, 141; introduced tapestries to France, 141.
 Sarakahs rugs, 58 (and plate), 67; spelling, 174.
 Sarawan, 67, 165, 174.
 Sardinian rugs, 187.
 Sarik tribe, 98.
 Sarre, Dr. F., 52, 185, 186.
 Saruk rugs, 67.
 Savalan rugs, 68, 70.
 Savas, 169.
Savonnerie, *La*, rug factory, 141.
 Sayce, Archibald Henry, LL.D., 177.
 Scarabæus, symbolism of, 159.
 Scarlet, symbolism of, 47.
 Schwarzenberg, Prince, Vienna, rug owned by, 134.
 Scorpion, symbolism of, 162.
 Scotland, power looms in, 25.
 Scroll design, 43.
 "Sculpture, Manual of," 177.
 Sedentary weavers, 26, 27.
 Sefevi Period, 182.
 Se-Ling-She, legendary discoverer of silk-weaving, 123.
 Serampur, 166, 174.
 Serapi rugs, 69.
 Serebend rugs, 66.
 Serinuggar, 166.
 Serpent, symbolism of, 159, 162.
 Serrated leaf design, 43.
 Servian rugs, 136.
 Shah Abbas, 53.
 Shah Abbas design, 43, 59.
 Shanghai, 163, 165, 174, 184.
 Shan-tung, 165, 174.
 Sharjah, 169, 174.
 Sharkah, 169.
 Sharpe, Samuel, 177.
 Sharrokhs on the Attrek, 87.
 Shawls, Kashmir, 89, 108.
 Shearing, Indian methods of, 147.
 Sheep, not raised in rocky regions, 72; not eaten by Hindoos, 88.
 Shelley, G. E., 177.
 Shemakha rugs, 108; spelling, 168, 174.
 Shepherds use felt rugs, 126.
 Shiah sect of Moslems employ animal designs, 38.
 Shikarpur, 166, 174.
 Shiraz, 66, 68, 167, 174.
 Shiraz rugs, 41, 68 (and plate).
 Shirvan, 117, 168, 169, 174.
 Shirvan, rugs, 41, 107, 108.
 Shirwan, 167, 174.
 Shoes removed in house by Persians, 55.
 "Short History of Tapestry, A," Müntz, 177.
 Show-window demonstrations by Oriental weavers, 21.
 Shrouds, rugs used as, 135.
 Shusha, 174.
 Shushu, 168.
 Shuster, ancient capital of Persia, 53, 55; spelling, 167, 174.
 Sicily, rug-weaving introduced by Saracens, 20; silk-weaving in, 123.
 Silk for rug-weaving, 30; introduced into antique Kirman rugs, 65; silk rugs of Brusa, 74; silk Polish rugs, 119; use of, discovered in China, 123; use of, outside of China, 123; description and prices of silk rugs, 124 (and plate), 125; silk added to wool rugs, 124.

INDEX

- Silver woven in Polish rugs, 119.
 Sindh rugs, 93.
 Sinna, 117, 167, 174.
 Sinna knotting, 34, 35.
 Sinna rugs, characteristic border of, 40; description, 69; plate, 34.
 Sirab rugs, 69; spelling, 167, 174.
 Sivas rugs, 82; spelling, 174.
 Skins sewed into rugs, 115.
 Smith, Byron L., rug owned by, 62 (plate).
 Smith, Major R. Murdock, R. E., 177.
 Smith's "Greek and Roman Antiquities," 177.
 Smith's "Religion of the Semites," 177.
 Smyrna, madder raised near, 44; trade with, 77, 82; spelling, 169, 174.
 Smyrna rugs, 72, 82, 134.
 Sohar, 169, 174.
 Solar disk with serpents, symbolism of, 159.
 Sonmeani, 165, 174.
 Soumak rugs, manner of knotting, 34, 35; characteristic design of, 41; description of, 108; *see* plate, page 30.
 Southesk's "Origin of Pictish Symbolism," 177.
 Spade design, 42.
 Spain, rug-weaving in, 20, 134; silk-weaving in, 123.
 Spanish rugs, 185, 186, 187.
 Spaniards taught weaving and sheep-raising to American Indians, 147.
 Sparta, 169.
 Sparta rugs, 83.
 Spear, symbolism of, 162.
 Spelling of place-names, 164-174.
 Sphinx, symbolism of, 159.
 Spider, symbolism of, 162.
 Spinning, legends of invention of, 16.
 Spon, —, 177.
 Squirrel, symbolism of, 162.
 Srinagar rugs, 93; meaning of *Srinagar*, 163; spelling, 166, 174.
 Staff in the hands of the gods, symbolism of, 159.
 Stamboul, 73.
 Standing eagle, symbolism of, 160.
 Star designs, 43, 162.
 Stark tree form in Turkoman rugs, 101, 102.
 Stein, Sir M. A., 117.
 Stieglitz Museum, Leningrad, 185.
 Stitches in Persian rugs, *see* Knots.
 Stockholm Palace, rug in, 128.
 Stork, symbolism of, 157, 160.
 Strickland, Agnes, 178.
 Stuart, H. Villiers, 178.
 Subdued colors, preference given to, 21, 47.
 Su-chau, 165, 174.
 Sultanabad, 55, 56, 59, 69, 125; spelling, 167, 174.
 Sultanabad rugs, 69, 70.
 Sultan's factories and schools, 76.
 Sumac, 44.
 Sun, symbolism of, 159, 160.
 Superstitions among weavers, 29.
 Supplement 1927, 179.
 Surat, 166, 174.
 Susiana, Ancient (Province), 167.
 Swastika design, 42, 148, 162.
 Switzerland, rug-weaving in, 142.
 Sword, symbolism of, 160.
 Sykes, Ella C., 178.
 "Symbolican Language of Ancient Art and Mythology, The," Knight, 176.
 "Symbolism in Christian Art," Hulme, 176.
 "Symbols Antiques, Les," O'Dagree, 177.
 Symbols, Navajo, 148; Oriental, 156; Chinese, 157; Egyptian, 158, 159; Indian, 159; Japanese, 160; Persian, 160; Turkish, 160; miscellaneous, 161, 162.
 "Symbols of Early Christian Art," Twining, 178.
 Syria, 168.
 Syrian Christian weavers, 71.
 Syrian rugs, 111.

INDEX

T

- Tabor, Mrs. Sydney Richmond, rug owned by, 56 (plate).
 Tabriez, 168.
 Tabriz, 63, 163, 168, 174.
 Tabriz rugs, 70 and frontispiece (plate).
 Tajura, 169, 174.
 Talim, or working drawing of rug design, 39.
 Tanjore, 166, 174.
 Tapestries synonymous with rugs, 16; introduced into England, 138; introduced into France by Saracens, 141.
 Tarantula design, 43.
 Tawarek tribe, 135.
 Tchechen rugs, 108.
 Teheran rug market, 70, 125; meaning of *Teheran*, 163; spelling, 168, 174.
 Tekké tribe, 98, 103.
 Tekké-Turkoman rugs, 98 (plate), 103.
 "Ten Years' Digging in Egypt," Petrie, 177.
 "Textile Manufactures and Costumes of the People of India, The," Watson, 178.
 Theban fresco represents rug-weavers, 17.
 Thibetan goat's hair, 30.
 "Things Chinese," Ball, 175.
 Thompson, —, 178.
 "Through Asia," Hedin, 176.
 "Through Persia on a Side Saddle," Sykes, 178.
 Tien-tsin, 165, 174, 184.
 Tokio, 167, 174.
 Tortoise, symbolism of, 157, 160.
 Tourcoing, 169, 174.
 Tourists, Cairo rug-market for, 52.
 Tournay, 169, 174.
 Trade in Ghiordes rugs, 75.
 Transcaucasia, 71, 105, 168.
 Trebizond, 169, 174.
 "Tree and Serpent Worship," Ferguson, 176.
 Tree of Health design, symbolism of, 160.
 Tree of Life design on Persian rugs, 17, 65; on Kashgar rugs, 101; on Ghiordes rugs, 122; symbolism of, 157, 160. *See* frontispiece plate and 124 (plate).
 Triangle design, 43.
 Tribute paid in insects for dye purposes, 45.
 Tripoli, 169, 174.
 Tshi, 183, 185.
 Tsi-nan, 165, 174.
 Tsing-chau, 165, 174.
 Tsing-ning, 165, 174.
 Tsun-hua rugs, 115.
 Tuareg rugs, 135.
 Tuareg tribe, 135.
 Tunis rugs, 135, 169.
 Turfani wool, 30.
 Turkey in Asia, place-names, 168.
 Turkish coat of arms, 160.
 Turkish knotting, 34, 35.
 Turkish loom and weavers, 24 (plate).
 Turkish Ministry of Commerce, 73.
 Turkish rug factories, 24.
 Turkish rugs, 24, 71-83, 183, 184; of silk, 125.
 Turkish symbolism, of green, 48; of crescent and star, 160.
 Turkish wool, 30.
 Turkoman rugs, 98-104, 125.
 Turks in Anatolia, 118.
 Turmeric, 44.
 Turtle, symbolism of, 162.
 Twining, —, 178.
 Tyrian purple (*see* Phoenician purple), 45, 47.
 Tzitzis rugs, 108.

INDEX

U

- Umballa, 166.
 "Unbeaten tracks in Japan," Bishop, 175.
 United States, Oriental weavers in, 21; power looms in, 24; import duties, 56; Persian rugs to supply trade of, 57; Sultanabad rugs imported into, 70; law against importation of jail-made goods, 90; rug-weaving in, 143-149.
 Urfa, 71, 169, 174.
 Ushak, 169.

V

- Value of square foot of best Persian rug, 28; of rug trade to Persia, 55, 56; of Persian rugs in the Orient, 70; of silk rugs, 125.
 Vandergoten, Cornelius, 186.
 Vase rugs, 182.
 Vámbéry, Arminius, 178.
 Van Dyke, John Charles, 178, 183.
 Vegetable dyes, 44, 46, 139.
 Vegetable fibre in Mirzapur rugs, 92.
 Verulam, Earl of, rug owned by, 138 (plate).
 Victoria and Albert Museum, 186, 187.
 Vienna, rug-weaving at, 136.
 Violet in old rugs, 80.
 Viper, symbolism of, 159.
 Volk, Mrs. Douglas, 145.
 "Vorderasiatische Knüpftteppiche," Bode, 175.

W

- Wagner collection, 182.
 Wake, Charles Staniland, 178.
 Warangal, 166, 174.
 Warangul rugs, 93.
 Washing to subdue colors, 77; to overcome odor, 95.
 Watson, Dr. Forbes, 178.
 Weale, John, 178.
 Weavers, skilled Oriental, 20; correct color sense of, 20; demonstrating their craft in United States, 21; women and girls, 26; men and boys, 26; sedentary, 26, 27; nomadic, 26; men naturally unsuited, 27; profits of, 27, 28, 82; time consumed, 28; wages and advance payment, 28; fare, 29; work underground, 29; superstitions, 29; skill of, 32, 33; use of dyes by, 44; Egyptian, 51; women of all classes, 55; Persian, in employ of factories, 57; use small patterns, 75; Indian, 88; Japanese, 116; Greek, 132; Flemish, 138; Navajo, 148.
 Weaving, legends of invention of, 16; in ancient Egypt, 22; method of Oriental, 22; in India, 23.
 Westroff, Hodder M., 178.
 Westwood, —, 178.
 Wheel, symbolism of, 159, 162.
 Wheeler, Mrs. A. D., rug owned by, 126 (plate).
 Wheeler, Samuel Green, 178.
 White, symbolism of, 47, 48; use of cotton for, 76.
 Wilkinson, Sir J. Gardner, quoted, 17, 178.
 William of Germany, Emperor, his rug collection, 77.
 Williams, S. Wells, 178.
 Wilson, Rev. Samuel Graham, M.A., 178.
 Wilton, power looms in, 24.
 Wings, symbolism of, 162.
 Winkleman, Johann Joachim, 178.
 Wolf, symbolism of, 162.
 Wool, preparation of, 27, 30, 32; where produced, 30; handling, 32; quality, 32; not produced in India, 88.
 Worcester, power looms in, 24.
 Worsted used in rug-weaving, 23.
 Writers, ancient, allude to rugs, 18.
 Wyatt, M. Digby, 178.

INDEX

X

Xanthin (yellow coloring matter), 44.

Y

Y-form design, 43.	Yezd rugs, 70; felt rugs, 126; meaning of <i>Yezd</i> , 163; spelling, 168, 174.
Yak's hair, 30.	Yomud rugs, 100, 103, 104.
Yangi-hissar, 165.	Yomud tribe, 98, 103.
Yapraks (Ouchak rugs), 81, 83.	Young stags, symbolism of, 157.
Yarkand, 165, 174.	Yuruk rugs, 83.
Yarkand rugs, 103.	
Yellow-dyes, how produced, 44, 45; symbolism of, 47; used by Turkomans, 98.	

Z

Zarand, 168, 174.	Zigzag design, 43, 159.
Zeli, 169.	Zileh, 169, 174.
Zerffi, G. C., 178.	Zilleh, 169.
Zerni, 165, 174.	

THE END



NOV 83

